



west virginia department of environmental protection

Office of Oil and Gas
601 57th Street SE
Charleston, WV 25304
(304) 926-0450
(304) 926-0452 fax

Earl Ray Tomblin, Governor
Randy C. Huffman, Cabinet Secretary
www.dep.wv.gov

June 02, 2016

WELL WORK PERMIT

Horizontal 6A Well


This permit, API Well Number: 47-8510277, issued to EQT PRODUCTION COMPANY, is evidence of permission granted to perform the specified well work at the location described on the attached pages and located on the attached plat, subject to the provisions of Chapter 22 of the West Virginia Code of 1931, as amended, and all rules and regulations promulgated thereunder, and to all conditions and provisions outlined in the pages attached hereto.

Notification shall be given by the operator to the Oil and Gas Inspector at least 24 hours prior to the construction of roads, locations, and/or pits for any permitted work. In addition, the well operator shall notify the same inspector 24 hours before any actual well work is commenced and prior to running and cementing casing. Spills or emergency discharges must be promptly reported by the operator to 1-800-642-3074 and to the Oil and Gas inspector.

Please be advised that form WR-35, Well Operators Report of Well Work is to be submitted to this office within 90 days completion of permitted well work, as should form WR-34 Discharge Monitoring Report within 30 days of discharge of pits, if applicable. Failure to abide by all statutory and regulatory provisions governing all duties and operations hereunder may result in suspension or revocation of this permit and, in addition, may result in civil and/or criminal penalties being imposed upon the operators.

In addition to the applicable requirements of this permit, and the statutes and rules governing oil and gas activity in WV, this permit may contain specific conditions which must be followed. Permit conditions are attached to this cover letter.

Per 35CSR-4-5.2.g this permit will expire in two (2) years from the issue date unless permitted well work is commenced. If there are any questions, please feel free to contact me at (304) 926-0499 ext. 1654.


James Martin
Chief

Operator's Well No: 513380

Farm Name: TASCHLER, BRIAN ET AL

API Well Number: 47-8510277

Permit Type: Horizontal 6A Well

Date Issued: 06/02/2016

Promoting a healthy environment.

PERMIT CONDITIONS **4708510277**

West Virginia Code § 22-6A-8(d) allows the Office of Oil and Gas to place specific conditions upon this permit. Permit conditions have the same effect as law. Failure to adhere to the specified permit conditions may result in enforcement action.

CONDITIONS

1. This proposed activity may require permit coverage from the United States Army Corps of Engineers (USACE). Through this permit, you are hereby being advised to consult with USACE regarding this proposed activity.
2. If the operator encounters an unanticipated void, or an anticipated void at an unanticipated depth, the operator shall notify the inspector within 24 hours. Modifications to the casing program may be necessary to comply with W. Va. Code § 22-6A-5a (12), which requires drilling to a minimum depth of thirty feet below the bottom of the void, and installing a minimum of twenty (20) feet of casing. Under no circumstance should the operator drill more than one hundred (100) feet below the bottom of the void or install less than twenty (20) feet of casing below the bottom of the void.
3. When compacting fills, each lift before compaction shall not be more than 12 inches in height, and the moisture content of the fill material shall be within limits as determined by the Standard Proctor Density test of the actual soils used in specific engineered fill, ASTM D698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort, to achieve 95 % compaction of the optimum density. Each lift shall be tested for compaction, with a minimum of two tests per lift per acre of fill. All test results shall be maintained on site and available for review.
4. Operator shall install signage per § 22-6A-8g (6) (B) at all source water locations included in their approved water management plan within 24 hours of water management plan activation.
5. Oil and gas water supply wells will be registered with the Office of Oil and Gas and all such wells will be constructed and plugged in accordance with the standards of the Bureau for Public Health set forth in its Legislative rule entitled *Water Well Regulations*, 64 C.S.R. 19. Operator is to contact the Bureau of Public Health regarding permit requirements. In lieu of plugging, the operator may transfer the well to the surface owner upon agreement of the parties. All drinking water wells within fifteen hundred feet of the water supply well shall be flow tested by the operator upon request of the drinking well owner prior to operating the water supply well.
6. Pursuant to the requirements pertaining to the sampling of domestic water supply wells/springs the operator shall, no later than thirty (30) days after receipt of analytical data provide a written copy to the Chief and any of the users who may have requested such analyses.
7. If any explosion or other accident causing loss of life or serious personal injury occurs in or about a well or well work on a well, the well operator or its contractor shall give notice, stating the particulars of the explosion or accident, to the oil and gas inspector and the Chief, within 24 hours of said accident.
8. During the casing and cementing process, in the event cement does not return to the surface, the oil and gas inspector shall be notified within 24 hours.
9. The operator shall provide to the Office of Oil and Gas the dates of each of the following within 30 days of their occurrence: completion of construction of the well pad, commencement of drilling, cessation of drilling, completion of any other permitted well work, and completion of the well. Such notice shall be provided by sending an email to DEPOOGNotify@wv.gov.

4708510277

WW - 6B
(4/15)

API NO. 47 - 085 - 0
 OPERATOR WELL NO. 513380
 Well Pad Name: AUB54

CASING AND TUBING PROGRAM

18)

TYPE	Size (in)	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: for Drilling	INTERVALS: Left in Well	CEMENT: Fill-up (Cu.Ft.)
Conductor	20	New	A-500	78.6	40	40	60 C.T.S.
Fresh Water	13 3/8	New	J-55	54.5	474	474	472 C.T.S.
Coal	-	-	-	-	-	-	
Intermediate	9 5/8	New	A-500	40	2,475	2,475	981 C.T.S.
Production	5 1/2	New	P-110	20	10,115	10,115	See Note 1
Tubing	2 3/8		J-55	4.6			May not be run, if run will be set 100' less than TD
Liners							

MDC
2/19/16

TYPE	Size (in)	Wellbore Diameter (in)	Wall Thickness (in)	Burst Pressure (psi)	Anticipated Max. Internal Pressure (psi)	Cement Type	Cement Yield (cu. ft./k)
Conductor	20	26	0.375	-	18	Construction	1.18
Fresh Water	13 3/8	17 1/2	0.38	2,730	2,184	* See Note 2	1.19
Coal							
Intermediate	9 5/8	12 3/8	0.395	3,950	3,160	* See Note 2	1.19
Production	5 1/2	8 1/2	0.361	12,640	10,112	-	1.07/1.86
Tubing							
Liners							

Packers

Kind:	N/A		
Sizes:	N/A		
Depths Set:	N/A		

Note 1: EQT plans to bring the TOC on the production casing cement job 500' above the top producing zone.

Note 2: Reference Variance 2014-17. (Attached)

WW - 6B
(10/14)

4708510277

API NO. 47 - 085 - 0
OPERATOR WELL NO. 513380
Well Pad Name: AUB54

19) Describe proposed well work, including the drilling and plugging back of any pilot hole:

Drill and complete a new horizontal well in the Marcellus formation. The vertical drill to go down to an approximate depth of 6756'.
Tag the Onondaga not more than 100', run logs, then plug back with a solid cement plug to approximately 5055'.
Kick off and drill curve. Drill lateral in the Marcellus. Cement casing.

20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:

Hydraulic fracturing is completed in accordance with state regulations using water recycled from previously fractured wells and obtained from freshwater sources. This water is mixed with sand and a small percentage (less than 0.3%) of chemicals (including 15% Hydrochloric acid, gelling agent, gel breaker, friction reducer, biocide, and scale inhibitor), referred to in the industry as a "slickwater" completion. Maximum anticipated internal casing pressure is expected to average approximately 8500 psi, maximum anticipated treating rates are expected to average approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximately 200,000 barrels of water per stage. Sand sizes vary from 100 mesh to 20/40 mesh. Average approximately 200,000 pounds of sand per stage.

MAC
2/19/16

21) Total area to be disturbed, including roads, stockpile area, pits, etc, (acres): 19.1

22) Area to be disturbed for well pad only, less access road (acres): 14.3

23) Describe centralizer placement for each casing string.
• Surface: Bow spring centralizers - One at the shoe and one spaced every 500'.
• Intermediate: Bow spring centralizers - One cent at the shoe and one spaced every 500'.
• Production: One spaced every joint from production casing shoe to KOP

24) Describe all cement additives associated with each cement type. **Surface (Type 1 Cement):** 0-3% Calcium Chloride
Used to speed the setting of cement slurries.
0.25% flake. Loss Circulation Material (LCM) is used to combat the loss of the cement slurry to a thief zone.
Intermediate (Type 1 Cement): 0-3% Calcium Chloride. Salt is used in shallow, low temperature formations to speed the setting of cement slurries. 0.25% flake. Loss Circulation Material (LCM) is used to combat the loss of whole drilling fluid or cement slurry (not filtrate) to a thief zone.

Production:
Lead (Type H Cement): 0.2% CD-20 (dispersant makes cement easier to mix). .15% SuperFL-300 (fluid loss/lengthens thickening time)
.15% SEC-10 (fluid loss) 50:50 POZ (extender)
Tail (Type H Cement): 0.2% Super CR-1 (Retarder). Lengthens thickening time. .3% Super FL-200 (fluid loss)
.2% SEC-10 (Fluid loss). .2% SuperFL-350 (fluid loss) Reduces amount of water lost to formation.
60 % Calcium Carbonate. Acid solubility.

25) Proposed borehole conditioning procedures. **Surface:** Circulate hole clean (Approximately 30-45 minutes) rotating & reciprocating one full joint until cuttings diminish at surface. When cuttings returning to surface diminish, continue to circulate an additional 5 minutes. A constant rate of higher than expected cuttings volume likely indicates washouts that will not clean up.

Intermediate: Circulate hole clean (Approximately 30-45 minutes) rotating & reciprocating one full joint until cuttings diminish at surface. When cuttings returning to surface diminish, continue to circulate an additional 5 minutes. If foam drilling, to enhance hole cleaning use a soap sweep or increase injection rate & foam concentration.

Production: Pump marker sweep with nut plug to determine actual hole washout. Calculate a gauge holes bottoms up volume. Perform a cleanup cycle by pumping 3-5 bottoms up or until the shakers are clean. Check volume of cuttings coming across the shakers every 15 minutes.

RECEIVED
Office of Oil and Gas
FEB 23 2016


*Note: Attach additional sheets as needed.

4708510277

4708510277

Top of Cement	Depth (feet)	Casing	Depth (feet)	Grade	WT (ppf)	WT (ppf)	Type	Flow Size	Method
Top of Cement	40	0.375	A-500	78.6	20	Conductor	20	20	Displacement
Surface	474	0.39	J-55	54.5	13.39	Surface	13.39	17 1/2	Displacement
Surface	2425	0.295	A-500	40	0.58	Intermediate	0.58	12.39	Displacement
500' above top Producing Zone	10115	0.304				Production Casing	5 1/2	20	Displacement

MAG
2/19/16



Well 513380 (AUBS4M2)
ECGT Production
Auburn
Ridgely
West Virginia
Account 182
Vertical Section 3121

RECEIVED
Department of Oil and Gas
FEB 23 2016
Department of Environmental Protection

Proposed Well Work:
Drill and complete a new horizontal well in the Marcellus formation.
Drill the wellbore to an approximate depth of 6750'.
Tag the Casing to not more than 100' from top, then plug back with a solid cement plug to approximately 5055'.
Kick off and drill curve. Drill lateral in the Marcellus. Cement casing.



Office of Oil and Gas

West Virginia Department of
Environmental Protection
Office of Oil & Gas
601 57th Street SE
Charleston, WV 25304-2345

85-10277

DEP Office Use only	
Date Received by Oil & Gas:	1/14/16
Assigned Impoundment ID #:	085-WPA-DDD29

4708510277

Permit Associated Impoundment / Pit Registration

Instruction: This form is to be used to register impoundments or waste pits, greater than 5,000 bbls, that are associated with a WVDEP, Office of Oil and Gas, well drilling permit. An **associated impoundment or pit** means it has been designed and included in the well drilling permit application, will follow the reclamation time frame of well work permit, and will be approved in conjunction with the well work permit. An impoundment ID number will be assigned by WVDEP, Office of Oil and Gas, to all impoundments and pits. This impoundment ID number will be sent to the applicant following receipt of this form by WVDEP. Please reference this impoundment ID number with all future correspondence and reference to this impoundment. Conditions as described in W.Va. State Rule §35-4-21 will be followed as it relates to impoundments and pits.

Section 1 – Operator and Facility Information

Operator Name:	EQT Production Company		
Operator ID:	306686		
Name of Structure*	AUB 54 Flowback Pit		
Address: Street	115 Professional Place P.O. Box 280		
City:	Bridgeport	State:	WV Zip: 26330
Contact Name:	Ron Furby	Contact Title:	Senior Mgr. Water Operations
Contact Phone:	304-543-9849	Contact Email:	rfurby@eqt.com

Section 2 – Engineering / Design Contractor Information

Design will be contracted	<input type="checkbox"/>	Designed in-house	<input checked="" type="checkbox"/>
Company Name:	Smith Land Surveying, Inc.		
Address: Street	12 Vanhorn Dr., P.O. Box 150		
City:	Glenville	State:	WV Zip: 26351
Contact Name:	Wes Wayne	Contact Title:	Design Coordinator
Contact Phone:	304-462-5634	Contact Email:	wwayne@slssurveys.com
Certifying Professional Engineer:	Kip Hall		
Professional Engineer Registration Number:	WV PE # 15176		

RECEIVED
Office of Oil and Gas

JAN 14 2016



Office of Oil and Gas

Section 3 - Impoundment / Pit InformationType of Structure. Check one of two choices below: Freshwater Impoundment Waste PitNote: Any waste in a pit will make it a waste pit.Name of Structure* AUB 54 Flowback PitCounty: Ritchie District: UnionUSGS 7.5' Quad Map Name: Auburn

Farm Name: _____

Pad Name: AUB 54Surface Owner Name: Brian Taschler et alPhysical Description of Location: The AUB 54 site is located on the ridge south of Co. Rt. 7/18, approximately 1.13 miles southeast of the intersection of Co. Rt. 7/18 and Co. Rt. 7/13.

(Note: Give general location, example: 2 miles south of Smalltown, WV on Rt. 22, left on Buffalo Creek)

Watershed (nearest perennial): Unnamed Tributary of Left Fork of Bone CreekDistance (Drainage Distance) to nearest perennial stream: 815'

Location Coordinates (NAD83, Decimal Degrees (xx.xxxx, -xx.xxxx))

Latitude: 39.114875 Longitude (Use negative sign): -80.853486UTM Coordinates : 4329534.728 M E 512666.367 M N

Access Road Coordinates (junction of state highway access)

Latitude: 39.124631 Longitude (Use negative sign): -80.847288UTM Coordinates : 4330618.268 M E 513200.373 M N

Approximate Dimensions

Length: 289' Width: 236' Height: 19'

Note: If irregularly shaped, give approximate dimensions of long axis.

Total Capacity – Provide all units of measure below:

Barrels: 74,269.0 Gallons: 3,119,296.4 Acre-Feet: 9.573

Capacity with 2' Freeboard – Provide all units of measure below:

Barrels: 60,214 Gallons: 2,528,984.0 Acre-Feet: 7.67

Incised volume:

Barrels: 23,959.9 Gallons: 1,006,314.2 Acre-Feet: 3.088

Net impounded volume: (Total volume less incised volume.)

Barrels: 50,309.1 Gallons: 2,112,982.2 Acre-Feet: 6.485Anticipated Construction Start Date (estimation, non-binding): To Be DeterminedNote: No construction may begin on **Associated** impoundment until WVDEP issues the drilling permit. At least 7 calendar days prior to confirmed construction start date, notify the Office of Oil & Gas **Office of Oil and Gas** inspector of construction start date. Use form IMP-2, "Notification of Impoundment / Pit Construction."

JAN 14 2016



Office of Oil and Gas

Section 4 - Associated Well Numbers and API Numbers. List associated well numbers and API number. API numbers may not be assigned at time of registering this impoundment, if so list as pending.

Well Number(s):	API Number(s) – If issued:
WV513380 (H2)	
WV513381 (H3)	
WV513382 (H4)	
WV513383 (H5)	
WV513384 (H6)	
WV514041 (H8)	

4703510277

Section 5 - Required Information Checklist To Register Permit Associated Impoundments or Pits. Include the following information and plans with application.

- Engineered Construction Plans, certified by WV Registered P.E.
- Erosion and Sediment Control Plan, certified by WV Registered P.E.
- Reclamation Plan, certified by WV Registered P.E.

Section 6 – Dam Standard Qualifying Evaluation

- The design of this structure has been evaluated by the applicant to determine it does NOT qualify to be defined as a dam, under W.Va Rule §47-34. If the design of this structure qualifies it to be defined as a dam, all permits regulating dams will be required prior to registering the structure with the Office of Oil and Gas. The dam standard, from the WVDEP, Div. Of Water and Waste, is available for review at: <http://www.dep.wv.gov/WWE/ee/ds/Pages/default.aspx>

Section 7 –Comments – Provide any additional comments concerning this project

RECEIVED
Office of Oil and Gas

JAN 14 2016



Office of Oil and Gas

Section 8 - Application Certification

I hereby certify that the information listed above is true and accurate. I understand that this pit/impoundment is to be constructed only in a location appropriate for the storage of water, including wastewater, and will be constructed in accordance with plans designed and certified by a West Virginia registered professional engineer. I further recognize that all required plans have been submitted to the Office of Oil and Gas. I understand that after construction, and prior to any fluid being placed in the pit/impoundment, it shall be inspected by a West Virginia registered professional engineer to ensure compliance with the certified design and construction plan, and that the professional engineer shall certify that this structure was constructed in accordance with design and construction plans. I understand that such certification shall be in writing to the Chief and that no fluids may be placed in the pit/impoundment until the certification has been filed with the chief. I agree that this pit/impoundment shall be constructed, maintained, operated and closed in accordance with all applicable laws and rules, including the requirements of W. Va. Code R § 35-4-2 .

4708510277


Name: Victoria Roark
Title: Permitting Supervisor
Signature: [Signature]

Taken, subscribed and sworn to before me this, 8 Day of Jan 20 16

Notary Public: [Signature]

My commission expires: 8-24-22

Notary Seal:



Section 9. Submittal Instructions

Submit original paper copy of application to:
West Virginia Department of Environmental Protection
Office of Oil and Gas
Impoundment Registration
601 57th Street, SE
Charleston WV 25304

Email PDF file format of this application and all related engineering Plans to :
Depimpoundments@wv.gov

* Name of Structure: Please give the pit or impoundment a unique name, and use the name consistently when referring to this structure. They are often given the same name as the pad, with a modifier to identify freshwater or flowback water. If more than one pit or impoundment is associated with this pad, use modifier to identify these as well, such as #1, #2, etc. Examples: ABC Pad Freshwater Impoundment, ABC Pad Flowback Pit #1, ABC Pad Flowback Pit #2.

Office of Oil and Gas

JAN 14 2016

OFFICIAL SEAL
STATE OF WEST VIRGINIA
NOTARY PUBLIC
Pamela Sykes
EQT Production
PO Box 280
Burdett, WV 26030
My Commission Expires 04/24/2025





Office of Oil and Gas

West Virginia Department of
Environmental Protection
Office of Oil & Gas
601 57th Street SE
Charleston, WV 25304-2345

85-10278

DEP Office Use only	
Date Received by Oil & Gas:	1/14/16
Assigned Impoundment ID #:	085-WPA-00029

Permit Associated Impoundment / Pit Registration

Instruction: This form is to be used to register impoundments or waste pits, greater than 5,000 bbls, that are associated with a WVDEP, Office of Oil and Gas, well drilling permit. An **associated impoundment or pit** means it has been designed and included in the well drilling permit application, will follow the reclamation time frame of well work permit, and will be approved in conjunction with the well work permit. An impoundment ID number will be assigned by WVDEP, Office of Oil and Gas, to all impoundments and pits. This impoundment ID number will be sent to the applicant following receipt of this form by WVDEP. Please reference this impoundment ID number with all future correspondence and reference to this impoundment. Conditions as described in W.Va. State Rule §35-4-21 will be followed as it relates to impoundments and pits.

Section 1 – Operator and Facility Information

Operator Name:	EQT Production Company		
Operator ID:	306686		
Name of Structure*	AUB 54 Flowback Pit		
Address: Street	115 Professional Place P.O. Box 280		
City:	Bridgeport	State:	WV Zip: 26330
Contact Name:	Ron Furby	Contact Title:	Senior Mgr. Water Operations
Contact Phone:	304-543-9849	Contact Email:	rfurby@eqt.com

Section 2 – Engineering / Design Contractor Information

Design will be contracted	<input type="checkbox"/>	Designed in-house	<input checked="" type="checkbox"/>
Company Name:	Smith Land Surveying, Inc.		
Address: Street	12 Vanhorn Dr., P.O. Box 150		
City:	Glenville	State:	WV Zip: 26351
Contact Name:	Wes Wayne	Contact Title:	Design Coordinator
Contact Phone:	304-462-5634	Contact Email:	wwayne@slssurveys.com
Certifying Professional Engineer:	Kip Hall		
Professional Engineer Registration Number:	WV PE # 15176		

RECEIVED
Office of Oil and Gas

JAN 14 2016

Page 1 of 4
WV Department of
Environmental Protection



Office of Oil and Gas

Section 3 - Impoundment / Pit Information

4708510277

Type of Structure. Check one of two choices below: Freshwater Impoundment Waste PitNote: Any waste in a pit will make it a waste pit.Name of Structure* AUB 54 Flowback PitCounty: Ritchie District: UnionUSGS 7.5' Quad Map Name: Auburn

Farm Name: _____

Pad Name: AUB 54Surface Owner Name: Brian Taschler et alPhysical Description of Location: The AUB 54 site is located on the ridge south of Co. Rt. 7/18, approximately 1.13 miles southeast of the intersection of Co. Rt. 7/18 and Co. Rt. 7/13.

(Note: Give general location, example: 2 miles south of Smalltown, WV on Rt. 22, left on Buffalo Creek)

Watershed (nearest perennial): Unnamed Tributary of Left Fork of Bone CreekDistance (Drainage Distance) to nearest perennial stream: 815'

Location Coordinates (NAD83, Decimal Degrees (xx.xxxx, -xx.xxxx))

Latitude: 39.114875 Longitude (Use negative sign): -80.853486UTM Coordinates : 4329534.728 M E 512666.367 M N

Access Road Coordinates (junction of state highway access)

Latitude: 39.124631 Longitude (Use negative sign): -80.847288UTM Coordinates : 4330618.268 M E 513200.373 M N

Approximate Dimensions

Length: 289' Width: 236' Height: 19'

Note: If irregularly shaped, give approximate dimensions of long axis.

Total Capacity – Provide all units of measure below:

Barrels: 74,269.0 Gallons: 3,119,296.4 Acre-Feet: 9.573

Capacity with 2' Freeboard – Provide all units of measure below:

Barrels: 60,214 Gallons: 2,528,984.0 Acre-Feet: 7.67

Incised volume:

Barrels: 23,959.9 Gallons: 1,006,314.2 Acre-Feet: 3.088

Net impounded volume: (Total volume less incised volume.)

Barrels: 50,309.1 Gallons: 2,112,982.2 Acre-Feet: 6.485Anticipated Construction Start Date (estimation, non-binding): To Be DeterminedNote: No construction may begin on **Associated** impoundment until WVDEP issues the drilling permit. At least 7 calendar days prior to confirmed construction start date, notify the Office of Oil & Gas, and the local Oil and Gas inspector of construction start date. Use form IMP-2, "Notification of Impoundment / Pit Construction."

JAN 14 2016

 RECEIVED
 Office of Oil and Gas
 WV Department of
 Environmental Protection
 Page 2 of 4



Office of Oil and Gas

Section 4 - Associated Well Numbers and API Numbers. List associated well numbers and API number. API numbers may not be assigned at time of registering this impoundment, if so list as pending.

Well Number(s):	API Number(s) – If issued:
WW513380 (H2)	
WW513381 (H3)	
WW513382 (H4)	
WW513383 (H5)	
WW513384 (H6)	
WW514041 (H8)	

4700510277

Section 5 - Required Information Checklist To Register Permit Associated Impoundments or Pits. Include the following information and plans with application.

- Engineered Construction Plans, certified by WV Registered P.E.
- Erosion and Sediment Control Plan, certified by WV Registered P.E.
- Reclamation Plan, certified by WV Registered P.E.

Section 6 – Dam Standard Qualifying Evaluation

- The design of this structure has been evaluated by the applicant to determine it does NOT qualify to be defined as a dam, under W.Va Rule §47-34. If the design of this structure qualifies it to be defined as a dam, all permits regulating dams will be required prior to registering the structure with the Office of Oil and Gas. The dam standard, from the WVDEP, Div. Of Water and Waste, is available for review at: <http://www.dep.wv.gov/WWE/ee/ds/Pages/default.aspx>

Section 7 –Comments – Provide any additional comments concerning this project

RECEIVED
Office of Oil and Gas

JAN 14 2016

RECEIVED
Office of Department of
Environmental Protection
JAN 14 2016



4708510277

Section 8 - Application Certification

I hereby certify that the information listed above is true and accurate. I understand that this pit/impoundment is to be constructed only in a location appropriate for the storage of water, including wastewater, and will be constructed in accordance with plans designed and certified by a West Virginia registered professional engineer. I further recognize that all required plans have been submitted to the Office of Oil and Gas. I understand that after construction, and prior to any fluid being placed in the pit/impoundment, it shall be inspected by a West Virginia registered professional engineer to ensure compliance with the certified design and construction plan, and that the professional engineer shall certify that this structure was constructed in accordance with design and construction plans. I understand that such certification shall be in writing to the Chief and that no fluids may be placed in the pit/impoundment until the certification has been filed with the chief. I agree that this pit/impoundment shall be constructed, maintained, operated and closed in accordance with all applicable laws and rules, including the requirements of W. Va. Code R § 35-4-2.

Name: Victoria Roark
Title: Permitting Supervisor
Signature: [Handwritten Signature]

Taken, subscribed and sworn to before me this, 8 Day of Jan 20 16

Notary Public: [Handwritten Signature]

My commission expires: 8-24-22

Notary Seal:

Section 9. Submittal Instructions

Submit original paper copy of application to:
West Virginia Department of Environmental Protection
Office of Oil and Gas
Impoundment Registration
601 57th Street, SE
Charleston WV 25304

Email PDF file format of this application and all related engineering Plans to :
Depimpoundments@wv.gov

* Name of Structure: Please give the pit or impoundment a unique name, and use the name consistently when referring to this structure. They are often given the same name as the pad, with a modifier to identify freshwater or flowback water. If more than one pit or impoundment is associated with this pad, use modifier to identify these as well, such as #1, #2, etc. Examples: ABC Pad Freshwater Impoundment, ABC Pad Flowback Pit #1, ABC Pad Flowback Pit #2.



Office of Oil and Gas

West Virginia Department of
Environmental Protection
Office of Oil & Gas
601 57th Street SE
Charleston, WV 25304-2345

85-10279

DEP Office Use only	
Date Received by Oil & Gas:	1/14/16
Assigned Impoundment ID #:	085-WPA-00029

4708510277

Permit Associated Impoundment / Pit Registration

Instruction: This form is to be used to register impoundments or waste pits, greater than 5,000 bbls, that are associated with a WVDEP, Office of Oil and Gas, well drilling permit. An **associated impoundment or pit** means it has been designed and included in the well drilling permit application, will follow the reclamation time frame of well work permit, and will be approved in conjunction with the well work permit. An impoundment ID number will be assigned by WVDEP, Office of Oil and Gas, to all impoundments and pits. This impoundment ID number will be sent to the applicant following receipt of this form by WVDEP. Please reference this impoundment ID number with all future correspondence and reference to this impoundment. Conditions as described in W.Va. State Rule §35-4-21 will be followed as it relates to impoundments and pits.

Section 1 – Operator and Facility Information

Operator Name:	EQT Production Company		
Operator ID:	306686		
Name of Structure*	AUB 54 Flowback Pit		
Address: Street	115 Professional Place P.O. Box 280		
City:	Bridgeport	State:	WV Zip: 26330
Contact Name:	Ron Furby	Contact Title:	Senior Mgr. Water Operations
Contact Phone:	304-543-9849	Contact Email:	rfurby@eqt.com

Section 2 – Engineering / Design Contractor Information

Design will be contracted	<input type="checkbox"/>	Designed in-house	<input checked="" type="checkbox"/>
Company Name:	Smith Land Surveying, Inc.		
Address: Street	12 Vanhorn Dr., P.O. Box 150		
City:	Glenville	State:	WV Zip: 26351
Contact Name:	Wes Wayne	Contact Title:	Design Coordinator
Contact Phone:	304-462-5634	Contact Email:	wwayne@slssurveys.com
Certifying Professional Engineer:	Kip Hall		
Professional Engineer Registration Number:	WV PE # 15176		

RECEIVED
Office of Oil and Gas

JAN 14 2016



Office of Oil and Gas

4708510277

Section 3 - Impoundment / Pit InformationType of Structure. Check one of two choices below: Freshwater Impoundment Waste PitNote: Any waste in a pit will make it a waste pit.Name of Structure* AUB 54 Flowback PitCounty: Ritchie District: UnionUSGS 7.5' Quad Map Name: Auburn

Farm Name: _____

Pad Name: AUB 54Surface Owner Name: Brian Taschler et alPhysical Description of Location: The AUB 54 site is located on the ridge south of Co. Rt. 7/18, approximately 1.13 miles southeast of the intersection of Co. Rt. 7/18 and Co. Rt. 7/13.

(Note: Give general location, example: 2 miles south of Smalltown, WV on Rt. 22, left on Buffalo Creek)

Watershed (nearest perennial): Unnamed Tributary of Left Fork of Bone CreekDistance (Drainage Distance) to nearest perennial stream: 815'

Location Coordinates (NAD83, Decimal Degrees (xx.xxxx, -xx.xxxx))

Latitude: 39.114875 Longitude (Use negative sign): -80.853486UTM Coordinates : 4329534.728 M E 512666.367 M N

Access Road Coordinates (junction of state highway access)

Latitude: 39.124631 Longitude (Use negative sign): -80.847288UTM Coordinates : 4330618.268 M E 513200.373 M N

Approximate Dimensions

Length: 289' Width: 236' Height: 19'

Note: If irregularly shaped, give approximate dimensions of long axis.

Total Capacity – Provide all units of measure below:

Barrels: 74,269.0 Gallons: 3,119,296.4 Acre-Feet: 9.573

Capacity with 2' Freeboard – Provide all units of measure below:

Barrels: 60,214 Gallons: 2,528,984.0 Acre-Feet: 7.67

Incised volume:

Barrels: 23,959.9 Gallons: 1,006,314.2 Acre-Feet: 3.088

Net impounded volume: (Total volume less incised volume.)

Barrels: 50,309.1 Gallons: 2,112,982.2 Acre-Feet: 6.485Anticipated Construction Start Date (estimation, non-binding): To Be DeterminedNote: No construction may begin on **Associated** impoundment until WVDEP issues the **Permit**. At least 7 calendar days prior to confirmed construction start date, notify the Office of Oil & Gas, and the local Oil and Gas inspector of construction start date. Use form IMP-2, "Notification of Impoundment / Pit Construction."

JAN 14 2016



Office of Oil and Gas

Section 4 - Associated Well Numbers and API Numbers. List associated well numbers and API number. API numbers may not be assigned at time of registering this impoundment, if so list as pending.

Well Number(s):	API Number(s) – If issued:
WV513380 (H2)	
WV513381 (H3)	
WV513382 (H4)	
WV513383 (H5)	
WV513384 (H6)	
WV514041 (H8)	

4703510277

Section 5 - Required Information Checklist To Register Permit Associated Impoundments or Pits. Include the following information and plans with application.

- Engineered Construction Plans, certified by WV Registered P.E.
- Erosion and Sediment Control Plan, certified by WV Registered P.E.
- Reclamation Plan, certified by WV Registered P.E.

Section 6 – Dam Standard Qualifying Evaluation

- The design of this structure has been evaluated by the applicant to determine it does NOT qualify to be defined as a dam, under W.Va Rule §47-34. If the design of this structure qualifies it to be defined as a dam, all permits regulating dams will be required prior to registering the structure with the Office of Oil and Gas. The dam standard, from the WVDEP, Div. Of Water and Waste, is available for review at: <http://www.dep.wv.gov/WWE/ee/ds/Pages/default.aspx>

Section 7 –Comments – Provide any additional comments concerning this project

RECEIVED
Office of Oil and Gas

JAN 14 2016



4708510277

Section 8 - Application Certification

I hereby certify that the information listed above is true and accurate. I understand that this pit/impoundment is to be constructed only in a location appropriate for the storage of water, including wastewater, and will be constructed in accordance with plans designed and certified by a West Virginia registered professional engineer. I further recognize that all required plans have been submitted to the Office of Oil and Gas. I understand that after construction, and prior to any fluid being placed in the pit/impoundment, it shall be inspected by a West Virginia registered professional engineer to ensure compliance with the certified design and construction plan, and that the professional engineer shall certify that this structure was constructed in accordance with design and construction plans. I understand that such certification shall be in writing to the Chief and that no fluids may be placed in the pit/impoundment until the certification has been filed with the chief. I agree that this pit/impoundment shall be constructed, maintained, operated and closed in accordance with all applicable laws and rules, including the requirements of W. Va. Code R § 35-4-2 .


Name: Victoria Roark
Title: Permitting Supervisor
Signature: [Handwritten Signature]

Taken, subscribed and sworn to before me this, 8 Day of Jan 20 16

Notary Public: [Handwritten Signature]

My commission expires: 8-24-22

Notary Seal:



Section 9. Submittal Instructions

Submit original paper copy of application to:
West Virginia Department of Environmental Protection
Office of Oil and Gas
Impoundment Registration
601 57th Street, SE
Charleston WV 25304

Email PDF file format of this application and all related engineering Plans to :
Depimpoundments@wv.gov

* Name of Structure: Please give the pit or impoundment a unique name, and use the name consistently when referring to this structure. They are often given the same name as the pad, with a modifier to identify freshwater or flowback water. If more than one pit or impoundment is associated with this pad, use modifier to identify these as well, such as #1, #2, etc. Examples: ABC Pad Freshwater Impoundment, ABC Pad Flowback Pit #1, ABC Pad Flowback Pit #2.

JAN 14 2016



Office of Oil and Gas

West Virginia Department of
Environmental Protection
Office of Oil & Gas
601 57th Street SE
Charleston, WV 25304-2345

85-10280

DEP Office Use only	
Date Received by Oil & Gas:	1/14/16
Assigned Impoundment ID #:	085-WPA-00029

4708510277

Permit Associated Impoundment / Pit Registration

Instruction: This form is to be used to register impoundments or waste pits, greater than 5,000 bbls, that are associated with a WVDEP, Office of Oil and Gas, well drilling permit. An **associated impoundment or pit** means it has been designed and included in the well drilling permit application, will follow the reclamation time frame of well work permit, and will be approved in conjunction with the well work permit. An impoundment ID number will be assigned by WVDEP, Office of Oil and Gas, to all impoundments and pits. This impoundment ID number will be sent to the applicant following receipt of this form by WVDEP. Please reference this impoundment ID number with all future correspondence and reference to this impoundment. Conditions as described in W.Va. State Rule §35-4-21 will be followed as it relates to impoundments and pits.

Section 1 – Operator and Facility Information

Operator Name:	EQT Production Company		
Operator ID:	306686		
Name of Structure*	AUB 54 Flowback Pit		
Address: Street	115 Professional Place P.O. Box 280		
City:	Bridgeport	State:	WV Zip: 26330
Contact Name:	Ron Furby	Contact Title:	Senior Mgr. Water Operations
Contact Phone:	304-543-9849	Contact Email:	rfurby@eqt.com

Section 2 – Engineering / Design Contractor Information

Design will be contracted	<input type="checkbox"/>	Designed in-house	<input checked="" type="checkbox"/>
Company Name:	Smith Land Surveying, Inc.		
Address: Street	12 Vanhorn Dr., P.O. Box 150		
City:	Glenville	State:	WV Zip: 26351
Contact Name:	Wes Wayne	Contact Title:	Design Coordinator
Contact Phone:	304-462-5634	Contact Email:	wwayne@slssurveys.com
Certifying Professional Engineer:	Kip Hall		
Professional Engineer Registration Number:	WV PE # 15176		



Office of Oil and Gas

Section 3 - Impoundment / Pit Information

Type of Structure. <u>Check one of two choices below:</u>		
<input type="checkbox"/> Freshwater Impoundment	<input checked="" type="checkbox"/> Waste Pit	470851027
Note: <u>Any</u> waste in a pit will make it a waste pit.		
Name of Structure* <u>AUB 54 Flowback Pit</u>		
County: <u>Ritchie</u>	District: <u>Union</u>	
USGS 7.5' Quad Map Name: <u>Auburn</u>		
Farm Name: _____		
Pad Name: <u>AUB 54</u>		
Surface Owner Name: <u>Brian Taschler et al</u>		
Physical Description of Location: <u>The AUB 54 site is located on the ridge south of Co. Rt. 7/18, approximately 1.13 miles southeast of the intersection of Co. Rt. 7/18 and Co. Rt. 7/13.</u>		
(Note: Give general location, example: 2 miles south of Smalltown, WV on Rt. 22, left on Buffalo Creek)		
Watershed (nearest perennial): <u>Unnamed Tributary of Left Fork of Bone Creek</u>		
Distance (Drainage Distance) to nearest perennial stream: <u>815'</u>		
Location Coordinates (NAD83, Decimal Degrees (xx.xxxx, -xx.xxxx))		
Latitude: <u>39.114875</u>	Longitude (Use negative sign): <u>-80.853486</u>	
UTM Coordinates: <u>4329534.728 M</u>	<u>E</u>	<u>512666.367 M</u> <u>N</u>
Access Road Coordinates (junction of state highway access)		
Latitude: <u>39.124631</u>	Longitude (Use negative sign): <u>-80.847288</u>	
UTM Coordinates: <u>4330618.268 M</u>	<u>E</u>	<u>513200.373 M</u> <u>N</u>
Approximate Dimensions		
Length: <u>289'</u>	Width: <u>236'</u>	Height: <u>19'</u>
Note: If irregularly shaped, give approximate dimensions of long axis.		
Total Capacity – Provide all units of measure below:		
Barrels: <u>74,269.0</u>	Gallons: <u>3,119,296.4</u>	Acre-Feet: <u>9.573</u>
Capacity with 2' Freeboard – Provide all units of measure below:		
Barrels: <u>60,214</u>	Gallons: <u>2,528,984.0</u>	Acre-Feet: <u>7.67</u>
Incised volume:		
Barrels: <u>23,959.9</u>	Gallons: <u>1,006,314.2</u>	Acre-Feet: <u>3.088</u>
Net impounded volume: (Total volume less incised volume.)		
Barrels: <u>50,309.1</u>	Gallons: <u>2,112,982.2</u>	Acre-Feet: <u>6.485</u>
Anticipated Construction Start Date (estimation, non-binding): <u>To Be Determined</u>		
Note: No construction may begin on Associated impoundment until WVDEP issues the drilling permit. At least 7 calendar days prior to confirmed construction start date, notify the Office of Oil & Gas, and the local Oil and Gas inspector of construction start date. Use form IMP-2, "Notification of Impoundment / Pit Construction."		



Office of Oil and Gas

Section 4 - Associated Well Numbers and API Numbers. List associated well numbers and API number. API numbers may not be assigned at time of registering this impoundment, if so list as pending.

Well Number(s):	API Number(s) – If issued:
WW513380 (H2)	
WW513381 (H3)	
WW513382 (H4)	
WW513383 (H5)	
WW513384 (H6)	
WW514041 (H8)	

470 8510277

Section 5 - Required Information Checklist To Register Permit Associated Impoundments or Pits. Include the following information and plans with application.

- Engineered Construction Plans, certified by WV Registered P.E.
- Erosion and Sediment Control Plan, certified by WV Registered P.E.
- Reclamation Plan, certified by WV Registered P.E.

Section 6 – Dam Standard Qualifying Evaluation

- The design of this structure has been evaluated by the applicant to determine it does NOT qualify to be defined as a dam, under W.Va Rule §47-34. If the design of this structure qualifies it to be defined as a dam, all permits regulating dams will be required prior to registering the structure with the Office of Oil and Gas. The dam standard, from the WVDEP, Div. Of Water and Waste, is available for review at: <http://www.dep.wv.gov/WWE/ee/ds/Pages/default.aspx>

Section 7 –Comments – Provide any additional comments concerning this project



Office of Oil and Gas

4708510277

Section 8 - Application Certification

I hereby certify that the information listed above is true and accurate. I understand that this pit/impoundment is to be constructed only in a location appropriate for the storage of water, including wastewater, and will be constructed in accordance with plans designed and certified by a West Virginia registered professional engineer. I further recognize that all required plans have been submitted to the Office of Oil and Gas. I understand that after construction, and prior to any fluid being placed in the pit/impoundment, it shall be inspected by a West Virginia registered professional engineer to ensure compliance with the certified design and construction plan, and that the professional engineer shall certify that this structure was constructed in accordance with design and construction plans. I understand that such certification shall be in writing to the Chief and that no fluids may be placed in the pit/impoundment until the certification has been filed with the chief. I agree that this pit/impoundment shall be constructed, maintained, operated and closed in accordance with all applicable laws and rules, including the requirements of W. Va. Code R § 35-4-2 .

Name: Victoria Roark
Title: Permitting Supervisor
Signature: [Signature]

Taken, subscribed and sworn to before me this, 8 Day of Jan 20 16

Notary Public: [Signature]

My commission expires: 8-24-22

Notary Seal:

Section 9. Submittal Instructions

Submit original paper copy of application to:
West Virginia Department of Environmental Protection
Office of Oil and Gas
Impoundment Registration
601 57th Street, SE
Charleston WV 25304

Email PDF file format of this application and all related engineering Plans to :
Depimpoundments@wv.gov

* Name of Structure: Please give the pit or impoundment a unique name, and use the name consistently when referring to this structure. They are often given the same name as the pad, with a modifier to identify freshwater or flowback water. If more than one pit or impoundment is associated with this pad, use modifier to identify these as well, such as #1, #2, etc. Examples: ABC Pad Freshwater Impoundment, ABC Pad Flowback Pit #1, ABC Pad Flowback Pit #2.



west virginia department of environmental protection

Office of Oil and Gas
601 57th Street, SE
Charleston, WV 25304
(304) 926-0450
(304) 926-0452 fax

Earl Ray Tomblin, Governor
Randy C. Huffman, Cabinet Secretary
dep.wv.gov

March 18, 2014

Nabors Completion & Production Services Company
1380 Route 286 Hwy E #121
Indiana PA 15701

4708510277

Re: Cement Variance Request

Dear Sir or Madam,

This agency is approving a variance request for the cement blend listed below to be used on surface and coal protection strings for the drilling of oil and gas wells in the state of West Virginia. The variance cannot be used without requesting its use on a permit application and approval by this agency:

- Type 1 (2% Calcium Chloride-Accelerator, 0.25% Super Flake-Lost Circulation, 5.2% Water, 94% Type "1" Cement)

If you have any questions regarding this matter feel free to contact me at 304-926-0499, ext. 1653.

Sincerely,

James Peterson
Environmental Resources Specialist / Permitting

Promoting a healthy environment.

RECEIVED
Office of Oil and Gas

JAN 14 2016

WV Department of
Environmental Protection



west virginia department of environmental protection

Office of Oil and Gas
601 57th Street, SE
Charleston, WV 25304
(304) 926-0450
(304) 926-0452 fax

Earl Ray Tomblin, Governor
Randy C. Huffman, Cabinet Secretary
dep.wv.gov

**BEFORE THE OFFICE OF OIL AND GAS
DEPARTMENT OF ENVIRONMENTAL PROTECTION
STATE OF WEST VIRGINIA**

**IN THE MATTER OF A VARIANCE FROM)
REGULATION 35 CSR § 4-11.4/11.5/14.1)
AND 35 CSR § 8-9.2.h. 4/5/6/8 OF THE)
THE OPERATIONAL)
REGULATIONS OF CEMENTING OIL)
AND GAS WELLS)**

ORDER NO. 2014 - 17

4708510277

REPORT OF THE OFFICE

Nabors Completion & Production Services Co. requests approval of a different cement blend for use in cementing surface and coal protection casing of oil and gas wells.

FINDINGS OF FACT

- 1.) Nabors Completion & Production Services Co. proposes the following cement blend:
 - 2% Calcium Chloride (Accelerator)
 - 0.25 % Super Flake (Lost Circulation)
 - 94% Type "1" Cement
 - 5.20 % Water
- 2.) Laboratory testing results indicate that the blend listed in Fact No.1 will achieve a 500 psi compressive strength within 6 hours and a 2,435 psi compressive strength within 24 hours.

Promoting a healthy environment.

RECEIVED
Office of Oil and Gas

JAN 14 2016

WV Department of
Environmental Protection

CONCLUSIONS OF LAW

Pursuant to Articles 6 and 6A, Chapter 22 of the Code of West Virginia, the Office of Oil and Gas has jurisdiction over the subject matter embraced in said notice, and the persons interested therein, and jurisdiction to promulgate the hereinafter prescribed Order.

Pursuant to 35 CSR § 4-11.5 and 35 CSR § 8-9.2.h.8 the Chief of the Office of Oil and Gas may approve different cement blends upon the well operator providing satisfactory proof that different cement types are adequate.

ORDER

It is ordered that Nabors Completion & Production Services Co. may use the cement blend listed in Findings of Fact No.1 for the cementing of surface and coal protection casing of oil and gas wells in the State as may be requested by oil and gas operators. The waiting time on the cement blend shall be 8 hours. The cement blend shall be mixed in strict accordance with the specifications for each blend and weight measurements made on-site to assure the cement slurries meet the minimum weight specifications. A sample shall be collected and, if after 8 hours the cement is not set up, additional time will be required. Nabors Completion & Production Services Co. shall keep a record of cement blend jobs in which the cement blend approved under this order is to be used and made available to the Office of Oil and Gas upon request.

Dated this, the 18th day of March, 2014.

IN THE NAME OF THE STATE OF WEST VIRGINIA

OFFICE OF OIL AND GAS
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OF THE STATE OF WEST VIRGINIA



James Martin, Chief
Office of Oil and Gas

RECEIVED
Office of Oil and Gas

JAN 14 2016

WV Department of
Environmental Protection



August 3, 2015

Mr. Gene Smith
West Virginia Department of Environmental Protection
Office of Oil and Gas
601 57th Street SE
Charleston, WV 25304

44-02510277

Re: Casing Plan on Wells (AUB54 513880, 513882, 513884, 514041)

Dear Mr. Smith,

EQT is requesting the 13-3/8" surface casing be set at 474' KB, 150' deepest freshwater show. We will set the 9-5/8" intermediate string at 2475' KB, 50' below the base of the Weir formation.

If you have any questions, please do not hesitate to contact me at (304) 848-0076.

Sincerely,

A handwritten signature in blue ink, appearing to read 'Vicki Roark'.

Vicki Roark
Permitting Supervisor

Enc.

RECEIVED
Office of Oil and Gas

JAN 14 2016

WW-9
(2/15)

Page 1 of 2
API No. 47 - 085 - 0
Operator's Well No. 513380

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS
Fluids/Cuttings Disposal & Reclamation Plan

4708510277

Operator Name EQT Production Company OP Code 306686
Watershed (HUC10) Left Fork & Brushy Fork of Bone Creek Quadrangle Auburn 7.5'
Do you anticipate using more than 5,000 bbls of water to complete the proposed well work? Yes No

Will a pit be used? Yes: No:

If so please describe anticipated pit waste: flowback water & residual solids

Will a synthetic liner be used in the pit? Yes No If so, what ml.? 60

Proposed Disposal Method For Treated Pit Wastes:

- Land Application
- Underground Injection (UIC Permit Number 0014, 8462, 4037)
- Reuse (at API Number Various)
- Off Site Disposal (Supply form WW-9 for disposal location)
- Other (Explain _____)

MDC
2/19/16

Will closed loop system be used? Yes. The closed loop system will remove drill cuttings from the drilling fluid. The drill cuttings are then prepared for transportation to an off-site disposal facility.

Drilling medium anticipated for this well (vertical and horizontal)? Air, freshwater, oil based, etc.

Air is used to drill the top-hole sections of the wellbore (surface, intermediate, and pilot). Water based mud may be necessary depending on hole conditions to stabilize and drill the intermediate section. The pilot hole, curve, and lateral sections will be drilled with either air, water based mud, or oil based mud.

- If oil based, what type? Synthetic, petroleum, etc Synthetic mud

Additives to be used in drilling medium? Air - biodegradable oil lubricant, detergent, defoaming, water. Water based mud - Barite, viscosifier, alkalinity control, lime, filtration control, defloculates, biodegradable oil lubricant, defoaming, walnut shell, salt, x-cide, carbonates.
Oil based mud - synthetic base oil, emulsifier, salt, lime, viscosifier, alkalinity control, filtration control, defloculates, biodegradable oil lubricant, defoaming, carbonates.

Drill cuttings disposal method? Leave in pit, landfill, removed offsite, etc. Landfill

- If left in pit and plan to solidify what medium will be used? (Cement, Lime, sawdust) n/a

- Landfill or offsite name/permit number? See Attached List

Permittee shall provide written notice to the Office of Oil and Gas of any load of drill cuttings or associated waste rejected at any West Virginia solid waste facility. The notice shall be provided within 24 hours of rejection and the permittee shall also disclose where it was properly disposed.

I certify that I understand and agree to the terms and conditions of the GENERAL WATER POLLUTION PERMIT issued on August 1, 2005, by the Office of Oil and Gas of the West Virginia Department of Environmental Protection. I understand that the provisions of the permit are enforceable by law. Violations of any term or condition of the general permit and/or other applicable law or regulation can lead to enforcement action.

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this application form and all attachments thereto and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine or imprisonment.

Company Official Signature [Signature]
Company Official (Typed Name) Victoria J. Roark
Company Official Title Permitting Supervisor

RECEIVED
Office of Oil and Gas
FEB 23 2016

Subscribed and sworn before me this 8 day of Jan

My commission expires 8-24-22



WV Department of Environmental Protection
OFFICIAL SEAL
STATE OF WEST VIRGINIA
NOTARY PUBLIC
Pamela Sykes
EQT Production
PO Box 280
Bridgeport, WV 26330
My Commission Expires Aug. 24, 2022

Form WW-9

Operator's Well No. 513300

Proposed Revegetation Treatment: Acres Disturbed 19.1 Prevegetation pH 6.3

Lime 3 Tons/acre or to correct to pH 6.5

Fertilize type Granular 10-20-20

Fertilizer Amount 1/3 lbs/acre (500 lbs minimum)

Mulch 2 Tons/acre

Seed Mixtures

Temporary		Permanent	
Seed Type	lbs/acre	Seed Type	lbs/acre
KY-31	40	Orchard Grass	15
Alsike Clover	5	Alsike Clover	5
Annual Rye	15		

4708510277

Attach:
Drawing(s) of road, location, pit and proposed area for land application.

Photocopied section of involved 7.5' topographic sheet.


Plan Approved by: Michael Goff

Comments: Re-seed & mulch any disturbed areas per WVDEP regulations. Maintain & upgrade E-n-s as necessary.

Title: Oil & Gas Inspector Date: 2/19/16

Field Reviewed? () Yes () No

RECEIVED
Office of Oil and Gas
FEB 23 2016
WV Department of
Environmental Protection



NOTE: SEE SITE PLAN AUB54 FOR COMPLETE CONSTRUCTION & EROSION & SEDIMENT CONTROL DETAILS.

RECEIVED
Office of Oil and Gas
FEB 23 2016
89

WV Department of
Environmental Protection

Professional Energy Consultants
A MEMBER OF BERKLAND SURVEYING, INC.



SLS
SURVEYORS
ENGINEERS
ENVIRONMENTAL
PROJECT MGMT.
WWW.SLSURVEYING.COM

DRAWN BY: K.D.W. FILE NO: 7580 DATE: 12-18-15 CADD FILE: 7580AUB54WELLS.PLA

TOPO SECTIONS OF AUBURN & OXFORD 7.5' TOPO QUADRANGLES

SHEET 1 OF 2
SCALE: 1"=500'




MDC
2/19/14

Professional Energy Consultants A Division of S&S Energy Services, Inc.	S&S ENGINEERS SURVEYORS	DATE: 12-18-15 FILE NO. 7590	DRAWN BY: K.D.W.
PROJECT MOUNT.	WWW.S&S-ENR.COM	CADD FILE: 7590-0001.rvt	

TOPO SECTION OF AUBURN 7.5
TOPO QUADRANGLE

NOTE: SEE SITE PLAN
AUB54 FOR COMPLETE
CONSTRUCTION &
EROSION & SEDIMENT
CONTROL DETAILS.




H2-013280
 H4-013282
 H4-013284
 H2-014001
 H2-013281
 H2-013283

Not To Scale

Detail Sketch for Proposed AUB54 Wells

SCALE: 1"=500'
 SHEET 2 OF 2
 0' 500' 1000'

NOTE: SEE SITE PLAN
AUB54 FOR COMPLETE
CONSTRUCTION &
EROSION & SEDIMENT
CONTROL DETAILS.



HALL LEASE AUB54 WELLS

Form WW-9

page of

4708510277

EQT Production Water plan
Offsite disposals for Marcellus wells

CWS TRUCKING INC.

P.O. Box 391
Williamstown, WV 26187
740-516-3586
Noble County/Noble Township
Permit # 3390

BROAD STREET ENERGY LLC

37 West Broad Street
Suite 1100
Columbus, Ohio 43215
740-516-5381
Washington County/Belpre Twp.
Permit # 8462

LAD LIQUID ASSETS DISPOSAL INC.

226 Rankin Road
Washington, PA 15301
724-350-2760
724-222-6080
724-229-7034 fax
Ohio County/Wheeling
Permit # USEPA WV 0014

TRIAD ENERGY

P.O. Box 430
Reno, OH 45773
740-516-6021 Well
740-374-2940 Reno Office Jennifer
Nobel County/Jackson Township
Permit # 4037

TRI COUNTY WASTE WATER MANAGEMENT, INC.

1487 Toms Run Road
Holbrook, PA 15341
724-627-7178 Plant
724-499-5647 Office
Greene County/Waynesburg
Permit # TC-1009

KING EXCAVATING CO.

Advanced Waste Services
101 River Park Drive
New Castle, Pa. 16101
Facility Permit# PAR000029132

WV 00010277

Waste Management - Meadowfill Landfill

Rt. 2, Box 68 Dawson Drive
Bridgeport, WV 26330
304-326-6027
Permit #SWF-1032-98
Approval #100785WV

Waste Management - Northwestern Landfill

512 E. Dry Road
Parkersburg, WV 26104
304-428-0602
Permit #SWF-1025 WV-0109400
Approval #100833WV

RECEIVED
Office of Oil and Gas

JAN 14 2016

WV Department of
Environmental Protection



Where energy meets innovation.™

Site Specific Safety Plan

EQT AUB 54 Pad

Auburn Quadrant

Ritchie County, WV

For Wells: 513380 ✓ 513382 513384 514041 _____

4708510277

Date Prepared:

February 3, 2016

EQT Production

Michael Hoff
WV Oil and Gas Inspector

Title

Title


Date

Date

2-12-14

2/19/16 FEB 23 2016

RECEIVED
Office of Oil and Gas
WV Department of
Environmental Protection




4708510277

Where energy meets innovation.



Azimuths to Grid North
True North: 0.86°
Magnetic North: -7.52°

Magnetic Field
Strength: 52051.1snT
Dip Angle: 66.60°
Date: 9/15/2015
Model: IGRF2015



4708510277

RECEIVED
Office of Oil and Gas

FEB 23 2016

WV Department of
Environmental Protection

MDG
2/19/16



WELL INFORMATION AND POTENTIAL WATER WELL SAMPLE DATA SHEET

OPERATOR: EQ1 Production Company

LEASE NAME AND NUMBER: AUB-54 Well Pad

4708510277

COMMENTS

The initial field and/or mapping review of the area surrounding the proposed well site revealed the below listed surface owner(s) that were potentially utilizing groundwater (potable) for Human Consumption or other purposes within 2500' of the proposed well site. (For location of each site see attached area map.)

INDIVIDUAL CONTACTED OR NOTIFIED

Site: 1 Spacing 2460' Owner/Occupant: Ralph Blankenship
Address: 2051 Brushy fork Rd. Auburn, WV 26325 Ph: (304)-349-2487
Field Contact Date: 05/26/2015 Located: Yes Date Located: 05/26/2015 Source: Water Well
If No, declined by who Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Par 10 *Note Mr. Blankenship has contacted and requested additional water wells be tested at this location.
Lat: 39.122968
Long: 80.855184

Site: 2 Spacing 2260' Owner/Occupant: Ralph Blankenship
Address: 2051 Brushy fork Rd. Auburn, WV 26325 Ph: (304)-349-2487
Field Contact Date: 05/26/2015 Located: Yes Date Located: 05/26/2015 Source: Water Well
If No, declined by who Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Par. 10
Lat: 39.122092
Long: 80.855927

Site: 3 Spacing 2335' Owner/Occupant: Louis Kopf
Address: 2220 Brushy fork Rd. Auburn, WV 26325 Ph: (304)-349-4507
Field Contact Date: 06/09/2015 Located: Yes Date Located: 06/09/2015 Source: Water Well
If No, declined by who Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Par. 11 *NOTE* Mr Kopf has informed there are two water wells at this location.
Lat: 39.122294
Long: 80.852869

Site: 4 Spacing 2245' Owner/Occupant: Patrick Lacey
Address: 2186 Brushy fork Rd. Auburn, WV 26325 Ph: (304)-349-4507
Field Contact Date: 06/09/2015 Located: Yes Date Located: 06/09/2015 Source: Water Well
If No, declined by who Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Par. 11.1 *NOTE* Mr. Kopf was present while the Lacey's water well was located.
Lat: 39.122110
Long: 80.853336

RECEIVED Office of Oil and Gas

JAN 14 2016

WV Department of Environmental Protection

Site: 5 Spacing _____ Owner/Occupant: Gregory Adams
Address: 109 south marion Ave. Hopewell, VA 23860 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Parcel 16
No response to certified letter as of 06/30/2015

Site: 6 Spacing _____ Owner/Occupant: Adams family Heirs
Address: 120 Marlboro Dr. McMurray, PA 15317 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Parcels 16 and 16.1
No response to certified letter as of 06/30/2015

Site: 7 Spacing _____ Owner/Occupant: Brad and Dean Faschler
Address: 795 Towamensing Rd. Lehighton, PA 18235 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Parcel 17
No response to certified letter as of 06/30/2015

Site: 8 Spacing _____ Owner/Occupant: Piny Holdings, INC.
Address: P.O. Box 5026 Fairmont, WV 26555 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Parcel 17.1
No response to certified letter as of 06/30/2015

4708510277

Site: 9 Spacing _____ Owner/Occupant: Donald and Tina Murphy
Address: 289 Riddle Hill Rd. Auburn, WV 26325 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 37, Par. 1
No response to certified letter as of 06/30/2015

Site: 10 Spacing _____ Owner/Occupant: Allen Merriman
Address: 925 Riddle Hill Rd. Auburn, WV 26325 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 37, Par. 4
No response to certified letter as of 06/30/2015

NOTE Mr. Merriman has phoned in and does not have any water sources within 200

RECEIVED
Office of Oil and Gas

JAN 14 2016

Site: 11 Spacing _____ Owner/Occupant: Kiedaisch and Summers Enterprises
Address: P.O. Box 254 Harrisville, WV 26362 Ph: _____
Field Contact Date: NA Located: No Date Located: NA Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Par. 12
No response to certified letter as of 06/30/2015

Site: 12 Spacing _____ Owner/Occupant: Ralph Blankenship
Address: 2051 Brushy fork Rd. Auburn, WV 26325 Ph: (304)-349-2487
Field Contact Date: 05/26/2015 Located: Yes Date Located: 7/29/2015 Source: Water Well
If No, declined by who _____ Letter/Notice Date: 1st 05/26/2015 2nd 06/09/2015 Certified (3rd) 06/17/2015
Comments: Tax Map 32, Par. 10
Lat: 39.122391
Long: 80.836668

Site: _____ Spacing _____ Owner/Occupant _____
Address: _____ Ph: _____
Field Contact Date: _____ Located: _____ Date Located: _____ Source: _____
If No, declined by who _____ Letter/Notice Date: 1st _____ 2nd _____ Certified (3rd) _____
Comments: _____

Site: _____ Spacing _____ Owner/Occupant _____
Address: _____ Ph: _____
Field Contact Date: _____ Located: _____ Date Located: _____ Source: _____
If No, declined by who _____ Letter/Notice Date: 1st _____ 2nd _____ Certified (3rd) _____
Comments: _____

Site: _____ Spacing _____ Owner/Occupant _____
Address: _____ Ph: _____
Field Contact Date: _____ Located: _____ Date Located: _____ Source: _____
If No, declined by who _____ Letter/Notice Date: 1st _____ 2nd _____ Certified (3rd) _____
Comments: _____


Site: _____ Spacing _____ Owner/Occupant _____
Address: _____ Ph: _____
Field Contact Date: _____ Located: _____ Date Located: _____ Source: _____
If No, declined by who _____ Letter/Notice Date: 1st _____ 2nd _____ Certified (3rd) _____
Comments: _____

4708510277

RECEIVED
Office of Oil and Gas

JAN 14 2016

WATER SOURCE LOCATIONS FOR HALL LEASE AUB54 WELLS



SCALE: 1-INCH=1000-FEET



RECEIVED
Office of Oil and Gas
LEGEND
● WATER WELL

Professional Energy Consultants
A DIVISION OF DEWY AND GLENN, INC.
SLS
SURVEYORS
ENGINEERS
ENVIRONMENTAL
FREQUENCY MONITORING

DRAWN BY: K.D.W. FILE NO: 7580 DATE: 08/12/15 CADD FILE: 7580AUB54WEL.dwg


TOPO SECTION OF:
AUBURN, WV 7.5' QUAD

DISTRICT	COUNTY	TAX MAP-PARCEL NO.
UNION	RITCHIE	32-17

OPERATOR:
EQT PRODUCTION COMPANY
115 PROFESSIONAL PLACE
P.O. BOX 280
BRIDGEPORT, WV 26330

RECEIVED
JAN 14 2016
Environmental Protection

EQT PRODUCTION COMPANY - HALL LEASE
208 ACRES± - WELL NO. WV 513380



WELL TIES		
ID	BEARING	DISTANCE
L1	S 36°46' E	2728.71'
L2	S 12°50' E	2998.79'

BUILD OUT DATA		
ID	BEARING	DISTANCE
L3	N 24°54' W	319.78'
L4	S 12°31' E	154.26'
L5	S 15°10' E	117.53'
L6	S 17°01' E	164.73'


ID	ARC LENGTH	RADIUS	CHORD BEARING	CHORD LENGTH
C1	134.71'	363.65'	N 31°11' W	133.94'
C2	36.00'	16.07'	S 67°31' W	28.92'
C3	131.88'	471.21'	S 04°18' E	131.45'

LATERAL		
ID	BEARING	DISTANCE
L7	S 18°00' E	3020.20'

Professional Energy Consultants
 A DIVISION OF SMITH LAND SURVEYING, INC.

SURVEYORS
ENGINEERS
ENVIRONMENTAL
PROJECT MGMT.
 (304) 482-5634 WWW.SLSURVEYS.COM

(S.P.C. NORTH ZONE) (UTM(M) ZONE 17 NORTH)		
NAD'27 S.P.C.(FT)	N. 227,300.04	E. 1,615,644.54
NAD'27 GEO.	LAT-(N) 39.116115	LONG-(W) 80.854640
NAD'83 UTM (M)	N. 4,329,681.77	E. 512,581.29
LANDING POINT		
NAD'27 S.P.C.(FT)	N. 227,140.99	E. 1,615,536.07
NAD'27 GEO.	LAT-(N) 39.115674	LONG-(W) 80.855014
NAD'83 UTM (M)	N. 4,329,632.77	E. 512,549.06
BOTTOM HOLE		
NAD'27 S.P.C.(FT)	N. 224,268.59	E. 1,616,469.32
NAD'27 GEO.	LAT-(N) 39.107827	LONG-(W) 80.851573
NAD'83 UTM (M)	N. 4,328,762.47	E. 512,847.97



(+) DENOTES LOCATION OF WELL ON UNITED STATES 7.5' TOPOGRAPHIC MAPS.

LEGEND	
LEASE LINE	
SURFACE LINE	
WELL LATERAL	
OFFSET LINE	
TIE LINE	
CREEK	
ROAD	
FENCE LINE	
STATE ROUTE	
COUNTY ROUTE	
PROPOSED WELL	
EXISTING WELL	
PERMITTED WELL	
TAX MAP-PARCEL	00-00

SCALE 1" = 1000'

DATE DECEMBER 17, 2015

REVISED _____, 20____

OPERATORS WELL NO. WV 513380

API WELL NO. 47

STATE 085 COUNTY PERMIT 1027746A

STATE OF WEST VIRGINIA
 DIVISION OF ENVIRONMENTAL PROTECTION
 OFFICE OF OIL AND GAS

WELL OPERATOR EQT PRODUCTION COMPANY DESIGNATED AGENT REX C. RAY

ADDRESS 115 PROFESSIONAL PLACE P.O. BOX 280 BRIDGEPORT, WV 26330

ADDRESS 115 PROFESSIONAL PLACE P.O. BOX 280 BRIDGEPORT, WV 26330

COUNTY NAME _____ PERMIT _____

BRIDGEPORT, WV 26330

BRIDGEPORT, WV 26330

ADDRESS 112 PROFESSIONAL PLACE P.O. BOX 380

ADDRESS 112 PROFESSIONAL PLACE P.O. BOX 380

METT OPERATOR EOT PRODUCTION COMPANY

DESIGNATED AGENT REX C. RAY

NO. STATE COUNTY PERMIT
 METT 47 082 10551104
 OPERATORS METT NO. WV 213380
 REVISED _____ '50 _____
 DATE DECEMBER 11 '05
 SCALE 1" = 1000'



OFFICE OF OIL AND GAS ENVIRONMENTAL PROTECTION DIVISION OF STATE OF WEST VIRGINIA

LAX MAP-LAYOUT 00-00
 PERMITTED METT ○
 EXISTING METT ⊙
 PROPOSED METT ⊕
 COUNTY ROUTE □
 STATE ROUTE □
 FENCE LINE — x — x — x —
 ROAD ————
 CREEK ————
 LE LINE ————
 OFFSET LINE ————
 METT GATEWAY ————
 SURFACE LINE ————
 LEASE LINE ————


LEGEND

UNITED STATES U.S. TOPOGRAPHIC MAPS (+) DENOTES LOCATION OF METT ON




WAD83 UTM (M) N 435938.10 E 215249.80
 WAD83 GEO LAT (N) 38.107133 LONG (W) 80.824213
 WAD83 2°P.C. (FT) N 554252.89 E 258944.19
 BOTTOM HOLE
 WAD83 UTM (M) N 435938.10 E 215249.80
 WAD83 GEO LAT (N) 38.107133 LONG (W) 80.824213
 WAD83 2°P.C. (FT) N 554252.89 E 258944.19
 LANDING POINT
 WAD83 UTM (M) N 435938.10 E 215249.80
 WAD83 GEO LAT (N) 38.107133 LONG (W) 80.824213
 WAD83 2°P.C. (FT) N 554252.89 E 258944.19
 (S.P.C. NORTH ZONE) (UTM(M) ZONE 17 NORTH)

Professional Energy Consultants
 A DIVISION OF SWARTH FUND ENGINEERS, INC.
 ENGINEERS & SURVEYORS
 WWW.SWARTHENGINEERS.COM
 (304) 463-2834



LATITUDE 39°07'30"

EQT PRODUCTION COMPANY - HALL LEASE
208 ACRES± - WELL NO. WV 513380



NOTES ON SURVEY


1. NO WATER WELLS WERE FOUND WITHIN 250' OF PROPOSED GAS WELL. NO AGRICULTURAL BUILDINGS ≥ 2500 SQ. FT. OR DWELLINGS WERE FOUND WITHIN 625' OF THE CENTER OF PROPOSED WELL PAD.

LONGITUDE 80°50'00"
3,237'

(S.P.C. NORTH ZONE) (UTM(M) ZONE 17 NORTH)

NAD'27 S.P.C.(FT)	N. 227,300.04	E. 1,615,644.54
NAD'27 GEO.	LAT-(N) 39.116115	LONG-(W) 80.854640
NAD'83 UTM (M)	N. 4,329,681.77	E. 512,581.29
LANDING POINT		
NAD'27 S.P.C.(FT)	N. 227,140.99	E. 1,615,536.07
NAD'27 GEO.	LAT-(N) 39.115674	LONG-(W) 80.855014
NAD'83 UTM (M)	N. 4,329,632.77	E. 512,549.06
BOTTOM HOLE		
NAD'27 S.P.C.(FT)	N. 224,268.59	E. 1,616,469.32
NAD'27 GEO.	LAT-(N) 39.107827	LONG-(W) 80.851573
NAD'83 UTM (M)	N. 4,328,762.47	E. 512,847.97

REFERENCES



A	BRIAN TASCHLER ET AL	200.665 AC.±	TM 32-17
B	BRIAN TASCHLER ET AL	3.915 AC.±	TM 32-17.2
C	DENSEL R. HALL ET AL	2.41 AC.±	
D	LOUIS J. KOPF	83.776 AC.±	
E	KIEDASCH & SUMMERS ENTERPRISES	40 AC.±	
F	JERRY A. RIDDLE ET AL	130 AC.±	
G	GERALDINE LUSK	82.21 AC.±	
H	BRIAN TASCHLER ET AL	109.81 AC.±	
I	RUSSEL S. & CLARA A. BLIZARD	102.4 AC.±	
J	VIOLET HARDBARGER	81.3 AC.±	
K	BRIAN TASCHLER ET AL	110 AC.±	
L	GREGORY ADAMS ET AL	100 AC.±	

Professional Energy Consultants
 A DIVISION OF SMITH LAND SURVEYING, INC.

SURVEYORS ENGINEERS ENVIRONMENTAL PROJECT MGMT.
 (304) 462-5634 WWW.SLSURVEYS.COM



I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DIVISION OF ENVIRONMENTAL PROTECTION.

P.S. 849 *C. Victor Moyers*

(+) DENOTES LOCATION OF WELL ON UNITED STATES 7.5' TOPOGRAPHIC MAPS.
 DATE DECEMBER 17, 20 15
 REVISED _____, 20 _____
 OPERATORS WELL NO. WV 513380
 API WELL NO. 47 - 085 - 10277 H
 STATE COUNTY PERMIT

MINIMUM DEGREE OF ACCURACY 1 / 2500 FILE NO. 7580P513380R2

HORIZONTAL & VERTICAL CONTROL DETERMINED BY DGPS (SURVEY GRADE TIE TO CORS NETWORK)

STATE OF WEST VIRGINIA
 DIVISION OF ENVIRONMENTAL PROTECTION
 OFFICE OF OIL AND GAS

WELL TYPE: OIL _____ GAS X LIQUID INJECTION _____ WASTE DISPOSAL _____ IF "GAS" PRODUCTION X STORAGE _____ DEEP _____ SHALLOW X

LOCATION: GROUND PROPOSED ELEVATION 1,215' 1,200' WATERSHED LEFT FORK & BRUSHY FORK OF BONE CREEK

DISTRICT _____ UNION _____ COUNTY RITCHIE QUADRANGLE AUBURN 7.5'

SURFACE OWNER BRIAN TASCHLER ET AL ACREAGE 200.665±

ROYALTY OWNER KAYRON HALL ET AL ACREAGE 208±

PROPOSED WORK: DRILL X CONVERT _____ DRILL DEEPER _____ REDRILL _____ FRACTURE OR STIMULATE X PLUG OFF OLD FORMATION _____ PERFORATE NEW FORMATION _____ PLUG AND ABANDON _____ CLEAN OUT AND REPLUG _____ OTHER _____

PHYSICAL CHANGE IN WELL (SPECIFY) _____ TARGET FORMATION MARCELLUS ESTIMATED DEPTH TVD 6,603'


WELL OPERATOR EQT PRODUCTION COMPANY DESIGNATED AGENT REX C. RAY
 ADDRESS 115 PROFESSIONAL PLACE P.O. BOX 280 BRIDGEPORT, WV 26330 ADDRESS 115 PROFESSIONAL PLACE P.O. BOX 280 BRIDGEPORT, WV 26330

COUNTY NAME PERMIT

EQT PRODUCTION COMPANY - HALL LEASE 208 ACRES ± - WELL NO. WV 513380


NOTES ON SURVEY

1. NO WATER WELLS WERE FOUND WITHIN 250' OF PROPOSED GAS WELL. NO AGRICULTURAL BUILDINGS > 2500 SQ. FT. OR DWELLINGS WERE FOUND WITHIN 625' OF THE CENTER OF PROPOSED WELL PAD.



BOTTOM HOLE	
NAD83 UTM (M)	N. 4328,762.47 E. 512,847.93
NAD27 S.P.C. (FT)	N. 524,288.59 E. 1,616,489.35
LANDING POINT	
NAD83 UTM (M)	N. 4329,632.77 E. 512,549.08
NAD27 S.P.C. (FT)	N. 527,140.99 E. 1,616,239.07
NORTH ZONE (UTM(M) ZONE 17 NORTH)	
NAD83 UTM (M)	N. 4329,681.77 E. 512,581.29
NAD27 GEO.	LAT-(N) 39.116112 LONG-(W) 80.824640
NAD27 S.P.C. (FT)	N. 527,300.04 E. 1,616,844.24

REFERENCES



J	100 AC±	GREGORY ADAMS ET AL.	TM 32-17
K	110 AC±	BRIAN TASCHE ET AL.	TM 32-17
L	81.3 AC±	VIOLLET HARDBARGER	
I	102.4 AC±	RUSSELL S & CLARA A BLIZARD	
H	109.81 AC±	BRIAN TASCHE ET AL.	
G	82.21 AC±	GERALDINE LUSK	
F	130 AC±	JERRY A. RIDDLE ET AL.	
E	40 AC±	KIEDASCH & SUMMERS ENTERPRISES	
D	83.76 AC±	LOUIS J. KOPF	
C	241 AC±	DENSEL R. HALL ET AL.	
B	3.912 AC±	BRIAN TASCHE ET AL.	
A	200.662 AC±	BRIAN TASCHE ET AL.	

Professional Energy Consultants
A DIVISION OF SMITH LAND SURVEYING, INC.
SURVEYORS
ENGINEERS
ENVIRONMENTAL
PROJECT MGMT.
WWW.SLSURVEYS.COM (304) 482-9324



I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAN IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DIVISION OF ENVIRONMENTAL PROTECTION.

P. S. 849
C. Victor Moyers

(+) DENOTES LOCATION OF WELL ON UNITED STATES 7.5 TOPOGRAPHIC MAPS.
DATE: DECEMBER 17, 2015
REVISED: _____, 20____
OPERATORS WELL NO.: WV 513380
NO. 47
WELL 082
PERMIT 10277 HW

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

MINIMUM DEGREE OF ACCURACY: 1/2500
FILE NO.: 7580P513380RS
CONTROL DETERMINED BY DGPS (SURVEY GRADE TIE TO CORS NETWORK)
HORIZONTAL & VERTICAL

WELL TYPE: OIL GAS LIQUID WASTE DISPOSAL "GAS" PRODUCTION STORAGE DEEP SHALLOW

PROPOSED WORK: DRILL CONVERT DRILL DEEPER REDRILL FRACTURE OR STIMULATE PLUG OFF OLD FORMATION PERFORM NEW FORMATION PLUG AND ABANDON CLEAN OUT AND REPLUG OTHER

PHYSICAL CHANGE IN WELL (SPECIFY) _____
TARGET FORMATION: MARCELLUS
ESTIMATED DEPTH: TVD @ 603'


SURFACE OWNER: BRIAN TASCHE ET AL.
ROYALTY OWNER: KAYRON HALL ET AL.
ACREAGE: 208±

DISTRICT: _____
UNION: _____
COUNTY: RITCHIE
QUADRANGLE: AUBURN T.S.
WATERSHED: LEFT FORK & BRUSHY FORK OF BONE CREEK
ELEVATION: 1215' ±
PROPOSED GROUND PROPOSED: 1200'

WELL OPERATOR: EQT PRODUCTION COMPANY
ADDRESS: 115 PROFESSIONAL PLACE, P.O. BOX 280, BRIDGEPORT, WV 26330
DESIGNATED AGENT: REX C. RAY

COUNTY NAME: _____
PERMIT: _____

EQT PRODUCTION COMPANY - HALL LEASE
208 ACRES±-WELL NO. WV 513380



Professional Energy Consultants
A DIVISION OF BATH LAND SURVEYING, INC.
SLS
SURVEYORS
ENGINEERS
ENVIRONMENTAL
PROJECT MGMT.
2041 RD 2634 WWW.SLSURVEYS.COM

(S.P.C. NORTH ZONE) (UTM(M) ZONE 17 NORTH)

NAD27 S.P.C.(FT)	N. 227,300.04	E. 1,615,644.54
NAD27 GEO.	LAT-(N) 39.116115	LONG-(W) 80.654640
NAD83 UTM (M)	N. 4,326,681.77	E. 512,581.29

LANDING POINT

NAD27 S.P.C.(FT)	N. 227,140.99	E. 1,615,536.07
NAD27 GEO.	LAT-(N) 39.115674	LONG-(W) 80.655014
NAD83 UTM (M)	N. 4,329,632.77	E. 512,649.06

BOTTOM HOLE

NAD27 S.P.C.(FT)	N. 224,268.59	E. 1,616,469.32
NAD27 GEO.	LAT-(N) 39.107827	LONG-(W) 80.651573
NAD83 UTM (M)	N. 4,326,762.47	E. 512,847.97

VICTOR MOYERS
LICENSED
No. 849
STATE OF WEST VIRGINIA
PROFESSIONAL SURVEYOR
C.V.M. 3-31-16

(+) DENOTES LOCATION OF WELL ON UNITED STATES 7.5' TOPOGRAPHIC MAPS.

LEGEND

- LEASE LINE: - - - - -
- SURFACE LINE: ————
- WELL LATERAL: - - - - -
- OFFSET LINE: ————
- TIE LINE: ————
- CREEK: ~~~~~
- ROAD: - - - - -
- FENCE LINE: ————
- STATE ROUTE: □
- COUNTY ROUTE: □
- PROPOSED WELL: ⊙
- EXISTING WELL: ⊙
- PERMITTED WELL: ⊙
- TAX MAP-PARCEL: 00-00

SCALE 1" = 1000'

DATE DECEMBER 17, 2016

REVISED _____, 20____

OPERATORS WELL NO. WV 513380

API WELL NO. 47-085-10277 HWP

NO. STATE COUNTY PERMIT

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

WELL OPERATOR EQT PRODUCTION COMPANY DESIGNATED AGENT REX C. RAY

ADDRESS 115 PROFESSIONAL PLACE P.O. BOX 280 BRIDGEPORT, WV 26330

ADDRESS 115 PROFESSIONAL PLACE P.O. BOX 280 BRIDGEPORT, WV 26330

COUNTY NAME PERMIT

**INFORMATION SUPPLIED UNDER WEST VIRGINIA CODE
Chapter 22, Article 6A, Section 5(a)(5)
IN LIEU OF FILING LEASE(S) AND OTHER CONTINUING CONTRACT(S)**

Under the oath required to make the verification on page 1 of this Notice and Application, I depose and say that I am the person who signed the Notice and Application for the Applicant, and that -

- (1) the tract of land is the same tract described in this Application, partly or wholly depicted in the accompanying plat, and described in the Construction and Reclamation Plan;
- (2) the parties and recordation data (if recorded) for lease(s) or other continuing contract(s) by which the Applicant claims the right to extract, produce or market the oil or gas are as follows:

Lease Name or Number	Grantor, Lessor, etc.	Grantee, Lessee, etc.	Royalty	Book/Page
107848	Kayron Hall et al (current royalty owner)		Min 1/8 pd	
	William H Hall et ux (original Lessor)	J.M. Basom		LB29/430
	J.M. Basom	James Gartlan		LB57/540
	James Gartlan	The Philadelphia Company of West Virginia		LB57/542
	The Philadelphia Company of West Virginia	Pittsburgh and West Virginia Gas Company		LB55/359
	Pittsburgh and West Virginia Gas Company	Equitable Gas Company		DB126/473
	Equitable Gas Company	Equitrans, Inc		LB201/253
	Equitrans, Inc	Equitrans, L.P.		433/777 recorded in Tyler Co.
	Equitrans, L.P.	Equitable Production-Eastern States Inc		AB234/830
	Equitable Production-Eastern States Inc	Equitable Production Company		CB281/346 rec. in Doddridge Co.
	Equitable Production Company	EQT Production Company		CB281/346 rec. in Doddridge Co.

4708510277

**Acknowledgement of Possible Permitting/Approval
In Addition to the Office of Oil and Gas**

The permit applicant for the proposed well work addressed in this application hereby acknowledges the possibility of the need for permits and/or approvals from local, state, or federal entities in addition to the DEP, Office of Oil and Gas, including but not limited to the following:

- WV Division of Water and Waste Management
- WV Division of Natural Resources WV Division of Highways
- U.S. Army Corps of Engineers
- U.S. Fish and Wildlife Service
- County Floodplain Coordinator

The applicant further acknowledges that any Office of Oil and Gas permit in no way overrides, replaces, or nullifies the need for other permits/approvals that may be necessary and further affirms that all needed permits/approvals should be acquired from the appropriate authority before the affected activity is initiated.

Well Operator: EQT Production Company
 By: 
 Its: Permitting Supervisor

RECEIVED
 Office of Oil and Gas
 Page 1 of JAN 14 2016
 WV Department of
 Environmental Protection



January 13, 2016

Mr. James Martin
West Virginia Department of Environmental Protection
Office of Oil and Gas
601 57th Street SE
Charleston, WV 25304

Re: AUB54 well pad, well number 513380
Union District, Ritchie County

Dear Mr. Martin,

EQT Production Company is submitting an application for a new well work permit for the above well number. Upon information and belief, Operator's lease and/ or other real property rights permit it to conduct drilling operations for the subject well in the location shown on the plat, including under any public roads that the well lateral crosses.

Sincerely,

A handwritten signature in blue ink, appearing to read 'Vicki L'.

Vicki Roark
Permitting Supervisor-WV

4708510277

RECEIVED
Office of Oil and Gas
JAN 14 2016
WV Department of
Environmental Protection

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE CERTIFICATION

Date of Notice Certification: 1-11-16

API No. 47 - 085 - 0
Operator's Well No. 513382
Well Pad Name: AUB54

Notice has been given:

Pursuant to the provisions in West Virginia Code § 22-6A, the Operator has provided the required parties with the Notice Forms listed below for the tract of land as follows:

State:	<u>WV</u>	UTM NAD 83 Easting:	<u>512,581.44</u>
County:	<u>Ritchie</u>	UTM NAD 83 Northing:	<u>4,329,677.20</u>
District:	<u>Union</u>	Public Road Access:	<u>WV RT 47</u>
Quadrangle:	<u>Auburn 7.5'</u>	Generally used farm name:	<u>Brian Taschler et al</u>
Watershed:	<u>Left Fork & Brushy Fork of Bone Creek</u>		

Pursuant to West Virginia Code § 22-6A-7(b), every permit application filed under this section shall be on a form as may be prescribed by the secretary, shall be verified and shall contain the following information: (14) A certification from the operator that (i) it has provided the owners of the surface described in subdivisions (1), (2) and (4), subsection (b), section ten of this article, the information required by subsections (b) and (c), section sixteen of this article; (ii) that the requirement was deemed satisfied as a result of giving the surface owner notice of entry to survey pursuant to subsection (a), section ten of this article six-a; or (iii) the notice requirements of subsection (b), section sixteen of this article were waived in writing by the surface owner; and Pursuant to West Virginia Code § 22-6A-11(b), the applicant shall tender proof of and certify to the secretary that the notice requirements of section ten of this article have been completed by the applicant.

Pursuant to West Virginia Code § 22-6A, the Operator has attached proof to this Notice Certification that the Operator has properly served the required parties with the following:

*PLEASE CHECK ALL THAT APPLY

- NOTICE OF SEISMIC ACTIVITY or NOTICE NOT REQUIRED BECAUSE NO SEISMIC ACTIVITY WAS CONDUCTED
- NOTICE OF ENTRY FOR PLAT SURVEY or NO PLAT SURVEY WAS CONDUCTED
- NOTICE OF INTENT TO DRILL or NOTICE OF ENTRY FOR PLAT SURVEY WAS CONDUCTED OR
- WRITTEN WAIVER BY SURFACE OWNER (PLEASE ATTACH)
- NOTICE OF PLANNED OPERATION
- PUBLIC NOTICE
- NOTICE OF APPLICATION

OOG OFFICE USE ONLY

- RECEIVED/NOT REQUIRED
- RECEIVED
- RECEIVED/NOT REQUIRED
- RECEIVED
- RECEIVED
- RECEIVED

Required Attachments:

The Operator shall attach to this Notice Certification Form all Notice Forms and Certifications of Notice that have been provided to the required parties and/or any associated written waivers. For the Public Notice, the operator shall attach a copy of the Class II Legal Advertisement with publication date verification or the associated Affidavit of Publication. The attached Notice Forms and Certifications of Notice shall serve as proof that the required parties have been noticed as required under West Virginia Code § 22-6A. Pursuant to West Virginia Code § 22-6A-11(b), the Certification of Notice to the person may be made by affidavit of personal service, the return receipt card or other postal receipt for certified mailing.


RECEIVED
Office of Oil and Gas
WV Department of Environmental Protection

Certification of Notice is hereby given:

THEREFORE, I *[Signature]*, have read and understand the notice requirements within West Virginia Code § 22-6A. I certify that as required under West Virginia Code § 22-6A, I have served the attached copies of the Notice Forms, identified above, to the required parties through personal service, by registered mail or by any method of delivery that requires a receipt or signature confirmation. I certify under penalty of law that I have personally examined and am familiar with the information submitted in this Notice Certification and all attachments, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

Well Operator: EQT Production Company
By: Victoria J. Roark
Its: Permitting Supervisor
Telephone: 304-848-0076

Address: P.O. Box 280
Bridgeport, WV 26330
Facsimile: 304-848-0040
Email: vroark@eqt.com



Subscribed and sworn before me this 8 day of Jan, 2016
[Signature] Notary Public
My Commission Expires 8-24-22

Oil and Gas Privacy Notice:

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at deprivacyofficer@wv.gov.

4708510277

My Commission Expires Aug 24, 2025
Bridgetown, WV 26730
PO Box 280
EQJ Production
Pamela Sykes
NOTARY PUBLIC
STATE OF WEST VIRGINIA
OFFICIAL SEAL



WW-6A
(9-13)

API NO. 47 - 085 - 0
OPERATOR WELL NO. 513380
Well Pad Name: AUB54

**STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE OF APPLICATION**

Notice Time Requirement: notice shall be provided no later than the filing date of permit application.

Date of Notice: 1-11-16 Date Permit Application Filed: 1-11-16

Notice of:

- PERMIT FOR ANY WELL WORK CERTIFICATE OF APPROVAL FOR THE CONSTRUCTION OF AN IMPOUNDMENT OR PIT

Delivery method pursuant to West Virginia Code § 22-6A-10(b)

- PERSONAL SERVICE REGISTERED MAIL METHOD OF DELIVERY THAT REQUIRES A RECEIPT OR SIGNATURE CONFIRMATION

Pursuant to W. Va. Code § 22-6A-10(b) no later than the filing date of the application, the applicant for a permit for any well work or for the construction of an impoundment or pit as required by this article shall deliver, by personal service or by registered mail or by any method that requires a receipt or signature confirmation, copies of the application, the erosion and sediment control plan required by section seven of this article to each of the following persons: (1) The owners of record of the surface of the tract on which the well is or is proposed to be located; (2) The surface tract or tracts overlying the oil and gas leasehold being developed by the proposed well work, if the surface tract is to be used for a purpose other than as described in the erosion and sediment control plan submitted pursuant to subsection (c), section seven of this article; (3) The lessee, in the event the tract of land on which the well proposed to be drilled is located [sic] is known to be underlain by one or more coal leases; (4) The record owner of the surface tract or tracts overlying the oil and gas leasehold being developed by the proposed well work, if the surface tract is to be used for a purpose other than as described in section nine of this article; (5) The water purveyor who is known to the applicant to have a water well, spring or water supply source located within one thousand five hundred feet of the well which is used to provide water for consumption by humans or domestic animals; and (6) The operator of any natural gas storage field in which a well work activity is to take place. (c)(1) If more than three tenants in common or other co-owners of interests described in subsection (b) of this article exist in the lands, the applicant may serve the documents required upon the person described in the records of the sheriff required to be maintained by this code. (2) Notwithstanding any provision of this article to the contrary, notice to a lien holder is not required unless the lien holder is the landowner. W. Va. Code R. § 35-8-5.7.a requires, in part, that the operator shall also provide the Well Site Notice to the surface owner and any water purveyor or surface owner subject to notice and water testing as provided in section 15 of this rule.

- Application Notice WSSP Notice E&S Plan Notice Well Plat Notice is hereby provided to:

SURFACE OWNER(s)
Name: _____ See Attached
Address: _____

COAL OWNER OR LESSEE
Name: _____ See Attached
Address: _____

Name: _____
Address: _____

COAL OPERATOR
Name: _____
Address: _____

SURFACE OWNERS(s) (Road and/or Other Disturbance)
Name: _____ See Attached
Address: _____

SURFACE OWNER OF WATER WELL AND/OR WATER PURVEYOR(s)
Name: _____ None
Address: _____

Name: _____
Address: _____

SURFACE OWNER(s) (Impoundments/Pits)
Name: _____ See Attached
Address: _____

OPERATOR OF ANY NATURAL GAS STORAGE FIELD
Name: _____
Address: _____

*Please attach additional forms if necessary

RECEIVED
Office of Oil and Gas
JAN 14 2016
WV Department of Environmental Protection

WW6-A

Surface Owners

Brian Taschler et al
795 Towamensing Rd.
Leighton Pa 18235

4708510277

RECEIVED
Office of Oil and Gas
JAN 14 2016
WV Department of
Environmental Protection

Surface Owners Access/ Other Disturbance

Brian Taschler et al
795 Towamensing Rd.
Leighton Pa 18235



Jerry Riddle
2187 Riddle Hill Rd.
Auburn WV 26325



Betty Jean Nutter
2499 Glendale Road
Cairo WV 26337



Kiedaisch & Summers ENT., LLC
PO Box 254
Harrisville, WV 26362



Louis and Linda Kopf
2220 Brushy Fork Road
Auburn WV 26325



Craig & Amy Williams
6390 Rotherby Circle
Hudson OH 44236



4708510277

Surface Owners Pits or Impoundment

Brian Taschler et al
795 Towamensing Rd.
Leighton Pa 18235



4708510277

RECEIVED
Office of Oil and Gas
JAN 14 2016
WV Department of
Environmental Protection

Coal Owners:

Piney Holdings Inc
PO Box 5026
Fairmont WV 26555

Eric Dean Goff
1661 Hazelgreen Rd
Harrisville WV 26362

Richard L Hall
PO Box 112
Kenna WV 25248

Danny Ray Hall
12052 Sheffield Rd
Jacksonville FL 32226

Michael L Hall
12052 Sheffield Rd
Jacksonville FL 32226

Byron G Hall
4005 Sayre Ave #8
Parkersburg WV 26104

Ella Jean Goff Reed
1661 Hazelgreen Rd
Harrisville WV 26362

Carla R Foster
35 Armin Rd
Tijeras NM 87059

Thomas Guy Hall
12052 Sheffield Rd
Jacksonville FL 32226

Gary Ronald Hall
12052 Sheffield Rd
Jacksonville FL 32226

Donna Kayron Porter
12052 Sheffield Rd
Jacksonville FL 32226

William Davis Hewitt
37 Willow Glen
Atlanta GA 30342

4708510277

RECEIVED
Office of Oil and Gas
JAN 14 2016
WV Department of
Environmental Protection

Coal Owners:

Union National Bank of West Virginia, Trustee
PO Box 659
Wichita Falls TX 76307

Haught Family Trust
210 E Main St
Harrisville WV 26362

Kayron B Hall
12052 Sheffield Rd
Jacksonville FL 32226

Susan Lee Hewitt
50 Lamsden Ln
Atlanta GA 30327

John Kerns Heirs Trust
Union Nat'l Bank of Clarksburg
PO Box 659
Wichita Falls TX 76307

Elizabeth Hewitt Taylor Ventures LLC
9925 Huntcliff Trace
Atlanta GA 30350

4708510277

RECEIVED
Office of Oil and Gas
JAN 14 2016
WV Department of
Environmental Protection

Notice is hereby given:

Pursuant to West Virginia Code § 22-6A-10(b), notice is hereby given that the undersigned well operator has applied for a permit for well work or for a certificate of approval for the construction of an impoundment or pit.

This Notice Shall Include:

Pursuant to W. Va. Code § 22-6A-10(b), this notice shall include: (1) copies of the application; (2) the erosion and sediment control plan required by section seven of this article; and (3) the well plat.

Pursuant to W. Va. Code § 22-6A-10(f), this notice shall include: (1) a statement of the time limits for filing written comments; (2) who may file written comments; (3) the name and address of the secretary for the purpose of filing the comments and obtaining additional information; and (4) a statement that the persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.

Pursuant to W. Va. Code R. § 35-8-5.7.a, the operator shall provide the Well Site Safety Plan to the surface owner and any water purveyor or surface owner subject to notice and water testing as provided in section 15 of this rule.

Pursuant to W. Va. Code R. § 35-8-15.2.c, this notice shall: (1) contain a statement of the surface owner's and water purveyor's right to request sampling and analysis; (2) advise the surface owner and water purveyor of the rebuttable presumption for contamination or deprivation of a fresh water source or supply; advise the surface owner and water purveyor that refusal to allow the operator to conduct a pre-drilling water well test constitutes a method to rebut the presumption of liability; (3) advise the surface owner and water purveyor of his or her independent right to sample and analyze any water supply at his or her own expense; advise the surface owner and water purveyor whether or not the operator will utilize an independent laboratory to analyze any sample; and (4) advise the surface owner and or water purveyor that he or she can obtain from the Chief a list of water testing laboratories in the subject area capable of and qualified to test water supplies in accordance with standard acceptable methods.

Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57th Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting www.dep.wv.gov/oil-and-gas/pages/default.aspx.

Well Location Restrictions

Pursuant to W. Va. Code § 22-6A-12, Wells may not be drilled within two hundred fifty feet measured horizontally from any existing water well or developed spring used for human or domestic animal consumption. The center of well pads may not be located within six hundred twenty-five feet of an occupied dwelling structure, or a building two thousand five hundred square feet or larger used to house or shelter dairy cattle or poultry husbandry. This limitation is applicable to those wells, developed springs, dwellings or agricultural buildings that existed on the date a notice to the surface owner of planned entry for surveying or staking as provided in section ten of this article or a notice of intent to drill a horizontal well as provided in subsection (b), section sixteen of this article was provided, whichever occurs first, and to any dwelling under construction prior to that date. This limitation may be waived by written consent of the surface owner transmitted to the department and recorded in the real property records maintained by the clerk of the county commission for the county in which such property is located. Furthermore, the well operator may be granted a variance by the secretary from these distance restrictions upon submission of a plan which identifies the sufficient measures, facilities or practices to be employed during well site construction, drilling and operations. The variance, if granted, shall include terms and conditions the department requires to ensure the safety and protection of affected persons and property. The terms and conditions may include insurance, bonding and indemnification, as well as technical requirements. (b) No well pad may be prepared or well drilled within one hundred feet measured horizontally from any perennial stream, natural or artificial lake, pond or reservoir, or a wetland, or within three hundred feet of a naturally reproducing trout stream. No well pad may be located within one thousand feet of a surface or ground water intake of a public water supply. The distance from the public water supply as identified by the department shall be measured as follows: (1) For a surface water intake on a lake or reservoir, the distance shall be measured from the boundary of the lake or reservoir. (2) For a surface water intake on a flowing stream, the distance shall be measured from a semicircular radius extending upstream of the surface water intake. (3) For a groundwater source, the distance shall be measured from the wellhead or spring. The department may, in its discretion, waive these distance restrictions upon submission of a plan identifying sufficient measures, facilities or practices to be employed during well site construction, drilling and operations to protect the waters of the state. A waiver, if granted, shall impose any permit conditions as the secretary considers necessary. (c) Notwithstanding the foregoing provisions of this section, nothing contained in this section prevents an operator from conducting the activities permitted or authorized by a Clean Water Act Section 404 permit or other approval from the United States Army Corps of Engineers within any waters of the state or within the restricted areas referenced in this section. (d) The well location restrictions set forth in this section shall not apply to any well on a multiple well pad if at least one of the wells was permitted prior to the effective date of this article. (e) The secretary shall, by December 31, 2012, report to the Legislature on the noise, light, dust and volatile organic compounds generated by the drilling of horizontal wells as they relate to the well location restrictions regarding occupied dwelling structures pursuant to this section. Upon a finding, if any, by the secretary that the well location restrictions regarding occupied dwelling structures are inadequate or otherwise require alteration to address the items

WW-6A
(8-13)

API NO. 47 - 085 - 0
OPERATOR WELL NO. 513380
Well Pad Name: AUB54

examined in the study required by this subsection, the secretary shall have the authority to propose for promulgation legislative rules establishing guidelines and procedures regarding reasonable levels of noise, light, dust and volatile organic compounds relating to drilling horizontal wells, including reasonable means of mitigating such factors, if necessary.

Water Well Testing:

Pursuant to West Virginia Code § 22-6A-10(d), notification shall be made, with respect to surface landowners identified in subsection (b) or water purveyors identified in subdivision (5), subsection (b) of this section, of the opportunity for testing their water well. The operator shall provide an analysis to such surface landowner or water purveyor at their request.

Water Testing Laboratories:

Pursuant to West Virginia Code § 22-6A-10(i), persons entitled to notice pursuant to subsection (b) of this section may contact the department to ascertain the names and locations of water testing laboratories in the subject area capable and qualified to test water supplies in accordance with standard accepted methods. In compiling that list of names the department shall consult with the state Bureau for Public Health and local health departments. A surface owner and water purveyor has an independent right to sample and analyze any water supply at his or her own expense. The laboratory utilized by the operator shall be approved by the agency as being certified and capable of performing sample analyses in accordance with this section.

Rebuttable Presumption for Contamination or Deprivation of a Fresh Water Source or Supply:

W. Va. Code § 22-6A-18 requires that (b) unless rebutted by one of the defenses established in subsection (c) of this section, in any action for contamination or deprivation of a fresh water source or supply within one thousand five hundred feet of the center of the well pad for horizontal well, there is a rebuttable presumption that the drilling and the oil or gas well or either was the proximate cause of the contamination or deprivation of the fresh water source or supply. (c) In order to rebut the presumption of liability established in subsection (b) of this section, the operator must prove by a preponderance of the evidence one of the following defenses: (1) The pollution existed prior to the drilling or alteration activity as determined by a predrilling or prealteration water well test. (2) The landowner or water purveyor refused to allow the operator access to the property to conduct a predrilling or prealteration water well test. (3) The water supply is not within one thousand five hundred feet of the well. (4) The pollution occurred more than six months after completion of drilling or alteration activities. (5) The pollution occurred as the result of some cause other than the drilling or alteration activity. (d) Any operator electing to preserve its defenses under subdivision (1), subsection (c) of this section shall retain the services of an independent certified laboratory to conduct the predrilling or prealteration water well test. A copy of the results of the test shall be submitted to the department and the surface owner or water purveyor in a manner prescribed by the secretary. (e) Any operator shall replace the water supply of an owner of interest in real property who obtains all or part of that owner's supply of water for domestic, agricultural, industrial or other legitimate use from an underground or surface source with a comparable water supply where the secretary determines that the water supply has been affected by contamination, diminution or interruption proximately caused by the oil or gas operation, unless waived in writing by that owner. (f) The secretary may order the operator conducting the oil or gas operation to: (1) Provide an emergency drinking water supply within twenty-four hours; (2) Provide temporary water supply within seventy-two hours; (3) Within thirty days begin activities to establish a permanent water supply or submit a proposal to the secretary outlining the measures and timetables to be used in establishing a permanent supply. The total time in providing a permanent water supply may not exceed two years. If the operator demonstrates that providing a permanent replacement water supply cannot be completed within two years, the secretary may extend the time frame on case-by-case basis; and (4) Pay all reasonable costs incurred by the real property owner in securing a water supply. (g) A person as described in subsection (b) of this section aggrieved under the provisions of subsections (b), (e) or (f) of this section may seek relief in court... (i) Notwithstanding the denial of the operator of responsibility for the damage to the real property owner's water supply or the status of any appeal on determination of liability for the damage to the real property owner's water supply, the operator may not discontinue providing the required water service until authorized to do so by the secretary or a court of competent jurisdiction.

Written Comment:

Pursuant to West Virginia Code § 22-6A-11(a), all persons described in subsection (b), section ten of this article may file written comments with the secretary as to the location or construction of the applicant's proposed well work within thirty days after the application is filed with the secretary. All persons described in West Virginia Code § 22-6A-10(b) may file written comments as to the location or construction of the applicant's proposed well work to the Secretary at:

Chief, Office of Oil and Gas
Department of Environmental Protection
601 57th St. SE
Charleston, WV 25304
(304) 926-0450

Such persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.
NOTE: YOU ARE NOT REQUIRED TO FILE ANY COMMENT.

RECEIVED
Office of Oil and Gas
JAN 14 2013
WV Department of
Environmental Protection

Time Limits and Methods for Filing Comments.

The law requires these materials to be served on or before the date the operator files its Application. You have THIRTY (30) DAYS after the filing date to file your comments. Comments must be filed in person or received in the mail by the Chief's office by the time stated above. You may call the Chief's office to be sure of the date. Check with your postmaster to ensure adequate delivery time or to arrange special expedited handling. If you have been contacted by the well operator and you have signed a "voluntary statement of no objection" to the planned work described in these materials, then the permit may be issued at any time.

Pursuant to West Virginia Code § 22-6A-11(c)(2), Any objections of the affected coal operators and coal seam owners and lessees shall be addressed through the processes and procedures that exist under sections fifteen, seventeen and forty, article six of this chapter, as applicable and as incorporated into this article by section five of this article. The written comments filed by the parties entitled to notice under subdivisions (1), (2), (4), (5) and (6), subsection (b), section ten of this article shall be considered by the secretary in the permit issuance process, but the parties are not entitled to participate in the processes and proceedings that exist under sections fifteen, seventeen or forty, article six of this chapter, as applicable and as incorporated into this article by section five of this article

Comment Requirements

Your comments must be in writing and include your name, address and telephone number, the well operator's name and well number and the approximate location of the proposed well site including district and county from the application. You may add other documents, such as sketches, maps or photographs to support your comments.

Disclaimer: All comments received will be placed on our web site <http://www.dep.wv.gov/oil-and-gas/Horizontal-Permits/Pages/default.aspx> and the applicant will automatically be forwarded an email notice that such comments have been submitted. The applicant will be expected to provide a response to comments submitted by any surface owner, water purveyor or natural gas storage operator noticed within the application.

Permit Denial or Condition

The Chief has the power to deny or condition a well work permit. Pursuant to West Virginia Code § 22-6A-8(d), the permit may not be issued or be conditioned, including conditions with respect to the location of the well and access roads prior to issuance if the director determines that:

- (1) The proposed well work will constitute a hazard to the safety of persons;
- (2) The plan for soil erosion and sediment control is not adequate or effective;
- (3) Damage would occur to publicly owned lands or resources; or
- (4) The proposed well work fails to protect fresh water sources or supplies.

A permit may also be denied under West Virginia Code § 22-6A-7(k), the secretary shall deny the issuance of a permit if the secretary determines that the applicant has committed a substantial violation of a previously issued permit for a horizontal well, including the applicable erosion and sediment control plan associated with the previously issued permit, or a substantial violation of one or more of the rules promulgated under this article, and in each instance has failed to abate or seek review of the violation within the time prescribed by the secretary pursuant to the provisions of subdivisions (1) and (2), subsection (a), section five of this article and the rules promulgated hereunder, which time may not be unreasonable.

Pursuant to West Virginia Code § 22-6A-10(g), any person entitled to submit written comments to the secretary pursuant to subsection (a), section eleven of this article, shall also be entitled to receive from the secretary a copy of the permit as issued or a copy of the order modifying or denying the permit if the person requests receipt of them as a part of the written comments submitted concerning the permit application. Such persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.

6700510277

RECEIVED
Office of Oil and Gas
JAN 14 2015
WV Department of
Environmental Protection

Notice is hereby given by:

Well Operator: EQT Production Company
Telephone: 304-848-0082
Email: Vroark@eqt.com

Address: 115 Professional Place P.O. Box 280
Bridgeport, WV 26330
Facsimile: 304-848-0041

Oil and Gas Privacy Notice:

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at depprivacyofficer@wv.gov.


I certify under penalty of law that I have personally examined and am familiar with the information submitted on this application form and all attachments, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete.

Victoria Roark

By: Victoria Roark

Its: Permitting Supervisor

Subscribed and sworn before me 8 day of Jan, 2016
Pamela Sykes Notary Public
My Commission Expires 8-24-22



4708510277

RECEIVED
Office of Oil and Gas
Jan 24 2016
WV Department of
Environmental Protection



[Faint, illegible handwritten text]

OFFICIAL SEAL
STATE OF WEST VIRGINIA
NOTARY PUBLIC
James Bykes
EOT Production
PO Box 580
Burdgett, WV 26030
My Commission Expires Aug. 24, 2025



[Faint, illegible handwritten text]

WATER SOURCE LOCATIONS FOR HALL LEASE AUB54 WELLS



LEGEND
 WATER WELL

Professional Energy Consultants
 A DIVISION OF SMITH LAND SURVEYING, INC.

 SURVEYORS
 ENGINEERS
 ENVIRONMENTAL
 PROJECT MGMT.
(304) 982-9634
 WWW.SLSURVEYS.COM

TOPO SECTION OF:
 AUBURN, WV 7.5' QUAD

DISTRICT	COUNTY	TAX MAP-PARCEL NO.
UNION	RITCHIE	32-17

OPERATOR: *Office of Oil and Gas*
EQT PRODUCTION COMPANY
 115 PROFESSIONAL PLACE
 P.O. BOX 280
 BRIDGEPORT, WV 26330
Department of Environmental Protection

DRAWN BY K.D.W.	FILE NO. 7580	DATE 08/12/15	CADD FILE: 7580AUB54WS.dwg
--------------------	------------------	------------------	-------------------------------

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE OF ENTRY FOR PLAT SURVEY

Notice Time Requirement: Notice shall be provided at least **SEVEN (7)** days but no more than **FORTY-FIVE (45)** days prior to entry.

Date of Notice: 2/5/2015

Date of Planned Entry: 2/13/2015

Delivery method pursuant to West Virginia Code § 22-6A-10(a):

PERSONAL SERVICE CERTIFIED MAIL METHOD OF DELIVERY THAT REQUIRES A RECEIPT OR SIGNATURE CONFIRMATION

Pursuant to West Virginia Code § 22-6A-10(a), prior to filing a permit application, the operator shall provide notice of planned entry on to the surface tract to conduct any plat surveys required pursuant to this article. Such notice shall be provided at least seven days but no more than forty-five days prior to such entry to: (1) The surface owner of such tract; (2) to any owner or lessee of coal seams beneath such tract that has filed a declaration pursuant to section thirty-six, article six, chapter twenty-two of this code; and (3) any owner of minerals underlying such tract in the county tax records. The notice shall include a statement that copies of the state Erosion and Sediment Control Manual and the statutes and rules related to oil and gas exploration and production may be obtained from the Secretary, which statement shall include contact information, including the address for a web page on the Secretary's web site, to enable the surface owner to obtain copies from the secretary.

Notice is hereby provided to:

SURFACE OWNER(S)

Name: Brian Taschler & Rochelle M. Taschler
Address: 795 Towamensing Rd.
Lehighton, PA 18235-5931

MINERAL OWNER(S)

Name: _____
Address: _____

COAL OWNER(S) OR LESSEE(S)

Coal Declaration pursuant to §22-6A-10 and §22-6-36 Not of Record

*Please attach additional forms if necessary

Notice is hereby given:

Pursuant to West Virginia Code § 22-6A-10(a), notice is hereby given that the undersigned well operator is planning entry to conduct a plat survey on the tract of land as follows:

State: <u>West Virginia</u>	Approx. Latitude & Longitude: <u>39.11613/-80.85453</u>
County: <u>Ritchie</u>	Public Road Access: <u>CR 7/18</u>
Dist/Map/Par: <u>Union / Map 32 / Parcel 17</u>	Watershed: <u>Little Kanawha</u>
Quadrangle: <u>Auburn</u>	Generally Used Farm Name: <u>Hall Lease</u>

Copies of the state Erosion and Sediment Control Manual and the statues and rules related to oil and gas exploration and production may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57th Street, SE, Charleston, WV 25304 (304-926-0450). Copies of such documents or additional information related to horizontal drilling may be obtained from the Secretary by visiting www.dep.wv.gov/oil-and-gas/pages/default.aspx.

Notice is hereby given by:

Well Operator: EQT Production Company
Telephone: 304-848-0099
Facsimile: 304-848-0040
Email: eqtlandentrynotice@eqt.com

Address: 115 Professional Place, Bridgeport, WV 26330
EQT Representative: Kathy Kugel

Signature: *Kathy Kugel*

Oil and Gas Privacy Notice:

The Office of Oil and Gas processes your personal information, such a name, address and telephone number, as part of regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at depprivacyofficer@wv.gov.

4708510277

RECEIVED
Office of Oil and Gas
JAN 14 2015

WW-6A5
(1/12)

Operator Well No. 513380

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE OF PLANNED OPERATION

Notice Time Requirement: notice shall be provided no later than the filing date of permit application.

Date of Notice: 1-11-16 Date Permit Application Filed: 1-11-16

Delivery method pursuant to West Virginia Code § 22-6A-16(c)

CERTIFIED MAIL RETURN RECEIPT REQUESTED HAND DELIVERY

Pursuant to W. Va. Code § 22-6A-16(c), no later than the date for filing the permit application, an operator shall, by certified mail return receipt requested or hand delivery, give the surface owner whose land will be used for the drilling of a horizontal well notice of the planned operation. The notice required by this subsection shall include: (1) A copy of this code section; (2) The information required to be provided by subsection (b), section ten of this article to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. (d) The notices required by this section shall be given to the surface owner at the address listed in the records of the sheriff at the time of notice.

Notice is hereby provided to the SURFACE OWNER(s)

(at the address listed in the records of the sheriff at the time of notice):

Name: See Attached Name: _____
Address: _____ Address: _____

Notice is hereby given:

Pursuant to West Virginia Code § 22-6A-16(c), notice is hereby given that the undersigned well operator has developed a planned operation on the surface owner's land for the purpose of drilling a horizontal well on the tract of land as follows:

State: WV UTM NAD 83 Easting: 512,581.290000
County: Ritchie Northing: 4,329,681.770000
District: Union Public Road Access: WV RT 47
Quadrangle: Auburn 7.5' Generally used farm name: Brian Taschler et al
Watershed: Left Fork & Brushy Fork of Bone Creek

This Notice Shall Include:

Pursuant to West Virginia Code § 22-6A-16(c), this notice shall include: (1) A copy of this code section; (2) The information required to be provided by **W. Va. Code § 22-6A-10(b)** to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57th Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting www.dep.wv.gov/oil-and-gas/pages/default.aspx.

Well Operator: EQT Production Company Address: 115 Professional Place, P.O. Box 280
Telephone: 304-848-0082 Bridgeport, WV 26330
Email: vroark@eqt.com Facsimile: 304-848-0040

Oil and Gas Privacy Notice:

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at depprivacyofficer@wv.gov.

RECEIVED
Office of Oil and Gas
JAN 14 2016
WV Department of
Environmental Protection

WW6-A

Surface Owner

Brian Taschler
795 Towamensing Rd.
Leighton Pa 18235

Surface Owner Access/ Other Disturbance

Brian Taschler
795 Towamensing Rd.
Leighton Pa 18235

Jerry Riddle
2187 Riddle Hill Rd.
Auburn WV 26325

Betty Jean Nutter
2499 Glendale Road
Cairo WV 26337

Kiedaisch & Summers ENT., LLC
Po Box 254
Harrisville, WV 26362

Louis and Linda Kopf
2220 Brushy Fork Road
Auburn WV 26325

Craig & Amy Williams
6390 Rotherby Circle
Hudson OH 44236

Surface Owner Pits or Impoundment

Brian Taschler
795 Towamensing Rd.
Leighton Pa 18235

4708510277

RECEIVED
Office of Oil and Gas

JAN 14 2016

WV Department of
Environmental Protection



479051020

WEST VIRGINIA DEPARTMENT OF TRANSPORTATION

Division of Highways

1900 Kanawha Boulevard East • Building Five • Room 110
Charleston, West Virginia 25305-0430 • (304) 558-3505

Earl Ray Tomblin
Governor

Paul A. Mattox, Jr., P. E.
Secretary of Transportation/
Commissioner of Highways

January 4, 2016

James A. Martin, Chief
Office of Oil and Gas
Department of Environmental Protection
601 57th Street, SE
Charleston, WV 25304

Subject: DOH Permit for the AUB 54 Pad Site, Ritchie County

- | | | |
|------------------|-----------------|-----------------|
| 513379 AUB54 H1 | 513380 AUB54 H2 | 513381 AUB54 H3 |
| 513382 AUB54 H4 | 513383 AUB54 H5 | 513384 AUB54 H6 |
| 514040 AUB54 H7 | 514041 AUB54 H8 | 514042 AUB54 H9 |
| 514043 AUB54 H10 | | |

Dear Mr. Martin,

This well site will be accessed from Permit #03-2015-0567 issued to EQT Production Company for access to the State Road. The well site is located off of Ritchie County Route 7/13 SLS. Approved permit must be received before the start of construction.

The operator has signed a STATEWIDE OIL AND GAS ROAD MAINTENANCE BONDING AGREEMENT and provided the required Bond. This operator is currently in compliance with the DOH OIL AND GAS POLICY dated January 3, 2012.

Very Truly Yours,

Gary K. Clayton, P.E.
Regional Maintenance Engineer
Central Office O&G Coordinator

Cc: Nick Bumgardner
EQT Production Company
CH, OM, D-3, File

RECEIVED
Office of Oil and Gas

JAN 14 2016

WV Department of
Environmental Protection

Anticipated Frac Additives
Chemical Names and CAS numbers

4700310277

<u>Material</u>	<u>Ingredient</u>	<u>CAS Number</u>
Water		
Sand	Hydrotreated light petroleum distillate	14808-60-7
Friction Reducer	Tributyl tetradecyl phosphonium chloride	64742-47-8
Biocide	Ammonium chloride	81741-28-8
Scale Inhibitor	Hydrochloric Acid	12125-02-9
15% Hydrochloric Acid	Propargyl Alcohol	7647-01-0
Corrosion Inhibitor	Methanol	107-19-7
Corrosion Inhibitor	Guar Gum	67-56-1
Gelling Agent	Sodium Persulfate	9000-30-0
Oxidizing Breaker	Potassium Carbonate	7775-27-1
Buffering Agent		584-08-7

RECEIVED
Office of Oil and Gas


JAN 14 2016

WV Department of
Environmental Protection

OPERATOR: EQT PRODUCTION COMP WELL NO: AUB 54PAD

PAD NAME: AUB 54

REVIEWED BY: REX BUMGARDNER

SIGNATURE: 

WELL RESTRICTIONS CHECKLIST

HORIZONTAL 6A WELL

Well Restrictions

- At Least 100 Feet from Pad and LOD (including any E&S Control Feature) to any Perennial Stream, Lake, Pond, Reservoir or Wetland; OR
 DEP Waiver and Permit Conditions
- At Least 300 Feet from Pad and LOD (including any E&S Control Feature) to any Naturally Producing Trout Stream; OR
 DEP Waiver and Permit Conditions
- At Least 1000 Feet from Pad and LOD (including any E&S Control Feature) to any Groundwater Intake or Public Water Supply; OR
 DEP Waiver and Permit Conditions
- At Least 250 Feet from an Existing Water Well or Developed Spring to Well Being Drilled; OR
 Surface Owner Waiver and Recorded with County Clerk, OR
 DEP Variance and Permit Conditions
- At Least 625 Feet from an Occupied Dwelling Structure to Center of the Pad; OR
 Surface Owner Waiver and Recorded with County Clerk, OR
 DEP Variance and Permit Conditions
- At Least 625 Feet from Agricultural Buildings Larger than 2500 Square Feet to the Center of the Pad; OR
 Surface Owner Waiver and Recorded with County Clerk, OR
 DEP Variance and Permit Conditions

4708510277

RECEIVED
Office of Oil and Gas
JAN 14 2016
WV Department of
Environmental Protection

4708510277

EQT Production
Hydraulic Fracturing Monitoring Plan
Pad ID: AUB54
Ritchie County, WV

1/4/2016

RECEIVED
Office of Oil and Gas
JAN 14 2016
Page 1 of 3
WV Department of
Environmental Protection

Purpose

The purpose of this pad-specific Hydraulic Fracturing Monitoring Plan is to establish a joint effort between EQT, the West Virginia Office of Oil and Gas (OOG), and local conventional well operators in the Ritchie County area. This plan applies to proposed wells on this pad: 513380, 513382, 513384 and 514041.

Due to the apparent presence of unique geological conditions, the potential for communication between deep geologic zones exists in this area. This potential communication, via natural gas, water, or both, may occur between hydraulically fractured wells in the Marcellus formation (approximately 6,600' TVD) and existing conventional natural gas wells in the partially-depleted, relatively high permeability Alexander formation (approximately 5,200' TVD).

The plan is being implemented as an additional safety measure to be utilized in conjunction with existing best management practices and emergency action plans for the site. The plan will further enable the participants to obtain data and information for a root cause analysis in the event communication between zones does occur during hydraulic fracturing.

These additional measures include pre-notification of conventional well operators of the timing and location of the hydraulic fracturing, establishment of measures conventional well operators should implement, and assurance that the OOG is notified of the timeline, as well as any issues that may arise during fracturing.

1. Communications with Conventional Well Operators

EQT, using available data (WV Geological Survey, WVDEP website, and IHS data service), has identified all known conventional wells and well operators within 1,500 feet of this pad and the lateral sections. A map showing these wells along with a list of the wells and operators is included in **Attachment A**.

Upon approval of this plan, EQT will notify these operators, via letter, of the hydraulic fracturing schedule for these wells. A copy of this letter is included in **Attachment B**.

The letter provides recommendations to these conventional operators to 1) increase their monitoring of their wells during that time period, 2) ensure that their well head equipment is sound, and 3) provide immediate notification to EQT and the OOG in the event of any changes in their well conditions.

Specifically, the letter recommends that conventional well operators conduct the following activities during and after fracturing operations:

1. Inspect their surface equipment prior to fracturing to establish integrity and establish pre-frac well conditions
2. Observe wells closely during and after fracturing and monitor for abnormal increases in water, gas or pressure
3. Inspect or install master valves rated to 3,000 psi or other necessary equipment for wellhead integrity
4. Notify the OOG and EQT if any changes in water, gas production, pressure, or other anomalies are identified

2. Monitoring

EQT will conduct pressure monitoring on select conventional wells before, during, and after hydraulic fracturing of this pad. EQT has selected conventional wells which are directly above its lateral section and completed within the Alexander formation, at approximately 1,000' intervals. EQT will also monitor select conventional wells that lie within the 1500' area identified above. EQT will monitor the wells prior to, during and post fracturing. Wells selected for monitoring are identified in **Attachment A**.

JAN 14 2016

RECEIVED
Office of Oil and Gas
Page 2 of 3
WV Department of
Environmental Protection

The wells to be monitored are conventional wells operated by Energy Corporation of America (ECA) or EQT. EQT will install pressure transducers and Eagle Research RTU's to obtain real-time pressure readings on these conventional wells. These units will allow continuous sampling of pressure throughout the fracturing operations.

EQT will also utilize chemical tracers during our hydraulic fracturing. Each well will have two different tracers. Should communication occur, these different tracers may allow us to identify which well(s), and which part of the horizontal well may have communicated with the monitored conventional wells. These tracers will be placed into the fracturing fluid.

EQT will closely monitor drilling and hydraulic fracturing activities to identify any abnormalities related to geology such as loss of fluid circulation during drilling or pressure anomalies noted during fracturing.

This pad will be drilled and hydraulically fractured by EQT without any other modifications to our normal practices, unless communication is observed. These include casing and cementing practices, hydraulic fracturing volumes, pumping rates, drillout , and flowback timeframes. This will assist in establishing a baseline for future monitoring of activities in this area. Should communication be observed, EQT may vary the completion design on fracturing stages completed after the communication is observed.

3. Reporting

EQT will provide information relating to the hydraulic fracturing schedule, communication with conventional operators, and ongoing monitoring of the work on a regular and routine basis, upon request of OOG, or immediately in the event of any noted abnormalities.

Upon completion of the hydraulic fracturing and monitoring, EQT will provide a written report documenting the monitoring activities identified in this plan.

4503370277

RECEIVED
Office of Oil and Gas

JAN 14 2016

WV Department of Environmental Protection
Page 3 of 3


WellID	Permit	Operator GGX	Operator DEP	Latitude	Longitude	Status	DatumEleva	TD SS	TD	Lateral Map Distance (ft)	SS Horiz	horiz - TD	Hypot Dist	Measured from well#
4708501657	01657	B E TALKINGTON	ROSS AND WHARTON GAS COMPANY, INC.	39.105400000000	-80.852300000000	GAS	870.0000	-985.0000	1855.0000	907.5600	-5445	7300	7356.199097	513380
4708501678	01678	J F DEEM O&G	DEEM, J. F. OIL & GAS, LLC	39.106600000000	-80.837000000000	DRY	905.0000	-966.0000	1871.0000	1311.6700	-5445	7316	7432.65324	514041
4708501709	01709	B E TALKINGTON	ROSS AND WHARTON GAS COMPANY, INC.	39.106500000000	-80.847400000000	GAS	1020.0000	-913.0000	1933.0000	599.8500	-5445	7378	7402.344495	513382
4708501723	01723	B E TALKINGTON	ROSS AND WHARTON GAS COMPANY, INC.	39.108500000000	-80.842400000000	GAS	1050.0000	-965.0000	2015.0000	66.5900	-5445	7460	7460.297194	514041
4708501746	01746	B E TALKINGTON	ROSS AND WHARTON GAS COMPANY, INC.	39.114000000000	-80.844500000000	GAS	930.0000	-916.0000	1846.0000	94.3900	-5445	7291	7291.610965	514041
4708501938	01938	B E TALKINGTON	POSTROCK EASTERN PRODUCTION LLC	39.103200000000	-80.843500000000	GAS	900.0000	-965.0000	1865.0000	418.5400	-5445	7310	7321.97212	513384
4708502004	02004	WILLARD E FERRELL	RITCHIE PETROLEUM CORP.	39.108400000000	-80.849400000000	GAS	1009.0000	-938.0000	1947.0000	209.8600	-5445	7392	7394.978379	513382
4708502018	02018	ALAMCO	TARGA DEVELOPMENT INC	39.121500000000	-80.851800000000	GAS	990.0000	-1116.0000	2106.0000	1432.2100	-5445	7551	7685.624665	513384
4708502035	02035	ALAMCO	ALAMCO INC	39.118300000000	-80.857200000000	DRY	1095.0000	-945.0000	2040.0000	1089.8800	-5445	7485	7563.931743	513380
4708502057	02057	B E TALKINGTON	OPERATOR UNKNOWN	39.105400000000	-80.839300000000	DRY	926.0000	-1006.0000	1932.0000	570.3200	-5445	7377	7399.013036	514041
4708502080	02080	WV DEPT OF O & G	UNKNOWN - DEP PAID PLUGGING CONTRACT	39.111000000000	-80.852200000000	GAS-P	1000.0000	-1815.0000	2815.0000	205.1300	-5445	8260	8262.546721	513380
4708502082	02082	WILLARD E FERRELL	OPERATOR UNKNOWN	39.113800000000	-80.848600000000	GAS	1191.0000	-934.0000	2125.0000	213.5500	-5445	7570	7573.011528	513384
4708502101	02101	PURSLEYS PULLING	RITCHIE PETROLEUM CORP.	39.120600000000	-80.843500000000	GAS	950.0000	-977.0000	1927.0000	1172.9900	-5445	7372	7464.736401	514041
4708502114	02114	WILLARD E FERRELL	OPERATOR UNKNOWN	39.116100000000	-80.851600000000	GAS	1070.0000	-1160.0000	2230.0000	67.5400	-5445	7675	7675.29717	51382
4708503404	03404	TROY A BRADY	ROSS AND WHARTON GAS COMPANY, INC.	39.108800000000	-80.855400000000	GAS	967.0000	-967.0000	1934.0000	912.8700	-5445	7379	7435.252022	513380
4708503409	03409	TROY A BRADY	POSTROCK EASTERN PRODUCTION LLC	39.101600000000	-80.839500000000	GAS	953.0000	-3957.0000	4910.0000	1423.0900	-5445	10355	10452.33037	514041
4708503414	03414	TROY A BRADY	ROSS AND WHARTON GAS COMPANY, INC.	39.103500000000	-80.847600000000	GAS	852.0000	-1009.0000	1861.0000	1157.2400	-5445	7306	7397.083237	513384
4708503419	03419	TROY A BRADY	ROSS AND WHARTON GAS COMPANY, INC.	39.105600000000	-80.844100000000	GAS	897.0000	-635.0000	1532.0000	29.8200	-5445	6977	6977.063726	513384
4708503439	03439	TROY A BRADY	ROSS AND WHARTON GAS COMPANY, INC.	39.110100000000	-80.844900000000	GAS	917.0000	-974.0000	1891.0000	344.4000	-5445	7336	7344.079749	513384
4708503464	03464	TROY A BRADY	ROSS AND WHARTON GAS COMPANY, INC.	39.112400000000	-80.840000000000	GAS	936.0000	-968.0000	1904.0000	1136.1900	-5445	7349	7436.311499	514041
4708503998	03998	EPC	EQT PRODUCTION COMPANY	39.116600000000	-80.846200000000	GAS	0.0000	-2057.0000	2057.0000	80.2200	-5445	7502	7502.42889	514041
4708508160	08160	ALAMCO	SWN PRODUCTION COMPANY, LLC	39.120000000000	-80.855400000000	GAS	1103.0000	-1458.0000	2561.0000	1391.8500	-5445	8006	8126.086538	513384
4708509668	09668	ROSS & WHARTON	ROSS AND WHARTON GAS COMPANY, INC.	39.103500000000	-80.848700000000	GAS	846.0000	-4156.0000	5002.0000	1445.5400	-5445	10447	10546.53473	513384
4708509735	09735	ROSS MIKE	ROSS AND WHARTON GAS COMPANY, INC.	39.109000000000	-80.839600000000	TA	872.0000	-5118.0000	5990.0000	860.2600	-5445	11435	11467.31321	514041
4708530871	30871	PGH & WV GAS		39.116900000000	-80.859700000000	GAS	0.0000	-1982.0000	1982.0000	1412.1100	-5445	7427	7560.051829	513380

4708510277

Attachment A

(1)

AUB54 Vertical Offsets





(date)

[Conventional Well Operator]
[address]
[state]

470 851 0277

RE: Ritchie County Hydraulic Fracturing Notice

Dear Sir/Madam,

EQT has developed a Marcellus pad (Auburn 54 pad) located in Ritchie County, WV. As an owner or operator of conventional natural gas wells in this area, we are requesting your assistance in this matter.

Due to the apparent presence of unique geological conditions, the potential for communication between deep geologic zones exists in this area. This potential communication, via natural gas, water, or both, may occur between hydraulically fractured wells in the Marcellus formation (approximately 6,600' TVD) and existing conventional natural gas wells in the partially-depleted, relatively high permeability, Alexander formation (approximately 5,200' TVD).

EQT anticipates conducting hydraulic fracturing at the Pennsboro 40 pad during the [first,second, third,fourth] quarter of [year]. We have identified conventional natural gas wells operated by your company within 1,500' (lateral distance) of our new/planned laterals. Plats for each well on this pad are attached.

We recommend that conventional well operators conduct the following activities before, during, and after fracturing operations:

1. Inspect surface equipment, prior to fracturing, to establish integrity and establish well conditions.
2. Observe wells closely during and after fracturing and monitor for abnormal increases in water, gas, or pressure.
3. Inspect or install master valves rated to 3,000 psi or other necessary equipment for wellhead integrity.
4. Notify the OOG and EQT if any changes in water, gas production, pressure, or other anomalies are identified.

Please feel free to contact me at 412-395-3305 with any questions or comments. You may also contact the West Virginia Office of Oil and Gas at 304-926-0440.

Sincerely,
EQT Production

John Centofanti
Corporate Director, Environmental Affairs

cc: James Martin, WV Office of Oil and Gas

Attachment B

AUB-54 FINAL SITE PLAN

PROPOSED WELL NUMBERS: H2-WW513380, H3-WW513381, H4-WW513382, H5-WW513383, H6-WW513384, AND H8-WW514041



Where energy meets innovation.




Land & Energy Development

THIS DOCUMENT IS THE PROPERTY OF EOT. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN. IT IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF EOT.

AUB-54 FINAL SITE PLAN
UNION DISTRICT
RITCHIE COUNTY, WV

DATE: 11-04-16
SCALE: 1" = 50'
DESIGNED BY: MLH
FILE NO.: 16060
SHEET: 7 OF 24
REV: 02-10-2016



APPROVED
WVDEP OOG
 6/2/2016
 [Signature]



PROJECT INFORMATION

PROJECT NAME: AUB-54
 TAX PARCEL: UNION DISTRICT MAP 19-35
 SURFACE OWNERS: BRIAN TACHLER ET AL, UNION DISTRICT, RITCHIE COUNTY, WV
 OIL AND GAS ROYALTY OWNER: DENISE HALL ET AL, UNION DISTRICT, RITCHIE COUNTY, WV

SURFACE OWNER DISTURBANCE		
SURFACE OWNER	LIMIT OF DISTURBANCE	
BRIAN TACHLER ET AL	17.6 ACRES	0.6 ACRES
RESEARCH & SERVICE ENTERPRISES	0.6 ACRES	0.6 ACRES
LOUIS J KOFF	0.6 ACRES	2.3 ACRES
FRANK A BEGUE ET AL	2.3 ACRES	

AUB-54 FINAL SITE PLAN

EQT PRODUCTION COMPANY

PROPOSED WELL NUMBERS: H2-WV513380, H3-WV513381, H4-WV513382, H5-WV513383, H6-WV513384, AND H8-WV514041

LIST OF DRAWINGS

- 1 - COVER SHEET
- 2 - NOTES
- 3 - OVERALL SHEET INDEX & VOLUMES
- 4 - PRELIMINARY SITE PLAN
- 5 - PRELIMINARY SITE PLAN
- 6 - PRELIMINARY SITE PLAN
- 7 - PRELIMINARY SITE PLAN
- 8 - PRELIMINARY SITE PLAN
- 9 - ACCESS ROAD PROFILES
- 10 - MAIN ACCESS CROSS SECTIONS
- 11 - SLOW BACK PIT AND CUT THRU ACCESS ROAD PROFILES
- 12 - STREAM IMPACTS
- 13 - MAIN ROAD CROSS SECTION
- 14 - MAIN ROAD CROSS SECTION
- 15 - FLOW BACK PIT AND CUT THRU CROSS-SECTIONS
- 16 - PAD AND PIT CROSS SECTIONS
- 17 - STOCKPILE CROSS SECTIONS
- 18 - PRELIMINARY RECLAMATION PLAN
- 19 - CONSTRUCTION DETAILS
- 20 - CONSTRUCTION DETAILS
- 21 - CONSTRUCTION DETAILS
- 22 - CONSTRUCTION DETAILS

SITUATE ON LEFT FORK & BRUSHY FORK OF BONE CREEK IN UNION DISTRICT, RITCHIE COUNTY

LOCATION COORDINATES

AUB-54 SITE ENTRANCE
 LATITUDE: 39.124631 LONGITUDE: -80.847286 (NAD 83)
 AUB-54 CENTER OF WELL PAD
 LATITUDE: 39.116849 LONGITUDE: -80.854494 (NAD 83)
 AUB-54 FLOW CENTER OF FLOW BACK PIT
 LATITUDE: 39.114675 LONGITUDE: -80.853485 (NAD 83)

SITE DISTURBANCE COMPUTATIONS

WELL PAD AREA & TANK BATTERY PAD: 5.8 ± ACRES
 MAIN ACCESS AREA: 9.0 ± ACRES
 STOCKPILE AREA: 8.4 ± ACRES
 FLOW BACK PIT & HANDLED AREA: 3.0 ± ACRES
 CUT THRU AREA: 2.3 ± ACRES
 TOTAL SITE DISTURBANCE: 29.1 ± ACRES

ENTRANCE PERMIT

EQT PRODUCTION COMPANY WILL OBTAIN AN ENTRANCE PERMIT (FORM M-100) FROM THE WEST VIRGINIA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

MISS UTILITY STATEMENT

MISS UTILITY OF WEST VIRGINIA WAS NOTIFIED FOR THE LOCATING OF UTILITIES PRIOR TO THIS PROJECT DESIGN. TICKET #102279999. IN ADDITION, MISS UTILITY WILL BE CONTACTED PRIOR TO START OF THE PROJECT.

FLOODPLAIN NOTE

THE PROPOSED LIMITS OF DISTURBANCE FOR THIS PROJECT IS LOCATED IN AN AREA THAT IS NOTED AS "Other Area" and could be designated either Zone D or Zone I on Flood Insurance Rate Maps 54085C033C & 54085C035C dated February 2, 2012.

ENVIRONMENTAL NOTES


A WETLAND DELINEATION WAS PERFORMED ON 4-16-2015, 6-6-2015, AND 6-7-2015 BY POTESTA & ASSOCIATES, INC TO REVIEW THE SITE FOR WATERS AND WETLANDS THAT ARE MOST LIKELY WITHIN THE REGULATORY JURISDICTION OF THE U.S. ARMY CORPS OF ENGINEERS (USACE) AND/OR THE WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (WVDEP). THE 6-17-2015 REPORT WAS PREPARED BY POTESTA & ASSOCIATES, INC. SUMMARIZED THE RESULTS OF THE FIELD DELINEATION. THE REPORT DOES NOT, IN ANY WAY, REPRESENT A JURISDICTIONAL DETERMINATION OF THE LANDFORD LIMITS OF WATERS AND WETLANDS WHICH MAY BE REGULATED BY THE USACE OR THE WVDEP. IT IS STRONGLY RECOMMENDED THAT THE APPLICANT CONSULT WITH THE APPROPRIATE AGENCIES PRIOR TO ANY PROPOSED IMPACTS TO WATERS OF THE U.S. INCLUDING WETLAND FILLS AND STREAM CROSSINGS.

GENERAL DESCRIPTION

THE AUB-54 PAD AND PITS ARE BEING CONSTRUCTED TO AID IN THE DEVELOPMENT OF INDIVIDUAL MARCELLUS SHALE GAS WELLS.

RESTRICTIONS NOTES:

1. THERE ARE NO PERENNIAL STREAMS/WETLANDS/OTHER WATER BODIES WITHIN 100 FEET OF THE WELL PAD LOD.
2. THERE ARE NO NATURALLY PRODUCING TROUT STREAMS WITHIN 300 FEET OF THE PAD AND LOD.
3. THERE ARE NO GROUNDWATER INTAKE OR PUBLIC WATER SUPPLY FACILITIES WITHIN 1000 FEET OF THE PAD AND LOD.
4. THERE ARE NO KNOWN EXISTING WATER WELLS OR DEVELOPED SPRINGS WITHIN 250 FEET OF THE WELLS (BEING DRILLED).
5. THERE ARE NO OCCUPIED DWELLING STRUCTURES WITHIN 625 FEET OF THE CENTER OF THE PAD.
6. THERE ARE NO AGRICULTURAL BUILDINGS LARGER THAN 2,500 SQUARE FEET WITHIN 625 FEET OF THE CENTER OF THE PAD.



MISS Utility of West Virginia
 1-800-245-4848
 West Virginia State Law
 (Section XIV, Chapter 24-C)
 Requires that you call two
 business days before you dig in
 the state of West Virginia.
 IT'S THE LAW!!

Michael Hoff
 2/19/16

OPERATOR
 EQT PRODUCTION COMPANY
 OPERATOR ID 30668
 115 PROFESSIONAL PLACE
 P.O. BOX 280
 BRIDGEPORT, WV 26330
 PHONE (304) 348-3070

ENGINEER/SURVEYOR
 SMITH LAND SURVEYING, INC.
 12 VANHORN DRIVE
 P.O. BOX 150
 CLENVILLE, WV 26031
 PHONE (204) 462-5634



THIS DOCUMENT WAS PREPARED BY SMITH LAND SURVEYING FOR EQT PRODUCTION COMPANY

COVER SHEET
AUB-54 FINAL SITE PLAN
 UNION DISTRICT
 RITCHIE COUNTY, WV

DATE: 11-6-15
 SCALE: 1" = 200'
 DESIGNED BY: KJA
 FILE NO: 7569
 SHEET 1 OF 22
 REV: 02-11-2016

RECEIVED
 Department of Environmental Protection
 Office of Oil and Gas
 FEB 23 2016


4708510277

4708510277

DATE: 11-9-15
 SCALE: 1" = 200'
 DESIGNED BY: KJR
 FILE NO: 1500
 SHEET 3 OF 22
 REV: 02-10-2016

AUB-54 FINAL
 SITE PLAN
 UNION DISTRICT
 RITCHIE COUNTY, WV

FOR EBT PRODUCTION
 LAND CONVERSION
 PERMITTED BY STATE



MAC
 8/19/16

AUB-54 COMPOST FILTER SOCK CALCULATIONS

NO.	AREA (SQ. FT.)	LENGTH (FT.)
151	151	151
152	152	152
153	153	153
154	154	154
155	155	155
156	156	156
157	157	157
158	158	158
159	159	159
160	160	160
161	161	161
162	162	162
163	163	163
164	164	164
165	165	165
166	166	166
167	167	167
168	168	168
169	169	169
170	170	170
171	171	171
172	172	172
173	173	173
174	174	174
175	175	175
176	176	176
177	177	177
178	178	178
179	179	179
180	180	180

AUB-54 COMPOST FILTER SOCK CALCULATIONS

NO.	AREA (SQ. FT.)	LENGTH (FT.)
181	181	181
182	182	182
183	183	183
184	184	184
185	185	185
186	186	186
187	187	187
188	188	188
189	189	189
190	190	190
191	191	191
192	192	192
193	193	193
194	194	194
195	195	195
196	196	196
197	197	197
198	198	198
199	199	199
200	200	200

COMMON FILTER SOCK TOTALS

NO.	AREA (SQ. FT.)	LENGTH (FT.)
201	201	201
202	202	202
203	203	203
204	204	204
205	205	205
206	206	206
207	207	207
208	208	208
209	209	209
210	210	210
211	211	211
212	212	212
213	213	213
214	214	214
215	215	215
216	216	216
217	217	217
218	218	218
219	219	219
220	220	220

AUB-54 COMPOST FILTER SOCK CALCULATIONS

NO.	AREA (SQ. FT.)	LENGTH (FT.)
221	221	221
222	222	222
223	223	223
224	224	224
225	225	225
226	226	226
227	227	227
228	228	228
229	229	229
230	230	230
231	231	231
232	232	232
233	233	233
234	234	234
235	235	235
236	236	236
237	237	237
238	238	238
239	239	239
240	240	240

AUB-54 COMPOST FILTER SOCK CALCULATIONS


NO.	AREA (SQ. FT.)	LENGTH (FT.)
241	241	241
242	242	242
243	243	243
244	244	244
245	245	245
246	246	246
247	247	247
248	248	248
249	249	249
250	250	250
251	251	251
252	252	252
253	253	253
254	254	254
255	255	255
256	256	256
257	257	257
258	258	258
259	259	259
260	260	260

AUB-54 COMPOST FILTER SOCK CALCULATIONS

NO.	AREA (SQ. FT.)	LENGTH (FT.)
261	261	261
262	262	262
263	263	263
264	264	264
265	265	265
266	266	266
267	267	267
268	268	268
269	269	269
270	270	270
271	271	271
272	272	272
273	273	273
274	274	274
275	275	275
276	276	276
277	277	277
278	278	278
279	279	279
280	280	280

AUB-54 COMPOST FILTER SOCK CALCULATIONS

NO.	AREA (SQ. FT.)	LENGTH (FT.)
281	281	281
282	282	282
283	283	283
284	284	284
285	285	285
286	286	286
287	287	287
288	288	288
289	289	289
290	290	290
291	291	291
292	292	292
293	293	293
294	294	294
295	295	295
296	296	296
297	297	297
298	298	298
299	299	299
300	300	300



PROPERTY

1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10

PROPERTY

1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10

PROPERTY

1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10

PROPERTY

1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10

PROPERTY

1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10

RECEIVED
 Department of
 Environmental Protection
 Office of Oil and Gas
 FEB 23 2016

4708510277



THIS DOCUMENT IS NOT TO BE USED FOR ANY OTHER PURPOSES WITHOUT THE WRITTEN CONSENT OF SLS.

AUB-54 FINAL
SITE PLAN
UNION DISTRICT
MITCHELL COUNTY, WV

DATE: 11-06-15
SCALE: 1" = 50'
DESIGNED BY: JMA
FILE NO: 7540
SHEET 4 OF 22
REV: 02-10-2016


May need additional

1/2
1/2
1/2
1/2
1/2



AUB-54 FINAL SITE PLAN

PROPOSED WELL NUMBERS: H2-WV513380, H3-WV513381, H4-WV513382, H5-WV513383, H6-WV513384, AND H8-WV514041




RECEIVED
Office of Oil and Gas

FEB 23 2016

WV Department of
Environmental Protection

AUB-54 FINAL SITE PLAN

PROPOSED WELL NUMBERS: H2-WV513380, H3-WV513381, H4-WV513382, H5-WV513383, H6-WV513384, AND H8-WV514041



MATCHLINE SHEET 6

THIS DOCUMENT WAS PREPARED BY JAMES LAND SURVEYING FOR EXE PRODUCTION COMPANY

AUB-54 FINAL SITE PLAN UNION DISTRICT RITCHIE COUNTY, WV

DATE 01-8-15
SCALE 1" = 50'
DESIGNED BY: KJH
FILE NO: 7500
SHEET 5 OF 22
REV: 02-10-2016



RECEIVED
 Office of Oil and Gas
 FEB 23 2016
 WV Department of
 Environmental Protection

4708510277

AUB-54 FINAL SITE PLAN

PROPOSED WELL NUMBERS: H2-WV513380, H3-WV513381, H4-WV513382, H5-WV513383, H6-WV513384, AND H8-WV514041




THIS DOCUMENT WAS PREPARED BY SMITH LAND SURVEYING FOR: EQT PRODUCTION COMPANY

AUB-54 FINAL SITE PLAN
UNION DISTRICT
RICHTIE COUNTY, WV

DATE: 11-6-15
SCALE: 1" = 50'
DESIGNED BY: KLR
FILE NO: 7560
SHEET 6 OF 22
REV: 02-10-2016

4708510277

MAG
2/19/16



RECEIVED
 Office of Oil and Gas
 FEB 23 2016
 WV Department of
 Environmental Protection

4708510277

0/10/16
C/MAC




AUB-54 FINAL
SITE PLAN
RITCHIE COUNTY, WV
UNION DISTRICT

DATE 11-8-15
SCALE 1" = 50'
DESIGNED BY KJH
FILE NO. 7589
SHEET 7 OF 22
REV. 02-10-2016

AUB-54 FINAL SITE PLAN

PROPOSED WELL NUMBERS: H2-WW513380, H3-WW513381, H4-WW513382, H5-WW513383, H6-WW513384, AND H8-WW514041



CHESTRY J. ADAMS
150 ACRES


MATCHLINE SHEET 6

MATCHLINE SHEET 8



AUB-54 FINAL SITE PLAN

PROPOSED WELL NUMBERS: H2-WV513380, H3-WV513381, H4-WV513382, H5-WV513383, H6-WV513384, AND H8-WV514041



THIS DOCUMENT WAS PREPARED BY SLS LAND SURVEYING FOR EXT PRODUCTION COMPANY

AUB-54 FINAL SITE PLAN
UNION DISTRICT
RITCHIE COUNTY, WV

DATE 11-6-15
SCALE 1" = 50'
DESIGNED BY KAJI
FILE NO. Y580
SHEET 8 OF 22
REV. 02-10-2016



4708510277

MAC
2/3/16

RECEIVED
Office of Oil and Gas
FEB 23 2016
Environmental Protection
Department of

