west virginia department of environmental protection

Office of Oil and Gas
601 57th Street SE
Charleston, WV 25304
(304) 926-0450
(304) 926-0452 fax

Earl Ray Tomblin, Governor
Randy C. Huffman, Cabinet Secretary
www.dep.wv.gov

August 28, 2015

WELL WORK PERMIT

Horizontal 6A Well

This permit, API Well Number: 47-9502280, issued to EQT PRODUCTION COMPANY, is evidence of permission granted to perform the specified well work at the location described on the attached pages and located on the attached plat, subject to the provisions of Chapter 22 of the West Virginia Code of 1931, as amended, and all rules and regulations promulgated thereunder, and to all conditions and provisions outlined in the pages attached hereto. Notification shall be given by the operator to the Oil and Gas Inspector at least 24 hours prior to the construction of roads, locations, and/or pits for any permitted work. In addition, the well operator shall notify the same inspector 24 hours before any actual well work is commenced and prior to running and cementing casing. Spills or emergency discharges must be promptly reported by the operator to 1-800-642-3074 and to the Oil and Gas inspector.

Please be advised that form WR-35, Well Operators Report of Well Work is to be submitted to this office within 90 days completion of permitted well work, as should form WR-34 Discharge Monitoring Report within 30 days of discharge of pits, if applicable. Failure to abide by all statutory and regulatory provisions governing all duties and operations hereunder may result in suspension or revocation of this permit and, in addition, may result in civil and/or criminal penalties being imposed upon the operators.

In addition to the applicable requirements of this permit, and the statutes and rules governing oil and gas activity in WV, this permit may contain specific conditions which must be followed. Permit conditions are attached to this cover letter.

Per 35CSR-4-5.2.g this permit will expire in two (2) years from the issue date unless permitted well work is commenced. If there are any questions, please feel free to contact me at (304) 926-0499 ext. 1654.

James Martin
Chief

Operator's Well No: 512892
Farm Name: PETER, DONNA J.
API Well Number: 47-9502280
Permit Type: Horizontal 6A Well
Date Issued: 08/28/2015

API Number: _____

PERMIT CONDITIONS 4709502280

West Virginia Code § 22-6A-8(d) allows the Office of Oil and Gas to place specific conditions upon this permit. Permit conditions have the same effect as law. Failure to adhere to the specified permit conditions may result in enforcement action.

CONDITIONS

1. This proposed activity may require permit coverage from the United States Army Corps of Engineers (USACE). Through this permit, you are hereby being advised to consult with USACE regarding this proposed activity.

2. If the operator encounters an unanticipated void, or an anticipated void at an unanticipated depth, the operator shall notify the inspector within 24 hours. Modifications to the casing program may be necessary to comply with W. Va. Code § 22-6A-5a (12), which requires drilling to a minimum depth of thirty feet below the bottom of the void, and installing a minimum of twenty (20) feet of casing. Under no circumstance should the operator drill more than one hundred (100) feet below the bottom of the void or install less than twenty (20) feet of casing below the bottom of the void.

3. When compacting fills, each lift before compaction shall not be more than 12 inches in height, and the moisture content of the fill material shall be within limits as determined by the Standard Proctor Density test of the actual soils used in specific engineered fill, ASTM D698, Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort, to achieve 95 % compaction of the optimum density. Each lift shall be tested for compaction, with a minimum of two tests per lift per acre of fill. All test results shall be maintained on site and available for review.

4. Operator shall install signage per § 22-6A-8g (6) (B) at all source water locations included in their approved water management plan within 24 hours of water management plan activation.

5. Oil and gas water supply wells will be registered with the Office of Oil and Gas and all such wells will be constructed and plugged in accordance with the standards of the Bureau for Public Health set forth in its Legislative rule entitled *Water Well Regulations,* 64 C.S.R. 19. Operator is to contact the Bureau of Public Health regarding permit requirements. In lieu of plugging, the operator may transfer the well to the surface owner upon agreement of the parties. All drinking water wells within fifteen hundred feet of the water supply well shall be flow tested by the operator upon request of the drinking well owner prior to operating the water supply well.

6. Pursuant to the requirements pertaining to the sampling of domestic water supply wells/springs the operator shall, no later than thirty (30) days after receipt of analytical data provide a written copy to the Chief and any of the users who may have requested such analyses.

7. If any explosion or other accident causing loss of life or serious personal injury occurs in or about a well or well work on a well, the well operator or its contractor shall give notice, stating the particulars of the explosion or accident, to the oil and gas inspector and the Chief, within 24 hours of said accident.

8. During the casing and cementing process, in the event cement does not return to the surface, the oil and gas inspector shall be notified within 24 hours.

9. Operator shall provide the Office of Oil & Gas notification of the date that drilling commenced on this well. Such notice shall be provided by sending an email to DEPOOGNotify@wv.gov within 30 days of commencement of drilling.

WW - 6B
(4/15)

4709502280

API NO. 47 - 095 -
OPERATOR WELL NO. 512892
Well Pad Name: WEU4

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
WELL WORK PERMIT APPLICATION

1) Well Operator: EQT Production Company

306686	095	1	671
Operator ID	County	District	Quadrangle

2) Operator's Well Number: 512892 Well Pad Name: WEU4

3) Farm Name/Surface Owner : Donna J. Peter Public Road Access: WV-18

4) Elevation, current ground: 1,098.0 Elevation, proposed post-construction: 1,078.0

5) Well Type: (a) Gas • Oil _____ Underground Storage _____

Other _____

(b) If Gas: Shallow • Deep _____

Horizontal •

Michael Duff
7/28/15

6) Existing Pad? Yes or No: No

7) Proposed Target Formation(s), Depth(s), Anticipated Thicknesses and Associated Pressure(s):

Target formation is Marcellus at a depth of 6680 with the anticipated thickness to be 54 feet and anticipated target pressure of 2747 PSI

8) Proposed Total Vertical Depth: 6680
9) Formation at Total Vertical Depth: Marcellus
10) Proposed Total Measured Depth: 11068
11) Proposed Horizontal Leg Length 3,790
12) Approximate Fresh Water Strata Depths: 139,182,193,211
13) Method to Determine Fresh Water Depth: By offset wells
14) Approximate Saltwater Depths: 1135, 1226, 1229
15) Approximate Coal Seam Depths: 239,292,707
16) Approximate Depth to Possible Void (coal mine, karst, other): None reported
17) Does proposed well location contain coal seams directly overlying or adjacent to an active mine? Yes _____ No x

(a) If Yes, provide Mine Info: Name: _____
Depth: _____
Seam: _____
Owner: _____

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

WW - 6B
(4/15)

4709502280

API NO. 47 - 095 -
OPERATOR WELL NO 512892
Well Pad Name. WEU4

CASING AND TUBING PROGRAM

18)

TYPE	Size (in)	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: For Drilling (ft)	INTERVALS: Left in Well (ft)	CEMENT: Fill- up (Cu.Ft.)
Conductor	20	New	MC-50	81	40	40	38 C.T.S.
Fresh Water	13 3/8	New	MC-50	54.5	361	361	336 C.T.S.
Coal	-	-	-	-	-	-	-
Intermediate	9 5/8	New	A-500	40	3,024	3,024	1,202 C.T.S.
Production	5 1/2	New	P-110	20	11,068	11,068	See Note 1
Tubing	2 3/8		J-55	4.6			May not be run. If run will be set 100 less than TD
Liners							

MAG
7/28/15

TYPE	Size (in)	Wellbore Diameter (in)	Wall Thickness (in)	Burst Pressure (psi)	Anticipated Max. Internal Pressure (psi)	Cement Type	Cement Yield (cu. ft./k)
Conductor	20	24	0.375	-	18	Construction	1.18
Fresh Water	13 3/8	17 1/2	0.38	2,730	2184	* See Note 2	1.21
Coal							
Intermediate	9 5/8	12 3/8	0.395	3,950	3160	* See Note 2	1.21
Production	5 1/2	8 1/2	0.361	12,640	10112	-	1.27/1.86
Tubing							
Liners							

Packers

Kind:	N/A			
Sizes:	N/A			
Depths Set:	N/A			

Note 1: EQT plans to bring the TOC on the production casing cement job 1,000' above kick off point, which is at least 500' above the shallowest production zone, to avoid communication.
Note 2: Reference Variance 2014-17. (Attached)

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

WW - 6B
(10/14)

4709502280

API NO. 47 - 095 -
OPERATOR WELL NO. 512892
Well Pad Name: WEU4

MDG
7/28/15

19) Describe proposed well work, including the drilling and plugging back of any pilot hole:

Drill and complete a new horizontal well in the Marcellus formation. The vertical drill to go down to an approximate depth of 4895'. Then kick off the horizontal leg into the Marcellus using a slick water frac.

20) Describe fracturing/stimulating methods in detail, including anticipated max pressure and max rate:

Hydraulic fracturing is completed in accordance with state regulations using water recycled from previously fractured wells and obtained from freshwater sources. This water is mixed with sand and a small percentage (less than 0.3%) of chemicals (including 15% Hydrochloric acid, gelling agent, gel breaker, friction reducer, biocide, and scale inhibitor), referred to in the industry as a "slickwater" completion. Maximum anticipated internal casing pressures is expected to average approximately 8500 psi, maximum anticipated treating rates are expected to average approximately 100 bpm. Stage lengths vary from 150 to 300 feet. Average approximately 200,000 barrels of water per stage. Sand sizes vary from 100 mesh to 20/40 mesh. Average approximately 200,000 pounds of sand per stage.

21) Total area to be disturbed, including roads, stockpile area, pits, etc, (acres): 19.18

22) Area to be disturbed for well pad only, less access road (acres): 13.17

23) Describe centralizer placement for each casing string.

- Surface: Bow spring centralizers – One at the shoe and one spaced every 500'.
- Intermediate: Bow spring centralizers– One cent at the shoe and one spaced every 500'.
- Production: One spaced every 1000' from KOP to Int csg shoe

24) Describe all cement additives associated with each cement type.

Surface (Type 1 Cement): 0-3% Calcium Chloride Used to speed the setting of cement slurries. 0.4% flake. Loss Circulation Material (LCM) is used to combat the loss of the cement slurry to a thief zone.

Intermediate (Type 1 Cement): 0-3% Calcium Chloride. Salt is used in shallow, low temperature formations to speed the setting of cement slurries. 0.4% flake. Loss Circulation Material (LCM) is used to combat the loss of whole drilling fluid or cement slurry (not filtrate) to a thief zone.

Production:

Lead (Type 1 Cement): 0.2-0.7% Lignosulfonate (Retarder). Lengthens thickening time.
0.3% CFR (dispersant). Makes cement easier to mix.

Tail (Type H Cement): 0.25-0.40% Lignosulfonate (Retarder). Lengthens thickening time.
0.2-0.3% CFR (dispersant). This is to make the cement easier to mix.
60 % Calcuim Carbonate. Acid solubility.
0.4-0.6% Halad (fluid loss). Reduces amount of water lost to formation.

25) Proposed borehole conditioning procedures.

Surface: Circulate hole clean (Approximately 30-45 minutes) rotating & reciprocating one full joint until cuttings diminish at surface. When cuttings returning to surface diminish, continue to circulate an additional 5 minutes. To ensure that there is no fill, short trip two stands with no circulation. If there is fill, bring compressors back on and circulate hole clean. A constant rate of higher than expected cuttings volume likely indicates washouts that will not clean up.

Intermediate: Circulate hole clean (Approximately 30-45 minutes) rotating & reciprocating one full joint until cuttings diminish at surface. When cuttings returning to surface diminish, continue to circulate an additional 5 minutes. If foam drilling, to enhance hole cleaning use a soap sweep or increase injection rate & foam concentration.

Production: Pump marker sweep with nut plug to determine actual hole washout. Calculate a gauge holes bottoms up volume. Perform a cleanup cycle by pumping 3-5 bottoms up or until the shakers are clean. Check volume of cuttings coming across the shakers every 15 minutes.

*Note: Attach additional sheets as needed.

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

4709502280

Well 512892(WEU4H3)
EQT Production
West Union
Tyler West Virginia



Proposed Well Work
Drill and complete a new horizontal well in the formation
The vertical drill to go down to an approximate depth of 4695'
Then kick off the horizontal leg into the using a slick water frac

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection
7/28/15

4709502280

Well Schematic
EQT Production

Well Name	512882(WEU4H3)
County	Tyler
State	West Virginia

Elevation KB	1009'
Target	Marcellus
Prospect	
Azimuth	335
Vertical Section	3752





MAC
7/28/15

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

west virginia department of environmental protection

Office of Oil and Gas
601 57th Street, SE
Charleston, WV 25304
(304) 926-0450
(304) 926-0452 fax

Earl Ray Tomblin, Governor
Randy C. Huffman, Cabinet Secretary
dep.wv.gov

March 18, 2014

Nabors Completion & Production Services Company
1380 Route 286 Hwy E #121
Indiana PA 15701

4709502280

Re: Cement Variance Request

Dear Sir or Madam,

This agency is approving a variance request for the cement blend listed below to be used on surface and coal protection strings for the drilling of oil and gas wells in the state of West Virginia. The variance cannot be used without requesting its use on a permit application and approval by this agency:

- Type 1 (2% Calcium Chloride-Accelerator, 0.25% Super Flake-Lost Circulation, 5.2% Water, 94% Type "1" Cement)

If you have any questions regarding this matter feel free to contact me at 304-926-0499, ext. 1653.

Sincerely,

James Peterson by GCS

James Peterson
Environmental Resources Specialist / Permitting

west virginia department of environmental protection

Office of Oil and Gas
601 57th Street, SE
Charleston, WV 25304
(304) 926-0450
(304) 926-0452 fax

Earl Ray Tomblin, Governor
Randy C. Huffman, Cabinet Secretary
dep.wv.gov

BEFORE THE OFFICE OF OIL AND GAS
DEPARTMENT OF ENVIRONMENTAL PROTECTION
STATE OF WEST VIRGINIA

IN THE MATTER OF A VARIANCE FROM	)	**ORDER NO. 2014 - 17**
REGULATION 35 CSR § 4-11.4/11.5/14.1	)	
AND 35 CSR § 8-9.2.h. 4/5/6/8 OF THE	)	
THE OPERATIONAL	)	
REGULATIONS OF CEMENTING OIL	)	
AND GAS WELLS	)	

4709502280

REPORT OF THE OFFICE

Nabors Completion & Production Services Co. requests approval of a different cement blend for use in cementing surface and coal protection casing of oil and gas wells.

FINDINGS OF FACT

1.) Nabors Completion & Production Services Co. proposes the following cement blend:

- 2% Calcium Chloride (Accelerator)
- 0.25 % Super Flake (Lost Circulation)
- 94% Type "1" Cement
- 5.20 % Water

2.) Laboratory testing results indicate that the blend listed in Fact No.1 will achieve a 500 psi compressive strength within 6 hours and a 2,435 psi compressive strength within 24 hours.

RECEIVED
Office of Oil and Gas

JUN 25 2015

WV Department of
Environmental Protection

CONCLUSIONS OF LAW

Pursuant to Articles 6 and 6A, Chapter 22 of the Code of West Virginia, the Office of Oil and Gas has jurisdiction over the subject matter embraced in said notice, and the persons interested therein, and jurisdiction to promulgate the hereinafter prescribed Order.

Pursuant to 35 CSR § 4-11.5 and 35 CSR § 8-9.2.h.8 the Chief of the Office of Oil and Gas may approve different cement blends upon the well operator providing satisfactory proof that different cement types are adequate.

ORDER

It is ordered that Nabors Completion & Production Services Co. may use the cement blend listed in Findings of Fact No.1 for the cementing of surface and coal protection casing of oil and gas wells in the State as may be requested by oil and gas operators. The waiting time on the cement blend shall be 8 hours. The cement blend shall be mixed in strict accordance with the specifications for each blend and weight measurements made on-site to assure the cement slurries meet the minimum weight specifications. A sample shall be collected and, if after 8 hours the cement is not set up, additional time will be required. Nabors Completion & Production Services Co. shall keep a record of cement blend jobs in which the cement blend approved under this order is to be used and made available to the Office of Oil and Gas upon request.

4709502280

Dated this, the 18th day of March, 2014.

IN THE NAME OF THE STATE OF WEST VIRGINIA

OFFICE OF OIL AND GAS
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OF THE STATE OF WEST VIRGINIA

James Martin, Chief
Office of Oil and Gas

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

May 12, 2015

4709502200

Mr. Gene Smith
West Virginia Department of Environmental Protection
Office of Oil and Gas
601 57th Street SE
Charleston, WV 25304

Re: Casing change on WEU4 (512890, 512891, 512893, 512894, 512895)

Dear Mr. Smith,

EQT is requesting the 13 3/8" surface casing to be set at 361' KB, 150' below the deepest fresh water. We will set the 9-5/8" intermediate string at 3024' KB, 50' below the base of the Fifth Sand.

If you have any questions, please do not hesitate to contact me at (304) 848-0076.

Sincerely,

Vicki Roark
Permitting Supervisor-WV

Enc.

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

WW-9
(2/15)

API No. 47 - 095 - 02280
Operator's Well No. 512892

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS
Fluids/Cuttings Disposal & Reclamation Plan

Operator Name EQT Production Company OP Code 306686

Watershed (HUC10) Tributary of Camp Mistake Run Quadrangle West Union 7.5'

Do you anticipate using more than 5,000 bbls of water to complete the proposed well work? Yes x No ___

Will a pit be used ? Yes: X No: ___

If so please describe anticipated pit waste: flowback water & residual solids

Will a synthetic liner be used in the pit? Yes X No ___ If so, what ml.? 60

Proposed Disposal Method For Treated Pit Wastes:

___ Land Application
• Underground Injection (UIC Permit Number 0014, 8462, 4037)
• Reuse (at API Number Various)
• Off Site Disposal (Supply form WW-9 for disposal location)
___ Other (Explain)

Will closed loop system be used ? Yes. The closed loop system will remove drill cuttings from the drilling fluid. The drill cuttings are then prepared for transportation to an off-site disposal facility.

Drilling medium anticipated for this well (vertical and horizontal)? Air, freshwater, oil based, etc.

Air is used to drill the top hole sections of the wellbore (surface, intermediate, and pilot). Water based mud may be necessary depending on hole conditions to stabilize and drill the intermediate section. The pilot hole, curve, and lateral sections will be drilled with either air, water based mud, or oil based mud.

- If oil based, what type? Synthetic, petroleum, etc Synthetic mud

Additives to be used in drilling medium? Air - biodegradable oil lubricant , detergent, defoaming, water. Water based mud - Barite, viscosifier, alkalinity control, lime, filtration control, deflocculates, biodegradable oil lubricant , defoaming, walnut shell, salt, x-cide, carbonates. Oil based mud – synthetic base oil, emulsifier, salt, lime, viscosifier, alkalinity control, filtration control, deflocculates, biodegradable oil lubricant , defoaming, carbonates.

Drill cuttings disposal method? Leave in pit, landfill, removed offsite, etc. Landfill

- If left in pit and plan to solidify what medium will be used? (Cement, Lime, sawdust) n/a
- Landfill or offsite name/permit number? See Attached List

Permittee shall provide written notice to the Office of Oil and Gas of any load of drill cuttings or associated waste rejected at any West Virginia solid waste facility. The notice shall be provided within 24 hours of rejection and the permittee shall also disclose where it was properly disposed.

I certify that I understand and agree to the terms and conditions of the GENERAL WATER POLLUTION PERMIT issued on August 1, 2005, by the Office of Oil and Gas of the West Virginia Department of Environmental Protection. I understand that the provisions of the permit are enforceable by law. Violations of any term or condition of the general permit and/or other applicable law or regulation can lead to enforcement action.

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this application form and all attachments thereto and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine or imprisonment.

Company Official Signature
Company Official (Typed Name) Victoria J. Roark
Company Official Title Permitting Supervisor

Subscribed and sworn before me this 29th day of July, 20 15

Rebecca L Heater Notary Public

My commission expires 4-7-20

OFFICIAL SEAL
NOTARY PUBLIC
STATE OF WEST VIRGINIA
REBECCA L. HEATER
EQT PRODUCTION COMPANY
PO BOX 280
BRIDGEPORT, WV 26330
My commission expires April 07, 2020

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

Form WW-9

47095022 80

Operator's Well No. 512892

Proposed Revegetation Treatment: Acres Disturbed 19.18 Prevegetation pH 6.3

Lime 3 Tons/acre or to correct to pH 6.5

Fertilize type Granular 10-20-20

Fertilizer Amount 1/3 lbs/acre (500 lbs minimum)

Mulch 2 Tons/acre

Seed Mixtures

Temporary		Permanent	
Seed Type	lbs/acre	Seed Type	lbs/acre
KY-31	40	Orchard Grass	15
Alsike Clover	5	Alsike Clover	5
Annual Rye	15		

Attach:
Drawing(s) of road, location,pit and proposed area for land application.

Photocopied section of involved 7.5' topographic sheet.

Plan Approved by: Michael Duff

Comments: Preseed & Mulch any disturbed areas per WVDEP regulations. Maintain & Upgrade E+S as necessary.

Title: Oil & Gas Inspector Date: 7/28/15

Field Reviewed? (✓) Yes ( ) No

RECEIVED
Office of Oil and Gas
JUL 29
WV Department of
Environmental Protection

Form WW-9

W.H. ASH ET AL LEASE WEU4 WELLS

page of

4709502280



NOTE: SEE SITE PLAN WEU4 FOR COMPLETE CONSTRUCTION & EROSION & SEDIMENT CONTROL DETAILS.

RECEIVED
Office of Oil and Gas
JUN 29 2015
WV Department of Environmental Protection

Professional Energy Consultants
A DIVISION OF SMITH LAND SURVEYING, INC.
SLS
SURVEYING ENGINEERING ENVIRONMENTAL PROJECT MGMT

DRAWN BY	FILE NO.	DATE	CADD FILE
K.D.W.	7701	06-18-15	

TOPO SECTIONS OF WEST UNION 7.5' TOPO QUADRANGLE

SHEET 1 OF 2
SCALE: 1"=500'

0' 500' 1000'

MAG
7/28/15

Form WW-9

W.H. ASH ET AL LEASE WEU4 WELLS

page of

4709502280



Professional Energy Consultants

SLS

DRAWN BY	FILE NO.	DATE	CADD FILE
K.D.W.	7701	06-18-15	

TOPO SECTIONS OF WEST UNION 7.5' TOPO QUADRANGLE

MAG
7/28/15

EQT Production Water plan
Offsite disposals for Marcellus wells

CWS TRUCKING INC.
P.O. Box 391
Williamstown, WV 26187
740-516-3586
Noble County/Noble Township
Permit # 3390

LAD LIQUID ASSETS DISPOSAL INC.
226 Rankin Road
Washington, PA 15301
724-350-2760
724-222-6080
724-229-7034 fax
Ohio County/Wheeling
Permit # USEPA WV 0014

TRI COUNTY WASTE WATER MANAGEMENT, INC.
1487 Toms Run Road
Holbrook, PA 15341
724-627-7178 Plant
724-499-5647 Office
Greene County/Waynesburg
Permit # TC-1009

Waste Management - Meadowfill Landfill
Rt. 2, Box 68 Dawson Drive
Bridgeport, WV 26330
304-326-6027
Permit #SWF-1032-98
Approval #100785WV

Waste Management - Northwestern Landfill
512 E. Dry Road
Parkersburg, WV 26104
304-428-0602
Permit #SWF-1025 WV-0109400
Approval #100833WV

BROAD STREET ENERGY LLC
37 West Broad Street
Suite 1100
Columbus, Ohio 43215
740-516-5381
Washington County/Belpre Twp.
Permit # 8462

4709502280

TRIAD ENERGY
P.O. Box 430
Reno, OH 45773
740-516-6021 Well
740-374-2940 Reno Office Jennifer
Nobel County/Jackson Township
Permit # 4037

KING EXCAVATING CO.
Advanced Waste Services
101 River Park Drive
New Castle, Pa. 16101
Facility Permit# PAR000029132

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

4709502280

EQT

Where energy meets innovation.™

Site Specific Safety Plan

EQT WEU 4 Pad

Alma
Tyler County, WV

For Wells:

512892

Date Prepared: May 6, 2015

RECEIVED
Office of Oil and Gas
MAY 20 2015
WV Department of
Environmental Protection

EQT Production

Drilling Supervisor
Title

6-23-15
Date

WV Oil and Gas Inspector

Title

7/22/15
Date



EQT

EQT Production
White Oaks Office
120 Professional Place
Bridgeport WV 26330

Site Safety Plan

WEU4
One Mile Safety Buffer
Tyler County, WV

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of Protection

MAC
7/28/15

WATER SOURCE LOCATIONS FOR W.H. ASH ET AL LEASE WEU4 WELLS



RECEIVED
Office of Oil and Gas
JUN 15 2015
WV Department of
Environmental Protection

Professional Energy Consultants
A DIVISION OF SMITH LAND SURVEYING INC.
SLS Surveying Engineering Environmental Project Mgmt.

DRAWN BY	FILE NO.	DATE	CADD FILE
K.D.W.	7701	05/27/15	7701WSHEU4.dwg

TOPO SECTION OF:
WEST UNION, WV 7.5' QUAD

DISTRICT	COUNTY	TAX MAP-PARCEL NO.
CENTERVILLE	TYLER	16-22

OPERATOR:
EQT PRODUCTION COMPANY
115 PROFESIONAL PLACE
P.O. BOX 280
BRIDGEPORT, WV 26330

FORM WW 6

8,237'

LATITUDE 39°22'30"

LONGITUDE 80°47'30"

3,102'

NAD '27 GRID NORTH

NOTES ON SURVEY

1. NO WATER WELLS WERE FOUND WITHIN 250' OF PROPOSED GAS WELL. NO AGRICULTURAL BUILDINGS ≥ 2500 SQ. FT. OR DWELLINGS WERE FOUND WITHIN 625' OF THE CENTER OF PROPOSED WELL PAD.

EQT PRODUCTION COMPANY
W.H. ASH ET AL LEASE
152 ACRES±
WELL NO. WV 512892

(S.P.C. NORTH ZONE) (UTM(M) ZONE 17 NORTH)

NAD'27 S.P.C.(FT)	N. 318,336.31	E. 1,626,585.65
NAD'27 GEO.	LAT-(N) 39.366485	LONG-(W) 80.820801
NAD'83 UTM (M)	N. 4,357,471.45	E. 515,451.62
LANDING POINT		
NAD'27 S.P.C.(FT)	N. 318,046.31	E. 1,626,140.19
NAD'27 GEO.	LAT-(N) 39.365671	LONG-(W) 80.822361
NAD'83 UTM (M)	N. 4,357,380.83	E. 515,317.39
BOTTOM HOLE		
NAD'27 S.P.C.(FT)	N. 321,480.77	E. 1,624,538.68
NAD'27 GEO.	LAT-(N) 39.375034	LONG-(W) 80.828205
NAD'83 UTM (M)	N. 4,358,419.00	E. 514,812.03





LEGEND

LEASE LINE	
SURFACE LINE	
WELL LATERAL	
OFFSET LINE	
TIE LINE	
CREEK	
ROAD	
FENCE LINE	
COUNTY ROUTE	
PROPOSED WELL	
EXISTING WELL	
PERMITTED WELL	
ABANDONED WELL	
PLUGGED WELL	
STORAGE WELL	
CENTERVILLE DISTRICT TAX MAP–PARCEL	C–00–00
McELROY DISTRICT TAX MAP–PARCEL	M–00–00

CORNER TIES	BEARING & DISTANCE	
L1	N 66°30' E	1378.26'
L2	S 34°20' E	646.40'

LATERAL PATH	BEARING & DISTANCE	
L3	S 56°56' W	531.54'
L4	N 25°00' W	3789.50'

A	BRADLEY D. DAVIS	2.73 AC.±	
B	WILLIAM DOLL ET AL.	0.50 AC.±	
C	WILLIAM DOLL ET AL.	0.49 AC.±	
D	WILLIAM DOLL	1 AC.±	
E	FRIEDERIKE DOHRMANN	7.067 AC.±	
F	WILBUR COMMUNITY CLUB	0.95 AC.±	
G	JOHN STARKEY	7.888 AC.±	
H	CHRIS A. BAUM ET AL	0.84 AC.±	
I	TERRY G. WEEKLEY	1.182 AC.±	
J	RUTH O. & OLIN T. DOLL	1 AC.±	
K	GARY PROSSER	0.50 AC.±	
L	GARY & BARBARA PROSSER	2.50 AC.±	
M	HOWARD SHRIVER ET AL	24.84 AC.±	TM C-16-16
N	CONRAD COSTILOW	46.17 AC.±	TM C-16-14
O	RICHARD & YVONNE METCALF	0.61 AC.±	
P	JOHN & SANDRA ANDERS	0.09 AC.±	
Q	ELIZABETH ABRUZZINO	109.94 AC.±	
R	L.B. & SANDRA STONEKING	42.86 AC.±	
S	PERRY J. HAUGHT	16.21 AC.±	
T	BILLY J. DOLL	0.58 AC.±	
U	KATHLEEN WINKELMANN	0.88 AC.±	
V	CHRIS A. BAUM	13 AC.±	
W	CHRIS A. BAUM	14 AC.±	
X	WILBUR CEMETERY	2 AC.±	
Y	WILBUR CHAPEL	0.84 AC.±	
Z	WILBUR CEMETERY COMMUNITY INC.	0.197 AC.±	

ROYALTY OWNERS		
FANCY M. MERCER ET AL	25 AC.±	LEASE NO. 126143
ROSA B. CRESS ET AL	47 AC.±	LEASE NO. 126144

REFERENCES



Professional Energy Consultants
A DIVISION OF SMITH LAND SURVEYING, INC.
SLS
SURVEYORS ENGINEERS ENVIRONMENTAL PROJECT MGMT.
(304) 462-8474 WWW.SLSSURVEYS.COM

I THE UNDERSIGNED, HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF AND SHOWS ALL THE INFORMATION REQUIRED BY LAW AND THE REGULATIONS ISSUED AND PRESCRIBED BY THE DIVISION OF ENVIRONMENTAL PROTECTION.

P.S. 849 C. Victor Moyers

C. VICTOR MOYERS LICENSED No. 849 STATE OF WEST VIRGINIA PROFESSIONAL SURVEYOR

(+) DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS.

DATE SEPTEMBER 03 , 20 14

REVISED 06/04/15 & 06/18/15

OPERATORS WELL NO. WV 512892

API WELL NO. 47 — 095 — 02280 H6A
STATE COUNTY PERMIT

MINIMUM DEGREE OF ACCURACY 1 / 2500 FILE NO. 7701P512892R2

SCALE 1" = 2000'

HORIZONTAL & VERTICAL CONTROL DETERMINED BY DGPS (SURVEY GRADE TIE TO CORS NETWORK)

STATE OF WEST VIRGINIA
DIVISION OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

WELL TYPE: OIL ___ GAS X LIQUID INJECTION ___ WASTE DISPOSAL ___ IF "GAS" PRODUCTION X STORAGE ___ DEEP ___ SHALLOW X

LOCATION :

ELEVATION 1,098'(GROUND)1,078'(PROPOSED) WATERSHED TRIBUTARY OF CAMP MISTAKE RUN

DISTRICT CENTERVILLE COUNTY TYLER QUADRANGLE WEST UNION 7.5'

SURFACE OWNER DONNA J. PETER ACREAGE 113.40±

ROYALTY OWNER WACO OIL & GAS CO. INC. ET AL ACREAGE 152±

PROPOSED WORK : LEASE NO. 126129

DRILL X CONVERT ___ DRILL DEEPER ___ REDRILL ___ FRACTURE OR STIMULATE X PLUG OFF OLD FORMATION ___ PERFORATE NEW FORMATION ___ PLUG AND ABANDON ___ CLEAN OUT AND REPLUG ___ OTHER ___

PHYSICAL CHANGE IN WELL (SPECIFY) ___ TARGET FORMATION MARCELLUS

ESTIMATED DEPTH TVD 6,696'

COUNTY NAME

PERMIT

WELL OPERATOR EQT PRODUCTION COMPANY DESIGNATED AGENT REX C. RAY

ADDRESS 115 PROFESSIONAL PLACE P.O. BOX 280 BRIDGEPORT, WV 26330

ADDRESS 115 PROFESSIONAL PLACE P.O. BOX 280 BRIDGEPORT, WV 26330

WW-6A1
(5/13)

Operator's Well No. 512892

INFORMATION SUPPLIED UNDER WEST VIRGINIA CODE
Chapter 22, Article 6A, Section 5(a)(5)
IN LIEU OF FILING LEASE(S) AND OTHER CONTINUING CONTRACT(S)

Under the oath required to make the verification on page 1 of this Notice and Application, I depose and say that I am the person who signed the Notice and Application for the Applicant, and that -

(1) the tract of land is the same tract described in this Application, partly or wholly depicted in the accompanying plat, and described in the Construction and Reclamation Plan;

(2) the parties and recordation data (if recorded) for lease(s) or other continuing contract(s) by which the Applicant claims the right to extract, produce or market the oil or gas are as follows:

Lease Name or Number	Grantor, Lessor, etc.	Grantee, Lessee, etc.	Royalty	Book/Page
126129			Min 1/8 pd	
	William A. Ash, et al	Equitable Gas Company		DB191/321
	Equitable Gas Company	Equitrans,Inc.		DB274/471
	Equitrans, Inc.	Equitable Production Company		DB396/640
	Equitable Production Company	EQT Production Company		DB281/346 Doddridge Co.
126143			Min 1/8 pd	
	Fanny Davis, et al	Equitable Gas Company		DB191/519
	Equitable Gas Company	Equitrans, Inc.		DB274/471
	Equitrans, Inc.	Equitable Production Company		DB396/640
	Equitable Production Company	EQT Production Company		DB281/346 Doddridge Co.
126144			Min 1/8 pd	
	Fanny Davis, et al	EQT Production Company		DB191/511
	Equitable Gas Company	Equitrans, Inc.		DB274/471
	Equitrans, Inc.	Equitable Production Company		DB396/640
	Equitable Production Company	EQT Production Company		DB281/346 Doddridge Co.

Upon information and belief, Operator's lease and/or other real property rights permit it to conduct drilling operations for the subject well in the location shown on the plat, including under any public roads that the well lateral crosses.

Acknowledgement of Possible Permitting/Approval In Addition to the Office of Oil and Gas

The permit applicant for the proposed well work addressed in this application hereby acknowledges the possibility of the need for permits and/or approvals from local, state, or federal entities in addition to the DEP, Office of Oil and Gas, including but not limited to the following:

- WV Division of Water and Waste Management
- WV Division of Natural Resources WV Division of Highways
- U.S. Army Corps of Engineers
- U.S. Fish and Wildlife Service
- County Floodplain Coordinator

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

The applicant further acknowledges that any Office of Oil and Gas permit in no way overrides, replaces, or nullifies the need for other permits/approvals that may be necessary and further affirms that all needed permits/approvals should be acquired from the appropriate authority before the affected activity is initiated.

appropriate authority before the affected activity is initiated.

Well Operator: EQT Production Company
By:
Its: Permitting Supervisor

WW-6AC
(1/12)

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE CERTIFICATION

Date of Notice Certification: _____

API No. 47 - 095 - 0
Operator's Well No. 512892
Well Pad Name: WEU4

4709502886

Notice has been given:

Pursuant to the provisions in West Virginia Code § 22-6A, the Operator has provided the required parties with the Notice Forms listed below for the tract of land as follows:

State:	WV	UTM NAD 83 Easting:	515,451.62
County:	Tyler	UTM NAD 83 Northing:	4,357,471.45
District:	Centerville	Public Road Access:	WV-18
Quadrangle:	West Union 7.5'	Generally used farm name:	Donna J. Peter
Watershed:	Tributary of Camp Mistake Run		

Pursuant to West Virginia Code § 22-6A-7(b), every permit application filed under this section shall be on a form as may be prescribed by the secretary, shall be verified and shall contain the following information: (14) A certification from the operator that (i) it has provided the owners of the surface described in subdivisions (1), (2) and (4), subsection (b), section ten of this article, the information required by subsections (b) and (c), section sixteen of this article; (ii) that the requirement was deemed satisfied as a result of giving the surface owner notice of entry to survey pursuant to subsection (a), section ten of this article six-a; or (iii) the notice requirements of subsection (b), section sixteen of this article were waived in writing by the surface owner; and Pursuant to West Virginia Code § 22-6A-11(b), the applicant shall tender proof of and certify to the secretary that the notice requirements of section ten of this article have been completed by the applicant.

Pursuant to West Virginia Code § 22-6A, the Operator has attached proof to this Notice Certification that the Operator has properly served the required parties with the following:	OOG OFFICE USE ONLY
*PLEASE CHECK ALL THAT APPLY	
☐ NOTICE OF SEISMIC ACTIVITY or ☑ NOTICE NOT REQUIRED BECAUSE NO SEISMIC ACTIVITY WAS CONDUCTED	☐ RECEIVED/NOT REQUIRED
☑ NOTICE OF ENTRY FOR PLAT SURVEY or ☐ NO PLAT SURVEY WAS CONDUCTED	☐ RECEIVED
☐ NOTICE OF INTENT TO DRILL or ☑ NOTICE NOT REQUIRED BECAUSE NOTICE OF ENTRY FOR PLAT SURVEY WAS CONDUCTED OR	☐ RECEIVED/NOT REQUIRED
☐ WRITTEN WAIVER BY SURFACE OWNER (PLEASE ATTACH)	
☑ NOTICE OF PLANNED OPERATION	☐ RECEIVED
☑ PUBLIC NOTICE	☐ RECEIVED
☑ NOTICE OF APPLICATION	☐ RECEIVED

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

Required Attachments:

The Operator shall attach to this Notice Certification Form all Notice Forms and Certifications of Notice that have been provided to the required parties and/or any associated written waivers. For the Public Notice, the operator shall attach a copy of the Class II Legal Advertisement with publication date verification or the associated Affidavit of Publication. The attached Notice Forms and Certifications of Notice shall serve as proof that the required parties have been noticed as required under West Virginia Code § 22-6A. Pursuant to West Virginia Code § 22-6A-11(b), the Certification of Notice to the person may be made by affidavit of personal service, the return receipt card or other postal receipt for certified mailing.

WW-6AC
(1/12)

Certification of Notice is hereby given:

THEREFORE, I _____, have read and understand the notice requirements within West Virginia Code § 22-6A. I certify that as required under West Virginia Code § 22-6A, I have served the attached copies of the Notice Forms, identified above, to the required parties through personal service, by registered mail or by any method of delivery that requires a receipt or signature confirmation. I certify under penalty of law that I have personally examined and am familiar with the information submitted in this Notice Certification and all attachments, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

4708502280

Well Operator:	EQT Production Company	Address:	P.O. Box 280
By:	Victoria J. Roark		Bridgeport, WV 26330
Its:	Permitting Supervisor	Facsimile:	304-848-0040
Telephone:	304-848-0076	Email:	vroark@eqt.com

OFFICIAL SEAL
NOTARY PUBLIC
STATE OF WEST VIRGINIA
NOTARY SEAL REBECCA L. HEATER
EQT PRODUCTION COMPANY
PO BOX 280
BRIDGEPORT, WV 26330
My commission expires April 07, 2020

Subscribed and sworn before me this 24 day of June ,2015

Rebecca L Heater Notary Public

My Commission Expires 4-7-20

Oil and Gas Privacy Notice:

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at depprivacyofficer@wv.gov.

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

4709502280

SMITH LAND SURVEYING, INC. P.O. BOX 150, GLENVILLE, WV 26351
(304) 462-5634 • FAX 462-5656

WELL INFORMATION AND POTENTIAL WATER WELL SAMPLE DATA SHEET

OPERATOR: *EQT Production Company*
LEASE NAME AND NUMBER: *WEU-4*

COMMENTS

The initial field and/or mapping review of the area surrounding the proposed well site revealed the below listed surface owner(s) that were potentially utilizing groundwater (potable) for Human Consumption or other purposes within 2500' of the proposed well site. (For location of each site see attached area map.)

INDIVIDUAL CONTACTED OR NOTIFIED

Site: *1* Spacing *1220'* Owner/Occupant: *Donna Peter*
Address: *733 ridge rd. Wilbur, WV 26320* Ph: *(304)-758-4495*
Field Contact Date: *04/23/2015* Located: *Yes* Date Located: *04/23/2015* Source: *Water Well*
If No, declined by who _____ Letter/Notice Date: 1st *04/09/2015* 2nd *04/23/2015* Certified (3rd) *04/17/2015*
Comments: *Lat : 39.369336*
Long : 80.823230
Tax Map 16, Parcel 22

Site: *2* Spacing *1075'* Owner/Occupant: *Donna Peter*
Address: *733 ridge rd. Wilbur, WV 26320* Ph: *(304)-758-4495*
Field Contact Date: *04/23/2015* Located: *Yes* Date Located: *04/23/2015* Source: *Water Well*
If No, declined by who _____ Letter/Notice Date: 1st *04/09/2015* 2nd *04/23/2015* Certified (3rd) *04/17/2015*
Comments: *Lat : 39.369112*
Long : 80.822699
Tax Map 16, Parcel 22

Site: *3* Spacing *1030'* Owner/Occupant: *Donna Peter*
Address: *733 ridge rd. Wilbur, WV 26320* Ph: *(304)-758-4495*
Field Contact Date: *04/23/2015* Located: *Yes* Date Located: *04/23/2015* Source: *Spring*
If No, declined by who _____ Letter/Notice Date: 1st *04/09/2015* 2nd *04/23/2015* Certified (3rd) *04/17/2015*
Comments: *Lat : 39.365439*
Long : 80.823990
Tax Map 16, Parcel 22

Site: *4* Spacing *2050'* Owner/Occupant: *Bruce Stoneking*
Address: *RR 1 Box 304 BB Elkins, WV 26241* Ph: _____
Field Contact Date: *04/23/2015* Located: *Yes* Date Located: *04/23/2015* Source: *Water Well*
If No, declined by who _____ Letter/Notice Date: 1st *04/09/2015* 2nd *04/23/2015* Certified (3rd) *04/17/2015*
Comments: *Lat : 39.370837*
Long : 80.815910
Tax Map 21, Parcels 28 and 29

Received
Office of Oil & Gas
JUL 06 2015

Site: 5 Spacing 1425' Owner/Occupant Bruce Stoneking
Address: RR 1 Box 304 BB Elkins, WV 26241 Ph:
Field Contact Date: 04/23/2015 Located: Yes Date Located 04/23/2015 Source Water Well
If No, declined by who _____ Letter/Notice Date 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.370270
Long : 80.818867
Tax Map 21, Parcels 28 and 29

Site: 6 Spacing 2830' Owner/Occupant: Edward and Carolyn White
Address: 4316 Teen Barnes Rd. Jefferson, MD 21755 Ph: (301)-371-8521
Field Contact Date: 05/20/2015 Located: Yes Date Located 05/20/2015 Source: Water Well
If No, declined by who _____ Letter/Notice Date 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments Lat : 39.368035
Long : 80.810833
Tax Map 21, Parcel 38

Site: 7 Spacing 2070' Owner/Occupant: Edward and Carolyn White
Address: 4316 Teen Barnes Rd. Jefferson, MD 21755 Ph: (301)-371-8521
Field Contact Date: 05/20/2015 Located: Yes Date Located: 05/20/2015 Source: Water Well
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.366470
Long : 80.813358
Tax Map 21, Parcel 38

Site: 8 Spacing 2540' Owner/Occupant Edward and Carolyn White
Address: 4316 Teen Barnes Rd. Jefferson, MD 21755 Ph: (301)-371-8521
Field Contact Date: 05/20/2015 Located: Yes Date Located 05/20/2015 Source: Pond
If No, declined by who _____ Letter/Notice Date 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.365666
Long : 80.811781
Tax Map 21, Parcel 38

Site: 9 Spacing 2665' Owner/Occupant: Edward and Carolyn White
Address: 4316 Teen Barnes Rd. Jefferson, MD 21755 Ph: (301)-371-8521
Field Contact Date: 05/20/2015 Located: Yes Date Located 05/20/2015 Source: Pond
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.366163
Long : 80.811260
Tax Map 21, Parcel 38

Site: 10 Spacing 3655' Owner/Occupant: Frank and Elizabeth Abruzzino
Address 91 Springhill Chapel Rd, Clarksburg, WV 26301 Ph: (304)-669-3892
Field Contact Date: 05/20/2015 Located: Yes Date Located 05/20/2015 Source: Pond
If No, declined by who _____ Letter/Notice Date 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.376041
Long : 80.825199
Tax Map 16, Parcel 10

Received
Office of Oil & Gas
JUL 06 2015

Site: 11 Spacing 2950' Owner/Occupant: Frank and Elizabeth Abruzzino
Address: 91 Springhill Chapel Rd, Clarksburg, WV 26301 Ph: (304)-669-3892
Field Contact Date: 05/20/2015 Located: Yes Date Located: 05/20/2015 Source: Water Well
If No, declined by who: _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.374129
Long : 80.824661
Tax Map 16, Parcel 10

Site: 12 Spacing 3750' Owner/Occupant: Frank and Elizabeth Abruzzino
Address: 91 Springhill Chapel Rd, Clarksburg, WV 26301 Ph: (304)-669-3892
Field Contact Date: 05/20/2015 Located: Yes Date Located: 05/20/2015 Source: Water Well
If No, declined by who: _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.376858
Long : 80.822312
Tax Map 16, Parcel 10

Site: 13 Spacing 3260' Owner/Occupant: Frank and Elizabeth Abruzzino
Address: 91 Springhill Chapel Rd, Clarksburg, WV 26301 Ph: (304)-669-3892
Field Contact Date: 05/20/2015 Located: Yes Date Located: 05/20/2015 Source: Pond
If No, declined by who: _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.375580
Long : 80.820202
Tax Map 16, Parcel 10

Site: 14 Spacing 1535' Owner/Occupant: Frank and Elizabeth Abruzzino
Address: 91 Springhill Chapel Rd, Clarksburg, WV 26301 Ph: (304)-669-3892
Field Contact Date: 05/20/2015 Located: Yes Date Located: 05/20/2015 Source: Water Well
If No, declined by who: _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: Lat : 39.370659
Long : 80.819027
Tax Map 16, Parcel 10

Site: 15 Spacing _____ Owner/Occupant: Conrad Costilow
Address: 13310 Middle island Rd. West Union, WV 26456 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who: _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcel 14

Site: 16 Spacing _____ Owner/Occupant: John McDonald Jr.
Address: HC 74 Box 34C Alma, WV 26320 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who: _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 21, Parcel 41

Received
Office of Oil & Gas
JUL 06 2015

Site: 17 Spacing _____ Owner/Occupant: Paul Weekley (life)
Address: 4500 Mcelroy creek Rd. Alma, WV 26320 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcel 28

Site: 18 Spacing _____ Owner/Occupant: Chris and Herstine Baum
Address: 7214 Ridgeview Dr. SE Waynesburg, OH 44688 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcel 23

Site: 19 Spacing _____ Owner/Occupant: Leona Lorkovich
Address: 1719 Jackson St. Aliquippa, PA 15001 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcel 24

Site: 20 Spacing _____ Owner/Occupant: Stonewall Gas Company
Address: 501 Martindale St. Ste. 500 Pitsburg, PA 15212 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcel 24.2

Site: 21 Spacing _____ Owner/Occupant: Richard Metcalf
Address: 128 Village Dr. Bridgeport, WV 26330 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcels 14.1 and 17

Site: 22 Spacing _____ Owner/Occupant: John Anders
Address: 804 Peters Run Rd. Wheeling, WV 26003 Ph: _____
Field Contact Date: N/A Located: No Date Located: N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcel 14.2

Received
Office of Oil & Gas
JUL 06 2015

4709502280

Site: 23 Spacing _____ Owner/Occupant: Gary Prosser
Address: HC 74 Box 21 Wilbur, WV 26320 Ph: _____
Field Contact Date: N/A Located: No Date Located N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcel 15

Site: 24 Spacing _____ Owner/Occupant: Howard and Shannon Shriver
Address: HCR 74 Box 22A Alma, WV 26320 Ph: _____
Field Contact Date: N/A Located: No Date Located N/A Source: Unknown
If No, declined by who _____ Letter/Notice Date: 1st 04/09/2015 2nd 04/23/2015 Certified (3rd) 04/17/2015
Comments: No Response To Certified Letter As Of 05/29/2015
Tax Map 16, Parcel 16

Site: _____ Spacing _____ Owner/Occupant: _____
Address: _____ Ph: _____
Field Contact Date: _____ Located: _____ Date Located: _____ Source: _____
If No, declined by who _____ Letter/Notice Date: 1st _____ 2nd _____ Certified (3rd) _____
Comments: _____

Site: _____ Spacing _____ Owner/Occupant: _____
Address: _____ Ph: _____
Field Contact Date: _____ Located: _____ Date Located: _____ Source: _____
If No, declined by who _____ Letter/Notice Date: 1st _____ 2nd _____ Certified (3rd) _____
Comments: _____

Site: _____ Spacing _____ Owner/Occupant: _____
Address: _____ Ph: _____
Field Contact Date: _____ Located: _____ Date Located: _____ Source: _____
If No, declined by who _____ Letter/Notice Date: 1st _____ 2nd _____ Certified (3rd) _____
Comments: _____

Site: _____ Spacing _____ Owner/Occupant: _____
Address: _____ Ph: _____
Field Contact Date: _____ Located: _____ Date Located: _____ Source: _____
If No, declined by who _____ Letter/Notice Date: 1st _____ 2nd _____ Certified (3rd) _____
Comments: _____

Received
Office of Oil & Gas
JUL 06 2015

WW-6A
(9-13)

API NO. 47 - 095 - 0
OPERATOR WELL NO. 512892
Well Pad Name: WEU4

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE OF APPLICATION

Notice Time Requirement: notice shall be provided no later than the filing date of permit application.

Date of Notice: JUN 2 4 2015 Date Permit Application Filed: JUN 2 4 2015

4709502280

Notice of:

☑ PERMIT FOR ANY WELL WORK ☐ CERTIFICATE OF APPROVAL FOR THE CONSTRUCTION OF AN IMPOUNDMENT OR PIT

Delivery method pursuant to West Virginia Code § 22-6A-10(b)

☐ PERSONAL SERVICE ☐ REGISTERED MAIL ☑ METHOD OF DELIVERY THAT REQUIRES A RECEIPT OR SIGNATURE CONFIRMATION

Pursuant to W. Va. Code § 22-6A-10(b) no later than the filing date of the application, the applicant for a permit for any well work or for for the construction of an impoundment or pit as required by this article shall deliver, by personal service or by registered mail or by any requires a receipt or signature confirmation, copies of the application, the erosion and sediment control plan required by section seven of plat to each of the following persons: (1) The owners of record of the surface of the tract on which the well is or is proposed to be located; the surface tract or tracts overlying the oil and gas leasehold being developed by the proposed well work, if the surface tract is to be used disturbance as described in the erosion and sediment control plan submitted pursuant to subsection (c), section seven of this article; (3) lessee, in the event the tract of land on which the well proposed to be drilled is located [sic] is known to be underlain by one or more coal record of the surface tract or tracts overlying the oil and gas leasehold being developed by the proposed well work, if the surface tract is to construction, enlargement, alteration, repair, removal or abandonment of any impoundment or pit as described in section nine of this water purveyor who is known to the applicant to have a water well, spring or water supply source located within one thousand five which is used to provide water for consumption by humans or domestic animals; and (6) The operator of any natural gas storage field work activity is to take place. (c)(1) If more than three tenants in common or other co-owners of interests described in subsection (b) of in the lands, the applicant may serve the documents required upon the person described in the records of the sheriff required to be article one, chapter eleven-a of this code. (2) Notwithstanding any provision of this article to the contrary, notice to a lien holder is not unless the lien holder is the landowner. W. Va. Code R. § 35-8-5.7.a requires, in part, that the operator shall also provide the Well Site the surface owner and any water purveyor or surface owner subject to notice and water testing as provided in section 15 of this rule.

☑ Application Notice ☑ WSSP Notice ☑ E&S Plan Notice ☑ Well Plat Notice is hereby provided to:

☑ SURFACE OWNER(s)
Name: Donna J Peter
Address: 733 Ridge Rd
Wilbur WV 26320

Name:
Address:

☑ SURFACE OWNERS(s) (Road and/or Other Disturbance)
Name: Donna J Peter
Address: 733 Ridge Rd
Wilbur WV 26320

Name: L. Bruce and Sandra Jean Stoneking
Address: R.D. 1 Box BB
Elkins WV 26241
See attached for additional surface (road/ disturbance)

☑ SURFACE OWNER(s) (Impoundments/Pits)
Name: Donna J Peter
Address: 733 Ridge Rd
Wilbur WV 26320

☑ COAL OWNER OR LESSEE
Name: Nancy M. Ash or Heirs Assigns
Address: 101 Lake Village Road
Slidell LA 70461
See attached for additional coal owners.

☐ COAL OPERATOR
Name:
Address:

☑ SURFACE OWNER OF WATER WELL AND/OR WATER PURVEYOR(s)
Name: Donna J Peter
Address: 733 Ridge Rd
Wilbur WV 26320
See Attached for additional water.

☐ OPERATOR OF ANY NATURAL GAS STORAGE FIELD
Name:
Address:

*Please attach additional forms if necessary

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of Environmental Protection

WW-6A
(8-13)

API NO. 47 - 095 - 0
OPERATOR WELL NO. 512892
Well Pad Name: WEU4

Notice is hereby given:

Pursuant to West Virginia Code § 22-6A-10(b), notice is hereby given that the undersigned well operator has applied for a permit for well work or for a certificate of approval for the construction of an impoundment or pit.

This Notice Shall Include:
Pursuant to W. Va. Code § 22-6A-10(b), this notice shall include: (1) copies of the application; (2) the erosion and sediment control plan required by section seven of this article; and (3) the well plat.

4709502780

Pursuant to W. Va. Code § 22-6A-10(f), this notice shall include: (1) a statement of the time limits for filing written comments; (2) who may file written comments; (3) the name and address of the secretary for the purpose of filing the comments and obtaining additional information; and (4) a statement that the persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.

Pursuant to W. Va. Code R. § 35-8-5.7.a, the operator shall provide the Well Site Safety Plan to the surface owner and any water purveyor or surface owner subject to notice and water testing as provided in section 15 of this rule.

Pursuant to W. Va. Code R. § 35-8-15.2.c, this notice shall: (1) contain a statement of the surface owner's and water purveyor's right to request sampling and analysis; (2) advise the surface owner and water purveyor of the rebuttable presumption for contamination or deprivation of a fresh water source or supply; advise the surface owner and water purveyor that refusal to allow the operator to conduct a pre-drilling water well test constitutes a method to rebut the presumption of liability; (3) advise the surface owner and water purveyor of his or her independent right to sample and analyze any water supply at his or her own expense; advise the surface owner and water purveyor whether or not the operator will utilize an independent laboratory to analyze any sample; and (4) advise the surface owner and or water purveyor that he or she can obtain from the Chief a list of water testing laboratories in the subject area capable of and qualified to test water supplies in accordance with standard acceptable methods.

Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57th Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting www.dep.wv.gov/oil-and-gas/pages/default.aspx.

Well Location Restrictions

Pursuant to W. Va. Code § 22-6A-12, Wells may not be drilled within two hundred fifty feet measured horizontally from any existing water well or developed spring used for human or domestic animal consumption. The center of well pads may not be located within six hundred twenty-five feet of an occupied dwelling structure, or a building two thousand five hundred square feet or larger used to house or shelter dairy cattle or poultry husbandry. This limitation is applicable to those wells, developed springs, dwellings or agricultural buildings that existed on the date a notice to the surface owner of planned entry for surveying or staking as provided in section ten of this article or a notice of intent to drill a horizontal well as provided in subsection (b), section sixteen of this article was provided, whichever occurs first, and to any dwelling under construction prior to that date. This limitation may be waived by written consent of the surface owner transmitted to the department and recorded in the real property records maintained by the clerk of the county commission for the county in which such property is located. Furthermore, the well operator may be granted a variance by the secretary from these distance restrictions upon submission of a plan which identifies the sufficient measures, facilities or practices to be employed during well site construction, drilling and operations. The variance, if granted, shall include terms and conditions the department requires to ensure the safety and protection of affected persons and property. The terms and conditions may include insurance, bonding and indemnification, as well as technical requirements. (b) No well pad may be prepared or well drilled within one hundred feet measured horizontally from any perennial stream, natural or artificial lake, pond or reservoir, or a wetland, or within three hundred feet of a naturally reproducing trout stream. No well pad may be located within one thousand feet of a surface or ground water intake of a public water supply. The distance from the public water supply as identified by the department shall be measured as follows: (1) For a surface water intake on a lake or reservoir, the distance shall be measured from the boundary of the lake or reservoir. (2) For a surface water intake on a flowing stream, the distance shall be measured from a semicircular radius extending upstream of the surface water intake. (3) For a groundwater source, the distance shall be measured from the wellhead or spring. The department may, in its discretion, waive these distance restrictions upon submission of a plan identifying sufficient measures, facilities or practices to be employed during well site construction, drilling and operations to protect the waters of the state. A waiver, if granted, shall impose any permit conditions as the secretary considers necessary. (c) Notwithstanding the foregoing provisions of this section, nothing contained in this section prevents an operator from conducting the activities permitted or authorized by a Clean Water Act Section 404 permit or other approval from the United States Army Corps of Engineers within any waters of the state or within the restricted areas referenced in this section. (d) The well location restrictions set forth in this section shall not apply to any well on a multiple well pad if at least one of the wells was permitted prior to the effective date of this article. (e) The secretary shall, by December 31, 2012, report to the Legislature on the noise, light, dust and volatile organic compounds generated by the drilling of horizontal wells as they relate to the well location restrictions regarding occupied dwelling structures pursuant to this section. Upon a finding, if any, by the secretary that the well location restrictions regarding occupied dwelling structures are inadequate or otherwise require alteration to address the items

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Protection

examined in the study required by this subsection, the secretary shall have the authority to propose for promulgation legislative rules establishing guidelines and procedures regarding reasonable levels of noise, light, dust and volatile organic compounds relating to drilling horizontal wells, including reasonable means of mitigating such factors, if necessary.

Water Well Testing:

Pursuant to West Virginia Code § 22-6A-10(d), notification shall be made, with respect to surface landowners identified in subsection (b) or water purveyors identified in subdivision (5), subsection (b) of this section, of the opportunity for testing their water well. The operator shall provide an analysis to such surface landowner or water purveyor at their request.

Water Testing Laboratories:

4709502208

Pursuant to West Virginia Code § 22-6A-10(i), persons entitled to notice pursuant to subsection (b) of this section may contact the department to ascertain the names and locations of water testing laboratories in the subject area capable and qualified to test water supplies in accordance with standard accepted methods. In compiling that list of names the department shall consult with the state Bureau for Public Health and local health departments. A surface owner and water purveyor has an independent right to sample and analyze any water supply at his or her own expense. The laboratory utilized by the operator shall be approved by the agency as being certified and capable of performing sample analyses in accordance with this section.

Rebuttable Presumption for Contamination or Deprivation of a Fresh Water Source or Supply:

W. Va. Code § 22-6A-18 requires that (b) unless rebutted by one of the defenses established in subsection (c) of this section, in any action for contamination or deprivation of a fresh water source or supply within one thousand five hundred feet of the center of the well pad for horizontal well, there is a rebuttable presumption that the drilling and the oil or gas well or either was the proximate cause of the contamination or deprivation of the fresh water source or supply. (c) In order to rebut the presumption of liability established in subsection (b) of this section, the operator must prove by a preponderance of the evidence one of the following defenses: (1) The pollution existed prior to the drilling or alteration activity as determined by a predrilling or prealteration water well test. (2) The landowner or water purveyor refused to allow the operator access to the property to conduct a predrilling or prealteration water well test. (3) The water supply is not within one thousand five hundred feet of the well. (4) The pollution occurred more than six months after completion of drilling or alteration activities. (5) The pollution occurred as the result of some cause other than the drilling or alteration activity. (d) Any operator electing to preserve its defenses under subdivision (1), subsection (c) of this section shall retain the services of an independent certified laboratory to conduct the predrilling or prealteration water well test. A copy of the results of the test shall be submitted to the department and the surface owner or water purveyor in a manner prescribed by the secretary. (e) Any operator shall replace the water supply of an owner of interest in real property who obtains all or part of that owner's supply of water for domestic, agricultural, industrial or other legitimate use from an underground or surface source with a comparable water supply where the secretary determines that the water supply has been affected by contamination, diminution or interruption proximately caused by the oil or gas operation, unless waived in writing by that owner. (f) The secretary may order the operator conducting the oil or gas operation to: (1) Provide an emergency drinking water supply within twenty-four hours; (2) Provide temporary water supply within seventy-two hours; (3) Within thirty days begin activities to establish a permanent water supply or submit a proposal to the secretary outlining the measures and timetables to be used in establishing a permanent supply. The total time in providing a permanent water supply may not exceed two years. If the operator demonstrates that providing a permanent replacement water supply cannot be completed within two years, the secretary may extend the time frame on case-by-case basis; and (4) Pay all reasonable costs incurred by the real property owner in securing a water supply. (g) A person as described in subsection (b) of this section aggrieved under the provisions of subsections (b), (e) or (f) of this section may seek relief in court... (i) Notwithstanding the denial of the operator of responsibility for the damage to the real property owner's water supply or the status of any appeal on determination of liability for the damage to the real property owner's water supply, the operator may not discontinue providing the required water service until authorized to do so by the secretary or a court of competent jurisdiction.

Written Comment:

Pursuant to West Virginia Code § 22-6A-11(a), all persons described in subsection (b), section ten of this article may file written comments with the secretary as to the location or construction of the applicant's proposed well work within thirty days after the application is filed with the secretary. All persons described in West Virginia Code § 22-6A-10(b) may file written comments as to the location or construction of the applicant's proposed well work to the Secretary at:

Chief, Office of Oil and Gas
Department of Environmental Protection
601 57th St. SE
Charleston, WV 25304
(304) 926-0450

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of Protection

Such persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.
NOTE: YOU ARE NOT REQUIRED TO FILE ANY COMMENT.

WW-6A
(8-13)

API NO. 47 - 095 - 0
OPERATOR WELL NO. 512892
Well Pad Name: WEU4

Time Limits and Methods for Filing Comments.

The law requires these materials to be served on or before the date the operator files its Application. You have THIRTY (30) DAYS after the filing date to file your comments. Comments must be filed in person or received in the mail by the Chief's office by the time stated above. You may call the Chief's office to be sure of the date. Check with your postmaster to ensure adequate delivery time or to arrange special expedited handling. If you have been contacted by the well operator and you have signed a "voluntary statement of no objection" to the planned work described in these materials, then the permit may be issued at any time.

Pursuant to West Virginia Code § 22-6A-11(c)(2), Any objections of the affected coal operators and coal seam owners and lessees shall be addressed through the processes and procedures that exist under sections fifteen, seventeen and forty, article six of this chapter, as applicable and as incorporated into this article by section five of this article. The written comments filed by the parties entitled to notice under subdivisions (1), (2), (4), (5) and (6), subsection (b), section ten of this article shall be considered by the secretary in the permit issuance process, but the parties are not entitled to participate in the processes and proceedings that exist under sections fifteen, seventeen or forty, article six of this chapter, as applicable and as incorporated into this article by section five of this article

4709503280

Comment Requirements

Your comments must be in writing and include your name, address and telephone number, the well operator's name and well number and the approximate location of the proposed well site including district and county from the application. You may add other documents, such as sketches, maps or photographs to support your comments.

Disclaimer: All comments received will be placed on our web site http://www.dep.wv.gov/oil-and-gas/Horizontal-Permits/Pages/default.aspx and the applicant will automatically be forwarded an email notice that such comments have been submitted. The applicant will be expected to provide a response to comments submitted by any surface owner, water purveyor or natural gas storage operator noticed within the application.

Permit Denial or Condition

The Chief has the power to deny or condition a well work permit. Pursuant to West Virginia Code § 22-6A-8(d), the permit may not be issued or be conditioned, including conditions with respect to the location of the well and access roads prior to issuance if the director determines that:

(1) The proposed well work will constitute a hazard to the safety of persons;
(2) The plan for soil erosion and sediment control is not adequate or effective;
(3) Damage would occur to publicly owned lands or resources; or
(4) The proposed well work fails to protect fresh water sources or supplies.

A permit may also be denied under West Virginia Code § 22-6A-7(k), the secretary shall deny the issuance of a permit if the secretary determines that the applicant has committed a substantial violation of a previously issued permit for a horizontal well, including the applicable erosion and sediment control plan associated with the previously issued permit, or a substantial violation of one or more of the rules promulgated under this article, and in each instance has failed to abate or seek review of the violation within the time prescribed by the secretary pursuant to the provisions of subdivisions (1) and (2), subsection (a), section five of this article and the rules promulgated hereunder, which time may not be unreasonable.

Pursuant to West Virginia Code § 22-6A-10(g), any person entitled to submit written comments to the secretary pursuant to subsection (a), section eleven of this article, shall also be entitled to receive from the secretary a copy of the permit as issued or a copy of the order modifying or denying the permit if the person requests receipt of them as a part of the written comments submitted concerning the permit application. Such persons may request, at the time of submitting written comments, notice of the permit decision and a list of persons qualified to test water.

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Protection

Notice is hereby given by:

Well Operator:	EQT Production Company	Address:	115 Professional Place P.O. Box 280
Telephone:	304-848-0082		Bridgeport, WV 26330
Email:	Vroark@eqt.com	Facsimile:	304-848-0041

Oil and Gas Privacy Notice:

The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at depprivacyofficer@wv.gov.

I certify under penalty of law that I have personally examined and am familiar with the information submitted on this application form and all attachments, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate and complete.

By: Victoria Roark

Its: Permitting Supervisor

Subscribed and sworn before n 24 day of June , 2015

Rebecca L Heater Notary Public

My Commission Expir 4-7-20

OFFICIAL SEAL
NOTARY PUBLIC
STATE OF WEST VIRGINIA
REBECCA L. HEATER
EQT PRODUCTION COMPANY
PO BOX 280
BRIDGEPORT, WV 26330
My commission expires April 7, 2020

4709502280

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

4709502280

WW6-A
Additional Coal Owners

Rosemary Brandon
3013 Delaware Avenue
Kenner, LA 70065

Oletha G. Moore or Heirs and Assigns
2428 Dewey Ave
Munhall PA 15120

Surface Owners(road or other disturbance):

James B. and Brenda J. Stoneking
2 Deerhaven Drive
Wheeling WV 26241

Diane L. Morgan and Glenn W. Morgan
590 Isner Creek Road
Elkins WV 26241

Richard and Yvonne Metcalf
128 Village Drive
Bridgeport WV 26330

Surface Owners(Pits or Impoundments):

Richard and Yvonne Metcalf
128 Village Drive
Bridgeport WV 26330

Additional Water Purveyors

Bruce Stoneking
R.D. 1 Box BB
Elkins WV 26241

Frank and Elizabeth Abruzzino
91 Springhill Chapel Road
Clarksburg, WV 26301

Received
Office of Oil & Gas
JUL 06 2015

WATER SOURCE LOCATIONS FOR W.H. ASH ET AL LEASE WEU4 WELLS



RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of Environmental Protection

Professional Energy Consultants
A DIVISION OF SMITH LAND SURVEYING INC.
SLS Surveyors Engineers Environmental Project Mgmt.

DRAWN BY	FILE NO.	DATE	CADD FILE:
K.D.W.	7701	05/27/15	7701WSNEU4.dwg

TOPO SECTION OF:
WEST UNION, WV 7.5' QUAD

DISTRICT	COUNTY	TAX MAP-PARCEL NO.
CENTERVILLE	TYLER	16-22

OPERATOR:
EQT PRODUCTION COMPANY
115 PROFESIONAL PLACE
P.O. BOX 280
BRIDGEPORT, WV 26330

WW6-A
Additional Coal Owners

Rosemary Brandon
3013 Delaware Avenue
Kenner, LA 70065

Oletha G. Moore or Heirs and Assigns
2428 Dewey Ave
Munhall PA 15120

Surface Owners(road or other disturbance):

James B. and Brenda J. Stoneking
2 Deerhaven Drive
Wheeling WV 26241

Diane L. Morgan and Glenn W. Morgan
590 Isner Creek Road
Elkins WV 26241

Richard and Yvonne Metcalf
128 Village Drive
Bridgeport WV 26330

Surface Owners(Pits or impoundments):

Richard and Yvonne Metcalf
128 Village Drive
Bridgeport WV 26330

VOID

Additional Water Purveyors

Bruce Stoneking
R.D. 1 Box BB
Elkins WV 26241

Fred and Elizabeth Abruzzino
RT1 Box 360
Clarksburg, WV 26301

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

WW-6A3
(1/12)

Operator Well No. Lease 126129

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE OF ENTRY FOR PLAT SURVEY

Notice Time Requirement: Notice shall be provided at least **SEVEN (7)** days but no more than **FORTY-FIVE (45)** days prior to entry.

Date of Notice: 3/26/2013 **Date of Planned Entry:** 4/2/2013

Delivery method pursuant to West Virginia Code § 22-6A-10(a):

[ ] PERSONAL SERVICE [x] CERTIFIED MAIL [ ] METHOD OF DELIVERY THAT REQUIRES A RECEIPT OR SIGNATURE CONFIRMATION

Pursuant to West Virginia Code § 22-6A-10(a), prior to filing a permit application, the operator shall provide notice of planned entry on to the surface tract to conduct any plat surveys required pursuant to this article. Such notice shall be provided at least sever days but no more than forty-five days prior to such entry to: (1) The surface owner of such tract; (2) to any owner or lessee of coal seams beneath such tract that has filed a declaration pursuant to section thirty-six, article six, chapter twenty-two of this code; and (3) any owner of minerals underlying such tract in the county tax records. The notice shall include a statement that copies of the state Erosion and Sediment Control Manual and the statutes and rules related to oil and gas exploration and production may be obtained from the Secretary, which statement shall include contact information, including the address for a web page on the Secretary's web site, to enable the surface owner to obtain copies from the secretary.

4708502280

Notice is hereby provided to:

[x] **SURFACE OWNER(S)**

Name: Norman E & Donna J. Peter
Address: HC74 Box 31
Wilbur, WV 26320

Name:
Address:

Name:
Address:

[x] **COAL OWNER OR LESSEE**

Name: Coal Declaration pursuant to §22-6A-10 and §22-6-36
Not of Record
Address:

[x] **MINERAL OWNER(S)**

Name: C. Phillip Fluharty, Donald G. Fluharty and
Caroline Fluharty Genewick
Address: PO Box 524
Santee, SC 29142

Name: Trio Petroleum and Waco Oil & Gas
Address: PO Box 880
Glenville, WV 26351

*Please attach additional forms if necessary

Notice is hereby given:

Pursuant to West Virginia Code § 22-6A-10(a), notice is hereby given that the undersigned well operator is planning entry to conduct a plat survey on the tract of land as follows:

State: West Virginia
County: Tyler
District: Centerville / Map16 / Parcel 22
Quadrangle: West Union
Approx. Latitude & Longitude: 39.36664 / -80.82072
Public Road Access: CR58
Watershed: Middle Island Creek
Generally Used Farm Name: Ash

Copies of the state Erosion and Sediment Control Manual and the statues and rules related to oil and gas exploration and production may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57th Street, SE, Charleston, WV 25304 (304-926-0450). Copies of such documents or additional information related to horizontal drilling may be obtained from the Secretary by visiting www.dep.wv.gov/oil-and-gas/pages/default.aspx.

RECEIVED
Office of Oil and Gas
NOV 05 2015
WV Department of Environmental Protection

Notice is hereby given by:

Well Operator: EQT Production Company
Address: 115 Professional Place, Bridgeport, WV 26330
Telephone: 304-848-0099
EQT Representative: Kathy Kugel
Facsimile: 304-848-0040
Email: EQTLandEntryNotice@eqt.com
Signature: Kathy Kugel

Oil and Gas Privacy Notice:

The Office of Oil and Gas processes your personal information, such a name, address and telephone number, as part of regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at depprivacyofficer@WV.gov.

WW-6A5
(1/12)

Operator Well No. 512892

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE OF PLANNED OPERATION

Notice Time Requirement: notice shall be provided no later than the filing date of permit application.

Date of Notice: JUN 24 2015 **Date Permit Application Filed:** JUN 24 2015

Delivery method pursuant to West Virginia Code § 22-6A-16(c)

☑ CERTIFIED MAIL RETURN RECEIPT REQUESTED ☐ HAND DELIVERY

Pursuant to W. Va. Code § 22-6A-16(c), no later than the date for filing the permit application, an operator shall, by certified mail return receipt requested or hand delivery, give the surface owner whose land will be used for the drilling of a horizontal well notice of the planned operation. The notice required by this subsection shall include: (1) A copy of this code section; (2) The information required to be provided by subsection (b), section ten of this article to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. (d) The notices required by this section shall be given to the surface owner at the address listed in the records of the sheriff at the time of notice.

Notice is hereby provided to the SURFACE OWNER(s)
(at the address listed in the records of the sheriff at the time of notice):

Name: Donna J Peter
Address: 733 Ridge Rd
Wilbur WV 26320

Name: L. Bruce and Sandra Jean Stoneking
Address: R.D. 1 Box BB
Elkins WV 26241

47095 02280

Notice is hereby given:
Pursuant to West Virginia Code § 22-6A-16(c), notice is hereby given that the undersigned well operator has developed a planned operation on the surface owner's land for the purpose of drilling a horizontal well on the tract of land as follows:

State:	WV	UTM NAD 83	Easting:	515,451.620000
County:	Tyler		Northing:	4,357,471.450000
District:	Centerville	Public Road Access:		WV-18
Quadrangle:	West Union 7.5'	Generally used farm name:		Donna J. Peter
Watershed:	Tributary of Camp Mistake Run			

This Notice Shall Include:
Pursuant to West Virginia Code § 22-6A-16(c), this notice shall include: (1)A copy of this code section; (2) The information required to be provided by **W. Va. Code § 22-6A-10(b)** to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57th Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting www.dep.wv.gov/oil-and-gas/pages/default.aspx.

Well Operator:	EQT Production Company	Address:	115 Professional Place, P.O. Box 280
Telephone:	304-848-0082		Bridgeport, WV 26330
Email:	vroark@eqt.com	Facsimile:	304-848-0040

Oil and Gas Privacy Notice:
The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at deprivacyofficer@wv.gov.

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Protection

WW-6A5
(1/12)

Operator Well No. 512892

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE OF PLANNED OPERATION

Notice Time Requirement: notice shall be provided no later than the filing date of permit application.

Date of Notice: JUN 24 2015 **Date Permit Application Filed:** JUN 24 2015

Delivery method pursuant to West Virginia Code § 22-6A-16(c)

☑ CERTIFIED MAIL RETURN RECEIPT REQUESTED ☐ HAND DELIVERY

Pursuant to W. Va. Code § 22-6A-16(c), no later than the date for filing the permit application, an operator shall, by certified mail return receipt requested or hand delivery, give the surface owner whose land will be used for the drilling of a horizontal well notice of the planned operation. The notice required by this subsection shall include: (1) A copy of this code section; (2) The information required to be provided by subsection (b), section ten of this article to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. (d) The notices required by this section shall be given to the surface owner at the address listed in the records of the sheriff at the time of notice.

Notice is hereby provided to the SURFACE OWNER(s)
(at the address listed in the records of the sheriff at the time of notice):

Name: James B and Brenda J Stoneking
Address: 2 Deerhaven Drive
Wheeling WV 26241

Name: Diane L Morgan and Glenn W Morgan
Address: 590 Isner Creek Rd
Elkins WV 26241

Notice is hereby given:
Pursuant to West Virginia Code § 22-6A-16(c), notice is hereby given that the undersigned well operator has developed a planned operation on the surface owner's land for the purpose of drilling a horizontal well on the tract of land as follows:

4709502280

State:	WV	UTM NAD 83	Easting:	515,451.620000
County:	Tyler		Northing:	4,357,471.450000
District:	Centerville	Public Road Access:		WV-18
Quadrangle:	West Union 7.5'	Generally used farm name:		Donna J. Peter
Watershed:	Tributary of Camp Mistake Run			

This Notice Shall Include:
Pursuant to West Virginia Code § 22-6A-16(c), this notice shall include: (1)A copy of this code section; (2) The information required to be provided by **W. Va. Code § 22-6A-10(b)** to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57th Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting www.dep.wv.gov/oil-and-gas/pages/default.aspx.

Well Operator:	EQT Production Company	Address:	115 Professional Place, P.O. Box 280
Telephone:	304-848-0082		Bridgeport, WV 26330
Email:	vroark@eqt.com	Facsimile:	304-848-0040

Office of Oil and Gas
JUN 25 2015
Department of

Oil and Gas Privacy Notice:
The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at depprivacyofficer@wv.gov.

WW-6A5
(1/12)

Operator Well No. 512892

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION, OFFICE OF OIL AND GAS
NOTICE OF PLANNED OPERATION

Notice Time Requirement: notice shall be provided no later than the filing date of permit application.
Date of Notice: JUN 24 2015 **Date Permit Application Filed:** JUN 24 2015

Delivery method pursuant to West Virginia Code § 22-6A-16(c)

☑ CERTIFIED MAIL RETURN RECEIPT REQUESTED ☐ HAND DELIVERY

Pursuant to W. Va. Code § 22-6A-16(c), no later than the date for filing the permit application, an operator shall, by certified mail return receipt requested or hand delivery, give the surface owner whose land will be used for the drilling of a horizontal well notice of the planned operation. The notice required by this subsection shall include: (1) A copy of this code section; (2) The information required to be provided by subsection (b), section ten of this article to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. (d) The notices required by this section shall be given to the surface owner at the address listed in the records of the sheriff at the time of notice.

Notice is hereby provided to the SURFACE OWNER(s)
(at the address listed in the records of the sheriff at the time of notice):

Name: Richard and Yvonne Metcalf
Address: 128 Village Dr
Bridgeport WV 26330

Name:
Address:

Notice is hereby given:
Pursuant to West Virginia Code § 22-6A-16(c), notice is hereby given that the undersigned well operator has developed a planned operation on the surface owner's land for the purpose of drilling a horizontal well on the tract of land as follows:

State:	WV	UTM NAD 83	Easting:	515,452.620000
County:	Tyler		Northing:	4,357,471.450000
District:	Centerville	Public Road Access:		WV-18
Quadrangle:	West Union 7.5'	Generally used farm name:		Donna J. Peter
Watershed:	Tributary of Camp Mistake Run			

4709502280

This Notice Shall Include:
Pursuant to West Virginia Code § 22-6A-16(c), this notice shall include: (1)A copy of this code section; (2) The information required to be provided by **W. Va. Code § 22-6A-10(b)** to a surface owner whose land will be used in conjunction with the drilling of a horizontal well; and (3) A proposed surface use and compensation agreement containing an offer of compensation for damages to the surface affected by oil and gas operations to the extent the damages are compensable under article six-b of this chapter. Additional information related to horizontal drilling may be obtained from the Secretary, at the WV Department of Environmental Protection headquarters, located at 601 57th Street, SE, Charleston, WV 25304 (304-926-0450) or by visiting www.dep.wv.gov/oil-and-gas/pages/default.aspx.

Well Operator:	EQT Production Company	Address:	115 Professional Place, P.O. Box 280
Telephone:	304-848-0082		Bridgeport, WV 26330
Email:	vroark@eqt.com	Facsimile:	304-848-0040

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

Oil and Gas Privacy Notice:
The Office of Oil and Gas processes your personal information, such as name, address and telephone number, as part of our regulatory duties. Your personal information may be disclosed to other State agencies or third parties in the normal course of business or as needed to comply with statutory or regulatory requirements, including Freedom of Information Act requests. Our office will appropriately secure your personal information. If you have any questions about our use or your personal information, please contact DEP's Chief Privacy Officer at depprivacyofficer@wv.gov.

WEST VIRGINIA DEPARTMENT OF TRANSPORTATION
Division of Highways
1900 Kanawha Boulevard East • Building Five • Room 110
Charleston, West Virginia 25305-0430 • (304) 558-3505

Earl Ray Tomblin
Governor

Paul A. Mattox, Jr., P. E.
Secretary of Transportation/
Commissioner of Highways

June 23, 2015

James A. Martin, Chief
Office of Oil and Gas
Department of Environmental Protection
601 57th Street, SE
Charleston, WV 25304

Subject: DOH Permit for the WEU 4 Well Pad, Tyler County

512890 WEU4H1	512891 WEU4H2	512892 WEU4H3
512893 WEU4H4	512894 WEU4H5	512895 WEU4H6
514052 WEU4H7	514053 WEU4H8	514054 WEU4H9
514055 WEU4H10		

Dear Mr. Martin,

This well site will be accessed from DOH Permit #06-2015-0241 issued to EQT Production Company for access to the State Road for a well site located off of Tyler County Route 58 SLS.

The operator has signed a STATEWIDE OIL AND GAS ROAD MAINTENANCE BONDING AGREEMENT and provided the required Bond. This operator is currently in compliance with the DOH OIL AND GAS POLICY dated January 3, 2012.

4709502280

Very Truly Yours,

Gary K. Clayton

Gary K. Clayton P.E.
Regional Maintenance Engineer
Central Office Oil & Gas Coordinator

RECEIVED
Office of Oil and Gas
JUN 25 2015
WV Department of
Environmental Protection

Cc: Nick Bumgardner
EQT Production Company
CH, OM, D-6
File

Anticipated Frac Additives

Chemical Names and CAS numbers

Material	Ingredient	CAS Number
Water		
Sand	Hydrotreated light petroleum distillate	14808-60-7
Friction Reducer	Tributyl tetradecyl phosphonium chloride	64742-47-8
Biocide	Ammonium chloride	81741-28-8
Scale Inhibitor	Hydrochloric Acid	12125-02-9
15% Hydrochloric Acid	Propargyl Alcohol	7647-01-0
Corrosion Inhibitor	Methanol	107-19-7
Corrosion Inhibitor	Guar Gum	67-56-1
Gelling Agent	Sodium Persulfate	9000-30-0
Oxidizing Breaker	Potassium Carbonate	7775-27-1
Buffering Agent		584-08-7

4709502280

RECEIVED
Office of Oil and Gas
JUN 2 6
WV Department of
Environmental Protection

WEU4 SITE PLAN
EQT PRODUCTION COMPANY

SITUATE ON THE WATERS OF CAMP MISTAKE RUN IN MCELROY AND CENTERVILLE DISTRICTS, TYLER COUNTY, WEST VIRGINIA

PROJECT INFORMATION

PROJECT NAME: WEU4

TAX PARCEL:
MCELROY AND CENTERVILLE DISTRICTS
TYLER COUNTY, WV
TAX MAP 16 PARCEL 22

SURFACE OWNER:
DONNA J. PETER
TOTAL PROPERTY AREA: 113.44± ACRES
TAX MAP 16 PARCEL 22

L.B. & SANDRA STONEKING
TOTAL PROPERTY AREA: 69.44± ACRES
TAX MAP 21 PARCEL 20

RICHARD & YVONNE METCALF
TOTAL PROPERTY AREA: 61.57± ACRES
TM 16-17

OIL AND GAS ROYALTY OWNER:
WACO OIL & GAS CO. INC. ET AL
WEST UNION DISTRICT
DODDRIDGE COUNTY, WV
TOTAL PROPERTY AREA: 152 ± ACRES

SITE LOCATION:
THE WEU4 WELL SITE IS SITUATE ON THE WATERS OF CAMP MISTAKE RUN APPROXIMATELY 0.58 MILES WEST OF COUNTY ROUTE 58. THE ENTRANCE IS LOCATED APPROXIMATELY 0.30 MILES SOUTHWEST FROM THE INTERSECTION OF COUNTY ROUTE 62 AND COUNTY ROUTE 58.

LOCATION COORDINATES

WEU4 SITE ENTRANCE
LATITUDE: 39.369229 LONGITUDE: -80.810071 (NAD 83 NORTH)

WEU4 RIG FOOTPRINT
LATITUDE: 39.368719 LONGITUDE: -80.820708 (NAD 83 NORTH)

WEU4 PUMP PAD
LATITUDE: 39.365889 LONGITUDE: -80.820869 (NAD 83 NORTH)

WEU4 FLOWBACK PIT
LATITUDE: 39.365315 LONGITUDE: -80.821118 (NAD 83 NORTH)

WEU4 TRUCK PAD
LATITUDE: 39.364962 LONGITUDE: -80.821587 (NAD 83 NORTH)

WEU4 COMPLETION PIT MANIFOLD PAD
LATITUDE: 39.365408 LONGITUDE: -80.824945 (NAD 83 NORTH)

WEU4 COMPLETION PIT
LATITUDE: 39.365884 LONGITUDE: -80.825816 (NAD 83 NORTH)

SITE DISTURBANCE COMPUTATIONS

ACCESS ROAD NO. 1 & NO. 2 = 8.01± ACRES
STOCKPILE SITES 1-6 = 4.28± ACRES
RIG FOOTPRINT = 3.25 ACRES
MANIFOLD PAD & FLOWBACK PIT = 8.31± ACRES
COMPLETION PIT = 3.33± ACRES
TOTAL SITE DISTURBANCE = 19.18± ACRES

ENTRANCE PERMIT

EQT PRODUCTION COMPANY WILL OBTAIN AN ENTRANCE PERMIT (FORM MM-109) FROM THE WEST VIRGINIA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.

MISS UTILITY STATEMENT

MISS UTILITY OF WEST VIRGINIA WAS NOTIFIED FOR THE LOCATING OF UTILITIES PRIOR TO THIS PROJECT DESIGN, TICKET #(SEE) 792253. IN ADDITION, MISS UTILITY WILL BE CONTACTED PRIOR TO START OF THE PROJECT.

FLOODPLAIN NOTE

THE PROPOSED LIMITS OF DISTURBANCE FOR THIS PROJECT IS LOCATED IN FEMA FLOOD ZONE X, PER THE FLOOD INSURANCE RATE MAP (FIRM) NUMBER 54095C0030C, DATED MAY 3, 2010.

ENVIRONMENTAL NOTES

A WETLAND DELINEATION WAS PERFORMED ON APRIL 25-26, 2013 BY POTESTA AND ASSOCIATES, INC. TO REVIEW THE SITE FOR WATERS AND WETLANDS THAT ARE MOST LIKELY WITHIN THE REGULATORY PURVIEW OF THE U.S. ARMY CORPS OF ENGINEERS (USACE) AND/OR THE WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION (WVDEP). THE MAY 29, 2013 REPORT PROJECT # 0101-11-147-15701 WAS PREPARED BY POTESTA AND ASSOCIATES, INC. SUMMARIZES THE RESULTS OF THE FIELD DELINEATION. THE REPORT DOES NOT, IN ANY WAY, REPRESENT A JURISDICTIONAL DETERMINATION OF THE LANDWARD LIMITS OF WATERS AND WETLANDS WHICH MAY BE REGULATED BY THE USACE OR THE WVDEP. IT IS STRONGLY RECOMMENDED THAT THE AFOREMENTIONED AGENCIES BE CONSULTED IN AN EFFORT TO GAIN WRITTEN CONFIRMATION OF THE DELINEATION DESCRIBED BY THIS REPORT PRIOR TO ENGAGING CONSTRUCTION ON THE PROPERTY DESCRIBED HEREIN. THE DEVELOPER SHALL OBTAIN THE APPROPRIATE PERMITS FROM THE FEDERAL AND/OR STATE REGULATORY AGENCIES PRIOR TO ANY PROPOSED IMPACTS TO WATERS OF THE U.S., INCLUDING WETLAND FILLS AND STREAM CROSSINGS.

HORIZONTAL & VERTICAL CONTROL

COORDINATES AND ELEVATIONS USED FOR ALL LAYOUTS AND DESIGNS WERE BASED UPON MAPPING FURNISHED BY SMITH LAND SURVEYING.

MISS Utility of West Virginia
1-800-245-4848
West Virginia State Law
(Section XIV: Chapter 24-C)
Requires that you call two business days before you dig in the state of West Virginia.
IT'S THE LAW!!

GRID NORTH AND ELEVATIONS SHOWN HEREON WERE ESTABLISHED BY SURVEY GRADE GPS

WEU4 NAD 83 WELL LOCATIONS

WELL	WV	WELL STATUS	API	LAT	LON	NORTHING	EASTING
H6	512940	PROPOSED	47-095-02278	39.366463	-80.820668	514399.60	1595233.70
H7	512941	PROPOSED	47-095-02279	39.366806	-80.820668	514585.63	1595159.09
H8	512942	PROPOSED	47-095-02280	39.366384	-80.820639	514371.62	1595244.43
1H	512943	PROPOSED	47-095-02281	39.366579	-80.820604	514557.4	1595159.88
2H	512944	PROPOSED		39.366496	-80.820589	514513.64	1595155.27
3H	512945	PROPOSED		39.366431	-80.820569	514479.41	1595150.86
4H	512946	PROPOSED		39.366415	-80.820619	514471.41	1595146.05
5H	516135	PROPOSED		39.366968	-80.820627	514762.37	1595260.56
6H	516136	PROPOSED		39.366905	-80.820757	514729.56	1595204.95
7H	516337	PROPOSED		39.366872	-80.820787	514685.58	1595190.34
8H	516138	PROPOSED		39.366836	-80.820767	514649.56	1595206.13
9H	516039	PROPOSED		39.366799	-80.820767	514611.58	1595212.43
10H	516040	PROPOSED		39.366466	-80.820679	514437.62	1595244.48
11H		PROPOSED		39.366719	-80.820708	514427.59	1595122.91
12H		PROPOSED		39.366641	-80.820693	514411.57	1595128.30

LIST OF DRAWINGS

1 - COVER SHEET
2 - NOTES
3 - OVERALL SHEET INDEX & VOLUMES
4 - EXISTING UTILITY PLAN
5-7 - ACCESS ROAD PLAN
8 - RIG FOOTPRINT DET
10-11 - FLOWBACK PIT NO. 1 SECTIONS
12-13 - FLOWBACK PIT NO. 2 SECTIONS
14 - TYPICAL SECTIONS
15 - ACCESS ROAD NO. 1 PROFILE
16-20 - ACCESS ROAD NO. 1 SECTIONS
21 - ACCESS ROAD NO. 1 SECTIONS & ACCESS ROAD NO. 2 PROFILE & SECTIONS
22 - ACCESS ROAD COORDINATE LAYOUT
23 - 24 TOPSOIL STORAGE AREAS PROFILES & SECTIONS
25 - SPOIL STORAGE AREA PROFILE & SECTIONS
26 - 29 - WEU4 RECLAMATION PLANS
30 - 33 - CONSTRUCTION DETAILS

APPROVED
WVDEP OOG
8/28/2015

DISTURBED AREA BY PROPERTY OWNER	
PROPERTY OWNER	DISTURBED AREA
L.B. & SANDRA STONEKING	0.42 AC.
RICHARD & YVONNE METCALF	2.25 AC.
DONNA J. PETER	20.08 AC.
TOTAL	22.75 AC.

OPERATOR
EQT PRODUCTION COMPANY
OPERATOR ID: 306686
115 PROFESSIONAL PLACE
P.O. BOX 280
BRIDGEPORT, WV 26330
PHONE: (304) 848-3870

ENGINEER
RKK ENGINEERS
242 NORTH TORNADO WAY
SUITE 1
KEYSER, WV 26726
PHONE: (304) 788-3370

SURVEYOR
SMITH LAND SURVEYING, INC.
12 VANHORN DRIVE
P.O. BOX 150
GLENVILLE, WV 26351
PHONE: (304) 462-5634

RUMMEL, KLEPPER & KAHL, LLP
242 NORTH TORNADO WAY, SUITE 1
KEYSER, WEST VIRGINIA 26726
T. 304.788.3370 F. 304.788.3377
www.rkk.com
RK&K ENGINEERS

Professional Energy Consultants
SLS SURVEYORS ENGINEERS ENVIRONMENTAL PROJECT MGMT

DAVID G. SAVACOOL
STATE OF WEST VIRGINIA
PROFESSIONAL ENGINEER

THIS DOCUMENT WAS PREPARED BY RK&K ENGINEERS FOR EQT PRODUCTION COMPANY

COVER SHEET
WEU4
McELROY DISTRICT
CENTERVILLE DISTRICT
TYLER COUNTY, WV

DATE: 04/30/2015
SCALE: 1" = 2,000'
DESIGNED BY: HWH
FILE NO. 308
SHEET 1 OF 33
REV.: 08/25/2015

RIG FOOTPRINT & FLOWBACK PIT NO. 1 LAYOUT

WEU4PROPOSED WELLS

H1-WV 512890, H2-WV 512891, H3-WV 512892, H4-WV 512893, H5-WV 512894, H6-WV 512895



RUMMEL, KLEPPER & KAHL, LLP
242 NORTH TORNADO WAY, SUITE 1
KEYSER, WEST VIRGINIA 26726
T - 304.788.3373 F - 304.788.3577
www.rkk.com
RK&K ENGINEERS
Professional Energy Consultants
SURVEYORS ENGINEERS ENVIRONMENTAL PROJECT MGMT.
www.SLSSURVEYS.com

THIS DOCUMENT WAS PREPARED BY: RK&K ENGINEERS FOR PUT PRODUCTION COMPANY

RIG FOOTPRINT & FLOWBACK PIT NO. 1
WEU4
McELROY DISTRICT
CENTERVILLE DISTRICT
TYLER COUNTY, WV

DATE: 04/29/2015
SCALE: 1" = 50'
DESIGNED BY: HWR
FILE NO: 208
SHEET 9 OF 33
REV: 08/25/2015

4709502280

WEU4 SITE PLAN
EQT PRODUCTION COMPANY

SITUATE ON THE WATERS OF CAMP MISTAKE RUN IN MCELROY AND CENTERVILLE DISTRICTS, TYLER COUNTY, WEST VIRGINIA

PROJECT INFORMATION

LOCATION COORDINATES

ENTRANCE PERMIT

MINE UTILITY STATEMENT

FLOODPLAIN NOTE

ENVIRONMENTAL NOTES

HORIZONTAL & VERTICAL CONTROL

West Virginia One Call System
811 or 1 800 245 4848
West Virginia State Law
(Section XIV Chapter 24 C)
Requires that you call two
business days before you dig in
the state of West Virginia
It's the Law

LIST OF DRAWINGS

OPERATOR

ENGINEER

SURVEYOR

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

RK ENGINEERS

Professional Energy Consultants

COVER SHEET
WEU4
McELROY DISTRICT
CENTERVILLE DISTRICT
TYLER COUNTY, WV

4709502280

ACCESS ROAD NO.1 PLAN

WEU4 PROPOSED WELLS

H1-WV 512890, H2-WV 512891, H3-WV 512892, H4-WV 512893, H5-WV 512894, H6-WV 512895

MATCH LINE SHEET 6

L B & Sandra Stoneking 42.66 Acres TM 21-29

Donna J. Peter 113.4 Acres TM 16-22

L B & Sandra Stoneking 83.44 Acres TM 21-28

ACCESS ROAD NO.1

Donna J. Peter 113.4 Acres TM 16-22

Edward A. Carolyn A. White 40 Acres TM 21-38

Notes:

1. ALL PROPOSED DRAINAGE DITCHES AND DRAIN PIPES SHALL BE ADEQUATE TO CARRY PROPER FLOW AS SHOWN ON THESE PLANS.

2. ALL DISTURBED AREAS SHALL BE SEEDED IN ACCORDANCE WITH A VEGETATIVE STABILIZATION PLAN TO MEET OR EXCEED THE STANDARD PROVIDED. MAXIMUM SLOPES SHALL NOT EXCEED 3:1.

3. ACCESS ROAD SURFACES TO BE PAVED WITH NO 4 STONE OR #8 OVER #4 OVER #2 CRUSHER RUN STONE.

4. IN AREA OF ACCESS ROAD NO.1 THAT RUNS PARALLEL TO SLOPE, ROADBED TO BE SLOPED AWAY FROM HILL TO AVOID ADJACENT PROPERTIES. A GEOLOGIST SHALL BE TO INVESTIGATE THE SITE TO DETERMINE IF SLOPES AS SHOWN IS STABLE OR STABLE. IF NOT ROAD WILL REQUIRE RETAINING WALL OR ADDITIONAL STABILIZATION METHODS SUGGESTED.

Professional Energy Consultants

SLS

RK ENGINEERS

ACCESS ROAD NO.1 PLAN

WEU4

MILL ROY DISTRICT
CENTERVILLE QUADRANGLE
TYLER COUNTY, WV

RECEIVED
Office of Oil & Gas
JUL 2 2
WV Department of
Environmental Protection

4709502280

ACCESS ROAD NO. 1 PLAN

WEU4 PROPOSED WELLS

H1-WV 512890, H2-WV 512891, H3-WV 512892, H4-WV 512893, H5-WV 512894, H6-WV 512895

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

4709502280

ACCESS ROAD NO. 1 CONCEPTUAL LAYOUT

WEU4 PROPOSED WELLS

H1-WV 512890, H2-WV 512891, H3-WV 512892, H4-WV 512893, H5-WV 512894, H6-WV 512895

RK ENGINEERS

Professional Energy Consultants

SLS

ACCESS ROAD NO. 1 PLAN

WEU4

NE, ROY DISTRICT
CENTERVILLE DISTRICT
TYLER COUNTY WV

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

ACCESS ROAD NO. 1 & ALTERNATE FLOWBACK PIT NO. 2 LAYOUT

WEU4 PROPOSED WELLS

H1-WV 512890, H2-WV 512891, H3-WV 512892, H4-WV 512893, H5-WV 512894, H6-WV 512895

4709502280



RK ENGINEERS

Professional Energy Consultants

ACCESS ROAD NO. 1
& ALTERNATE FLOWBACK PIT NO. 2
WEU4
WELSH DISTRICT
CENTERVILLE DISTRICT
TYLER COUNTY, WV

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

RIG FOOTPRINT & FLOWBACK PIT NO. 1 LAYOUT

WEU4PROPOSED WELLS

H1-WV 512890, H2-WV 512891, H3-WV 512892, H4-WV 512893, H5-WV 512894, H6-WV 512895

4709502280

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

4709502280

Note:
All fill areas will require a toe bench and will be "keyed in". Fill will be placed in 24" maximum loose lifts, maximum particle size of 6" compacted to 90% per standard proctor (ASTM D 698) with a vibrating sheepsfoot roller, and on a level surface. See toe bench detail.

ADD 9/30/15

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection


STORAGE SITES # 1 & #2
RECLAMATION PLAN
WELBOY DISTRICT
CENTERVILLE DISTRICT
TYLER COUNTY WV
WELBOY
WELBOY
WELBOY

4709502280

RECEIVED
Office of Oil and Gas
JUL 29 2015
WV Department of
Environmental Protection

4709502280

RECEIVED
Office of Oil and Gas
JUL 2 5
WV Department of
Environmental Protection